



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

MICHAEL F. EASLEY  
GOVERNOR

LYNDO TIPPETT  
SECRETARY

September 8, 2006

**Addendum No. 1**

RE: Contract ID: C201471  
WBS# 33188.3.2  
F. A. # BRZ-1400 (4)  
Gates County (B-3640)  
Bridge over Merchants Mill Pond  
And Approaches on SR-1400.

**September 19, 2006 Letting**

To Whom It May Concern:

Reference is made to the plans and proposal form recently furnished to you on this project.

The following revision has been made to the structure plans.

Sheet Nos. S-31, S-32 and S-33 have been revised to make changes to the fish ladder and to add details of a sluice gate platform. Please void Sheet Nos. S-31, S-32 and S-33 in your plans and staple the revised Sheet Nos. S-31, S-32, S-33 and new Sheet Nos. S-33A and S-33B thereto.

The following revision has been made to the proposal form:

On Page No. 65, the first paragraph of the project special provision entitled "Spillway Construction" has been revised. Please void Page No. 65 in your proposal and staple the revised Page No. 65 thereto.

Sincerely,

A handwritten signature in black ink, appearing to read "R. A. Garris".

R. A. Garris, PE  
Contract Officer

**Page No. 2 (C201471)**  
**Gates County.**

RAG/jag/pa

cc: Mr. W. S. Varnedoe, PE  
Mr. S. D. DeWitt, PE  
Mr. E. C. Powell, PE  
Mr. A. W. Roper, PE  
Ms. D. M. Barbour, PE  
Mr. Art McMillan, PE  
Mr. Victor Barbour, PE  
Mr. G. R. Perfetti, PE  
Mr. Mark Staley (2)  
Mr. Robert Memory  
Mr. R. E. Davenport, Jr., PE  
Ms. Norma Smith  
Ms. Marsha Byrd  
Mr. Ronnie Higgins  
Project File (2)

7. Stain shall be applied in two thin coats (minimum) providing a uniform appearance. The first coat must be allowed to become tack free before the second coat is applied. The final coat shall be consistent with the quality and appearance of the approved sample area. Note that care should be taken to provide a uniform appearance between the cored slab surface (precast concrete) and the curb and parapet surfaces (cast-in-place concrete). Additional coats of stain may be required to provide this uniform appearance.
8. Adequate protection shall be provided to protect adjacent persons, vehicles and property from concrete surface preparation activities and from overspray during staining operations.
9. Stain shall be applied to the concrete surfaces prior to the attachment of the two bar metal rail and wood hand railing to the bridge.

D. Basis of Payment

No separate measurement or payment will be made for preparing, furnishing, and applying of the concrete penetrating stain to the specified concrete surfaces.

Payment at the lump sum price for "construction of superstructure" will be full compensation for the above work including all materials, equipment, tools, labor, and incidentals necessary to complete the work.

**SPILLWAY CONSTRUCTION**

**(SPECIAL)**

**General:**

This work consists of constructing a new spillway, fish ladder and sluice gate platforms in accordance with applicable sections of the Standard Specifications for Roads and Bridges and additional special provisions incorporated with this package.

Referenced special provisions:

Fish Ladder  
Sluice Gate  
Epoxy Coating for Steel Members