

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	251,000 CY		
0006	0036000000-E	225	UNDERCUT EXCAVATION	100 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION (IV)	500 TON		
0008	0098000000-E	228	PRE-SPLITTING OF ROCK	33,000 SY		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	65 CY		
0010	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	6,700 SY		
0011	0192000000-N	260	PROOF ROLLING	3 HR		
0012	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0013	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0014	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	30 TON		
0015	0343000000-E	310	15" SIDE DRAIN PIPE	88 LF		
0016	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	84 LF		
0017	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	184 LF		
0018	0986000000-E	SP	GENERIC PIPE ITEM 1-1/2" SLOTTED PVC 2110 PIPE, TYPE II	400 LF		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0986000000-E	SP	GENERIC PIPE ITEM 1-1/2" UNSLOTTED PVC 2110 PIPE, TYPE II	100 LF		
0020	0986000000-E	SP	GENERIC PIPE ITEM HORIZONTAL DRAIN BOREHOLE	500 LF		
0021	0986000000-E	SP	GENERIC PIPE ITEM WEEP HOLES	4,200 LF		
0022	0995000000-E	340	PIPE REMOVAL	197 LF		
0023	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0024	1121000000-E	520	AGGREGATE BASE COURSE	9,400 TON		
0025	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
0026	1231000000-E	560	SHOULDER BORROW	2,002 CY		
0027	1275000000-E	600	PRIME COAT	4,305 GAL		
0028	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (12")	2,253 SY		
0029	1330000000-E	607	INCIDENTAL MILLING	200 SY		
0030	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	922 TON		
0031	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	2,150 TON		
0032	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	2,050 TON		
0033	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	142 TON		
0034	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	123 TON		
0035	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0036	2022000000-E	815	SUBDRAIN EXCAVATION	336 CY		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2033000000-E	815	SUBDRAIN FINE AGGREGATE	168 CY		
0038	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
0039	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30 EA		
0040	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0041	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0042	2253000000-E	840	PIPE COLLARS	1.105 CY		
0043	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0044	2354200000-N	840	FRAME WITH GRATE, STD 840.24	2 EA		
0045	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	6 EA		
0046	3030000000-E	862	STEEL BM GUARDRAIL	425 LF		
0047	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0048	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	2 EA		
0049	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	6 EA		
0050	3360000000-E	863	REMOVE EXISTING GUARDRAIL	2,200 LF		
0051	3628000000-E	876	PLAIN RIP RAP, CLASS I	50 TON		
0052	3642000000-E	876	PLAIN RIP RAP, CLASS A	500 TON		
0053	3649000000-E	876	PLAIN RIP RAP, CLASS B	94 TON		
0054	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	2,475 SY		
0055	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	232 SF		
0056	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	144 SF		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	4430000000-N	1130	DRUMS	36 EA		
0058	4446100000-E	SP	BARRICADES (TYPE III)	128 LF		
0059	4450000000-N	1150	FLAGGER	35 HR		
0060	4485000000-E	1170	PORTABLE CONCRETE BARRIER	2,663 LF		
0061	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	1,112.5 LF		
0062	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	150 EA		
0063	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	22,092 LF		
0064	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	16 LF		
0065	4847000000-E	SP	POLYUREA PAVEMENT MARKING LINES (4")	8,762 LF		
0066	4847140000-E	SP	POLYUREA PAVEMENT MARKING LINES (24")	16 LF		
0067	4847220000-N	SP	POLYUREA PAVEMENT MARKING SYMBOL	5 EA		
0068	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	6,000 LF		
0069	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	112 EA		
0070	6000000000-E	1605	TEMPORARY SILT FENCE	3,000 LF		
0071	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	17 TON		
0072	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	490 TON		
0073	6012000000-E	1610	SEDIMENT CONTROL STONE	50 TON		
0074	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0076	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.1 TON		
0077	6024000000-E	1622	TEMPORARY SLOPE DRAINS	600 LF		
0078	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	6 EA		
0079	6030000000-E	1630	SILT EXCAVATION	100 CY		
0080	6036000000-E	1631	MATTING FOR EROSION CONTROL	5,000 SY		
0081	6042000000-E	1632	1/4" HARDWARE CLOTH	50 LF		
0082	6084000000-E	1660	SEEDING & MULCHING	4.4 ACR		
0083	6108000000-E	1665	FERTILIZER TOPDRESSING	0.1 TON		

1522/Aug03/Q380573.205/D231585260000/E83

Total Amount Of Bid For Entire Project :

C201578 (R-2409B)
COUNTY: Jackson

2/16/99

Contract No: C201578
County: Jackson

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General