

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (10+34.50 -L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-M	226	SUPPLEMENTARY CLEARING & GRUB- BING	0.4 HA		
0006	0057000000-M	226	UNDERCUT EXCAVATION	500 M3		
0007	0080000000-M	SP	CLASS IV SUBGRADE STABILIZA- TION	450 MTN		
0008	0134000000-M	240	DRAINAGE DITCH EXCAVATION	100 M3		
0009	0195000000-M	265	SELECT GRANULAR MATERIAL	500 M3		
0010	0196000000-M	270	FABRIC FOR SOIL STABILIZATION	500 M2		
0011	0241000000-M	SP	GENERIC GRADING ITEM ROCK FILL FABRIC	500 M2		
0012	0318000000-M	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	35 MTN		
0013	0345000000-M	310	600MM SIDE DRAIN PIPE	12 M		
0014	0366000000-M	310	375MM RC PIPE CULVERTS, CLASS III	52.8 M		
0015	0708000000-M	310	400MM BIT COAT CS PIPE CUL- VERTS, TYPE B 1.63MM THICK	13.2 M		
0016	0720000000-M	310	600MM BIT COAT CS PIPE CUL- VERTS, TYPE B 1.63MM THICK	18 M		
0017	0806000000-M	310	400MM BIT COAT CS PIPE ELBOWS, TYPE B 1.63MM THICK	4 EA		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0808000000-M	310	600MM BIT COAT CS PIPE ELBOWS, TYPE B 1.63MM THICK	3 EA		
001E	0995000000-M	340	PIPE REMOVAL	9.4 M		
002C	1121000000-M	520	AGGREGATE BASE COURSE	770 MTN		
0021	1220000000-M	545	INCIDENTAL STONE BASE	240 MTN		
0022	1275000000-M	600	PRIME COAT	2,800 L		
002E	1489000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	128 MTN		
0024	1525000000-M	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	470 MTN		
002E	1560000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	33 MTN		
002E	2000000000-N	806	RIGHT OF WAY MARKERS	38 EA		
0027	2022000000-M	815	SUBDRAIN EXCAVATION	28 M3		
002E	2033000000-M	815	SUBDRAIN FINE AGGREGATE	21 M3		
002E	2044000000-M	815	150MM PERFORATED SUBDRAIN PIPE	50 M		
003C	2055000000-M	815	150MM SUBDRAIN PIPE WYES, TEES, & ELBOWS	5 EA		
0031	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0032	2077000000-M	815	150MM OUTLET PIPE (SUBDRAINS)	2 M		
003E	2154000000-N	820	METAL FUNNELS	1 EA		
0034	2165000000-M	820	300MM FUNNEL DRAIN PIPE	4.8 M		
003E	2176000000-M	820	300MM FUNNEL DRAIN PIPE ELBOWS	1 EA		
003E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	9 EA		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2308000000-M	840	MASONRY DRAINAGE STRUCTURES	0.3 M		
003E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	9 EA		
0039	2556000000-M	846	SHOULDER BERM GUTTER	130 M		
004C	2619000000-M	850	100MM CONCRETE PAVED DITCH	21 M2		
0041	3030000000-M	862	STEEL BM GUARDRAIL	205.74 M		
0042	3045000000-M	862	STEEL BM GUARDRAIL, SHOP CURVED	41.91 M		
0043	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0044	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (B-77, SHOP CURVED)	2 EA		
004E	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III, SHOP CURVED)	2 EA		
004E	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0047	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	7 EA		
004E	3635000000-M	876	PLAIN RIP RAP, CLASS II	200 MTN		
004E	3649000000-M	876	PLAIN RIP RAP, CLASS B	8 MTN		
005C	3656000000-M	876	FILTER FABRIC FOR DRAINAGE	709 M2		
0051	4412000000-M	SP	WORK ZONE SIGNS (STATIONARY)	44 M2		
0052	4412100000-M	SP	WORK ZONE SIGNS (PORTABLE)	22 M2		
0053	4412200000-M	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	9 M2		
0054	4425000000-N	1125	WARNING FLAG SETS	1 EA		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	4430000000-N	1130	DRUMS	100 EA		
005E	4435000000-N	1135	CONES	100 EA		
0057	4446100000-M	SP	BARRICADES (TYPE III)	35 M		
005E	4455000000-N	1150	FLAGGER	90 MD		
005E	4475000000-N	1165	TRUCK MOUNTED IMPACT ATTENUATOR (45 MPH)	1 EA		
006C	4507000000-M	SP	WATER FILLED BARRIER	105 M		
0061	4508000000-M	SP	RESET WATER FILLED BARRIER	105 M		
0062	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	22 EA		
006E	4685000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 2.3MM)	327 M		
0064	4686000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 3.1MM)	338 M		
006E	4710000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (600MM, 3.1MM)	16 M		
006E	4810000000-M	1205	PAINT PAVEMENT MARKING LINES (100MM)	4,154 M		
0067	4835000000-M	1205	PAINT PAVEMENT MARKING LINES (600MM)	13 M		
006E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	6 EA		
006E	6000000000-M	1605	TEMPORARY SILT FENCE	125 M		
007C	6006000000-M	1610	STONE FOR EROSION CONTROL, CLASS A	250 MTN		
0071	6009000000-M	1610	STONE FOR EROSION CONTROL, CLASS B	150 MTN		
0072	6012000000-M	1610	SEDIMENT CONTROL STONE	610 MTN		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6015000000-M	1615	TEMPORARY MULCHING	1 HA		
0074	6018000000-M	1620	SEED FOR TEMPORARY SEEDING	50 KG		
007E	6021000000-M	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 MTN		
007E	6029000000-M	SP	SAFETY FENCE	180 M		
0077	6030000000-M	1630	SILT EXCAVATION	215 M3		
007E	6036000000-M	1631	MATTING FOR EROSION CONTROL	240 M2		
007E	6042000000-M	1632	6.4MM HARDWARE CLOTH	410 M		
008C	6070000000-N	SP	SPECIAL STILLING BASINS	12 EA		
0081	6084000000-M	1660	SEEDING & MULCHING	1 HA		
0082	6087000000-M	1660	MOWING	0.5 HA		
0083	6090000000-M	1661	SEED FOR REPAIR SEEDING	25 KG		
0084	6093000000-M	1661	FERTILIZER FOR REPAIR SEEDING	0.25 MTN		
008E	6096000000-M	1662	SEED FOR SUPPLEMENTAL SEEDING	25 KG		
008E	6108000000-M	1665	FERTILIZER TOPDRESSING	1.25 MTN		
0087	6111000000-M	SP	IMPERVIOUS DIKE	43 M		
008E	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
008E	6123000000-M	1670	REFORESTATION	0.05 HA		
009C	6132000000-N	SP	GENERIC EROSION CONTROL ITEM RESPONSE FOR EROSION CONTROL	8 EA		
0091	7060000000-M	1705	SIGNAL CABLE	300 M		
0092	7120000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 3 SECTION)	4 EA		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	7264000000-M	1710	MESSENGER CABLE (9.52MM)	20	M	
0094	7300000000-M	1715	TRENCHING (UNPAVED)	275	M	
009E	7360000000-N	1720	WOOD POLE	4	EA	
0096	7372000000-N	1721	GUY ASSEMBLY	4	EA	
0097	7408000000-M	1722	25MM RISER WITH WEATHERHEAD	1	EA	
009E	7420000000-M	1722	50MM RISER WITH WEATHERHEAD	2	EA	
009E	7444000000-M	1725	INDUCTIVE LOOP SAWCUT	95	M	
010C	7456000000-M	1726	LEAD-IN CABLE	280	M	
0101	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	1	EA	
0102	7780000000-N	SP	DETECTOR CARD (TYPE 2070L)	1	EA	

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

0103	0378000000-M	310	600MM RC PIPE CULVERTS, CLASS III	25.2	M	
AA1						

*** OR ***

0104	0378000000-M	310	600MM RC PIPE CULVERTS, CLASS III	10.8	M	
AA2						

010E	0986000000-M	SP	GENERIC PIPE ITEM 600MM HDPE PIPE CULVERTS	14.4	M	
AA2						

*** OR ***

010E	0378000000-M	310	600MM RC PIPE CULVERTS, CLASS III	10.8	M	
AA3						

0107	0986000000-M	SP	GENERIC PIPE ITEM 600MM ALUMINIZED CS PIPE CULVERTS, 1.63MM THICK	14.4	M	
AA3						

***** END SCHEDULE AA *****

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
CULVERT ITEMS						
010E	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (10+49.900 -L2-)	Lump Sum	L.S.	
010G	8196000000-M	420	CLASS A CONCRETE (CULVERT)	35 M3		
011C	8804000000-N	SP	GENERIC CULVERT ITEM PRECAST REINF CONC THREE-SIDED CULVERT AT STA 10+49.900-L2-	Lump Sum	L.S.	
WALL ITEMS						
0111	8848000000-M	SP	GENERIC RETAINING WALL ITEM PILE/PANEL RETAINING WALL	93.9 M2		
STRUCTURE ITEMS						
0112	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (10+34.500 -L-)	Lump Sum	L.S.	
0113	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (10+34.500 -L-)	Lump Sum	L.S.	
0114	8096000000-M	SP	PILE EXCAVATION IN SOIL	10.6 M		
011E	8097000000-M	SP	PILE EXCAVATION NOT IN SOIL	2 M		
011F	8105540000-M	SP	1066MM DIA DRILLED PIERS IN SOIL	12.4 M		
0117	8105640000-M	SP	1066MM DIA DRILLED PIERS NOT IN SOIL	6 M		
011E	8113000000-N	SP	SID INSPECTION	1 EA		
0119	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
012C	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (10+34.500 -L-)	Lump Sum	L.S.	
0121	8147000000-M	420	REINFORCED CONCRETE DECK SLAB	416.6 M2		
0122	8161000000-M	420	GROOVING BRIDGE FLOORS	383.3 M2		
0123	8182000000-M	420	CLASS A CONCRETE (BRIDGE)	63.3 M3		
0124	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (10+34.500 -L-)	Lump Sum	L.S.	
012E	8217000000-M	425	REINFORCING STEEL (BRIDGE)	10,123 KG		
012E	8238000000-M	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	600 KG		
0127	8280000000-M	440	APPROX KG STRUCTURAL STEEL	66,400 LS		
012E	8364000000-M	450	HP310X79 STEEL PILES	12.6 M		
012E	8503000000-M	460	CONCRETE BARRIER RAIL	78.73 M		
013C	8608000000-M	876	PLAIN RIP RAP CLASS II (600MM THICK)	255 MTN		
0131	8622000000-M	876	FILTER FABRIC FOR DRAINAGE	284 M2		
0132	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0133	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1112/Dec05/Q96331.88/D603171080000/E133

Total Amount Of Bid For Entire Project :

C201222 (B-3119)
COUNTY: BUNCOMBE

2/16/99

Contract No: C201222
County: Buncombe

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General