

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	20 CY		
0005	0141000000-E	240	BERM DITCH CONSTRUCTION	700 LF		
0006	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	181 TON		
0007	0343000000-E	310	15" SIDE DRAIN PIPE	16 LF		
0008	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	108 LF		
0009	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	3 EA		
001C	0995000000-E	340	PIPE REMOVAL	620 LF		
0011	1077000000-E	SP	#57 STONE	10 TON		
0012	1220000000-E	545	INCIDENTAL STONE BASE	60 TON		
0013	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	3,560 TON		
0014	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1,620 TON		
0015	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	3,850 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	230 TON		
0017	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	231 TON		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	4 TON		
001E	2253000000-E	840	PIPE COLLARS	2 CY		
002C	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	51 EA		
0021	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	48 LF		
0022	2352000000-N	840	FRAME WITH GRATE, STD 840.**** (840.16)	9 EA		
0023	2355000000-N	840	FRAME WITH GRATE, STD 840.29 (840.29)	2 EA		
0024	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1 EA		
002E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	20 EA		
002E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	7 EA		
0027	2396000000-N	840	FRAME WITH COVER, STD 840.54	10 EA		
002E	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	2 EA		
002E	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	4,225 LF		
003C	2556000000-E	846	SHOULDER BERM GUTTER	655 LF		
0031	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	535 LF		
0032	2591000000-E	848	4" CONCRETE SIDEWALK	2,390 SY		
003E	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	20 EA		
0034	2619000000-E	850	4" CONCRETE PAVED DITCH	90 SY		
003E	2627000000-E	852	4" CONCRETE ISLAND COVERS	440 SY		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	950 SY		
0037	2710000000-N	854	CONCRETE BARRIER TRANSITION SECTION	2 EA		
003E	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	240 LF		
003E	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	2 EA		
004C	3030000000-E	862	STEEL BM GUARDRAIL	650 LF		
0041	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0042	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		
004E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1 EA		
0044	3360000000-E	863	REMOVE EXISTING GUARDRAIL	700 LF		
004E	3649000000-E	876	RIP RAP, CLASS B	4 TON		
004E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	14 SY		
0047	3982000000-N	SP	GENERIC WALL ITEM SOIL NAIL RETAINING WALLS	Lump Sum	L.S.	
004E	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (D)	22 SF		
004E	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	138 SF		
005C	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (F)	138 SF		
0051	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	610 LF		
0052	4096000000-N	904	SIGN ERECTION, TYPE D	1 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	4102000000-N	904	SIGN ERECTION, TYPE E	22 EA		
0054	4108000000-N	904	SIGN ERECTION, TYPE F	6 EA		
0055	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	3 EA		
0056	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	2 EA		
0057	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	24 EA		
0058	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	7 EA		
0059	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	394 SF		
0060	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	372 SF		
0061	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	70 SF		
0062	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	3 EA		
0063	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	4 EA		
0064	4430000000-N	1130	DRUMS	200 EA		
0065	4435000000-N	1135	CONES	100 EA		
0066	4445000000-E	1145	BARRICADES (TYPE III)	128 LF		
0067	4450000000-N	1150	FLAGGER	3,000 HR		
0068	4480000000-N	1165	TMIA	3 EA		
0069	4510000000-N	SP	POLICE	200 HR		
0070	4516000000-N	1180	SKINNY DRUM	100 EA		
0071	4520000000-N	1266	TUBULAR MARKERS (FIXED)	80 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,582 LF		
0073	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	9,747 LF		
0074	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	430 LF		
0075	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,500 LF		
0076	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	24 EA		
0077	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	71 EA		
007E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	14,894 LF		
007F	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	1,200 LF		
008C	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,148 LF		
0081	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	12 EA		
0082	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	82 EA		
0083	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	40 LF		
0084	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	155 LF		
008E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	155 EA		
008F	5045000000-N	1404	LIGHT STANDARD, TYPE MTL5 ***** (35', SA 15')	4 EA		
0087	5070000000-N	1405	STANDARD FOUNDATION ***** (TYPE R1)	4 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	5080000000-N	1406	LIGHT STANDARD LUMINAIRES, TYPE ***** (TYPE RDW, 250W HPS)	4 EA		
008E	5125000000-E	1407	ELECTRIC SERVICE LATERAL ***** (3 #1/0, USE)	70 LF		
009C	5145000000-N	1408	LIGHT CONTROL EQUIPMENT, TYPE RW ***** (240/480 VOLT)	1 EA		
0091	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (3")	30 LF		
0092	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (3")	126 LF		
0093	5205000000-E	1410	** #8 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	757 LF		
0094	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC 18)	2 EA		
009E	5252000000-N	1412	UNDERPASS LUMINARIES ***** (WM 150W)	6 EA		
009E	5253000000-N	1412	UNDERPASS CIRCUITRY AT ***** (WAKE FOREST RD/I-440)	Lump Sum	L.S.	
0097	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
009E	5540000000-E	1515	6" VALVE	1 EA		
009E	5815000000-N	1530	REMOVE WATER METER	2 EA		
010C	5815500000-N	1530	REMOVE FIRE HYDRANT	1 EA		
0101	5882000000-N	SP	GENERIC UTILITY ITEM ADJUST EXISTING 10" RPZ BACKFLOW PREVENTER	1 EA		
0102	5882000000-N	SP	GENERIC UTILITY ITEM FIRE HYDRANT, 150# WP	1 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0103	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE EXISTING 4" WATER METER WITH NEW METER VAULT	2 EA		
0104	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE EXISTING WATER METER WITH NEW METER BOX	2 EA		
010E	5882000000-N	SP	GENERIC UTILITY ITEM REMOVE EXISTING CHECK VALVE VAULT	1 EA		
010E	5888000000-E	SP	GENERIC UTILITY ITEM 1" COPPER WATER PIPE, TYPE K	65 LF		
0107	5888000000-E	SP	GENERIC UTILITY ITEM 10" DI WATER PIPE, PC 350	10 LF		
010E	5888000000-E	SP	GENERIC UTILITY ITEM 2" COPPER WATER PIPE, TYPE K	28 LF		
010E	5888000000-E	SP	GENERIC UTILITY ITEM 4" DI WATER PIPE, PC 350	10 LF		
011C	5888000000-E	SP	GENERIC UTILITY ITEM 6" DI WATER PIPE, PC 350	25 LF		
0111	5906000000-E	SP	GENERIC UTILITY ITEM DUCTILE IRON WATER PIPE FITTINGS, 250PSI MIN WP	600 LB		
0112	6000000000-E	1605	TEMPORARY SILT FENCE	400 LF		
0113	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	15 TON		
0114	6012000000-E	1610	SEDIMENT CONTROL STONE	10 TON		
011E	6030000000-E	1630	SILT EXCAVATION	50 CY		
011E	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
0117	7000000000-E	1705	PEDESTRIAN SIGNAL HEAD (**, ** SECTION) (16", 1 SECTION W/COUNTDOWN)	6 EA		
011E	7060000000-E	1705	SIGNAL CABLE	8,080 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0119	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	37 EA		
0120	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	8 EA		
0121	7252000000-E	1710	MESSENGER CABLE (1/4")	200 LF		
0122	7264000000-E	1710	MESSENGER CABLE (3/8")	1,900 LF		
0123	7288000000-E	1715	PAVED TRENCHING (***** (1, 2"))	75 LF		
0124	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2"))	715 LF		
0125	7301000000-E	1715	DIRECTIONAL DRILL (***** (1, 2"))	600 LF		
0126	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	8 EA		
0127	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEAVY DUTY)	1 EA		
0128	7360000000-N	1720	WOOD POLE	10 EA		
0129	7372000000-N	1721	GUY ASSEMBLY	29 EA		
0130	7396000000-E	1722	1/2" RISER WITH WEATHERHEAD	3 EA		
0131	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0132	7420000000-E	1722	2" RISER WITH WEATHERHEAD	14 EA		
0133	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	5,900 LF		
0134	7456000000-E	1726	LEAD-IN CABLE (***** (18-4))	6,215 LF		
0135	7504000000-E	SP	COMMUNICATIONS CABLE (** TWISTED-PAIR) (25)	620 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0136	7504000000-E	SP	COMMUNICATIONS CABLE (** TWISTED-PAIR) (6)	620	LF	
0137	7575160000-E	1734	REMOVE EXISTING COMMUNICATIONS CABLE	450	LF	
013E	7575180000-N	1735	CABLE TRANSFER	5	EA	
013E	7624000000-N	1743	SIGNAL PEDESTAL WITH FOUNDATION	1	EA	
014C	7636000000-N	1745	SIGN FOR SIGNALS	18	EA	
0141	7648000000-N	SP	RELOCATE EXISTING SIGN	9	EA	
0142	7684000000-N	1750	SIGNAL CABINET FOUNDATION	2	EA	
0143	7828000000-N	1751	CONTROLLER WITH CABINET (NEMA TS-2, TYPE 2 CONTROLLER, TYPE 1 CABINET, BASE MOUNTED)	2	EA	
0144	7852000000-N	1751	DETECTOR CARD (NEMA TS-2)	13	EA	
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
014E	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	684	LF	
AA1						
014E	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	344	LF	
AA1						
0147	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	548	LF	
AA1						
*** OR ***						
014E	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	344	LF	
AA2						
014E	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	56	LF	
AA2						
015C	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	48	LF	
AA2						

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0151 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	340 LF		
0152 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	288 LF		
0153 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	500 LF		
*** OR ***						
0154 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	344 LF		
0155 AA3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	56 LF		
0156 AA3	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	48 LF		
0157 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (15", 0.064")	340 LF		
0158 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (18", 0.064")	288 LF		
0159 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (24", 0.064")	500 LF		
***** END SCHEDULE AA *****						
1130/Dec12/Q92462.0/D705601640000/E159			Total Amount Of Bid For Entire Project :			

Contract No: C 201454

County: Wake

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General