



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

MICHAEL F. EASLEY  
GOVERNOR

LYNDO TIPPETT  
SECRETARY

February 13, 2007

**Addendum No. 1**

RE: Contract ID: C201180  
WBS# 32597.3.2, 32728.3.2  
F. A. # BRSTP-197 (1), BRZ-1304 (9)  
Mitchell-Yancey Counties (**B-1443, B-2848**)  
Bridges over North Toe River and Approaches on NC-197  
And on SR-1304 South of Red Hill at the County Line.

**February 20, 2007 Letting**

To Whom It May Concern:

Reference is made to the plans and proposal form recently furnished to you on this project.

The following revisions have been made to the Roadway Plans:

Sheet No. 3 has been revised to reflect the changes noted below. Please void Sheet No. 3 in your plans and staple the revised Sheet No. 3 thereto.

Plan Sheet No. TCP-4 has been revised to change the reference for Temporary Soil Nail Wall to Temporary Shoring-Contractor Designed. Please void Sheet No. TCP-4 in your plans and staple the revised Sheet No. TCP-4 thereto.

The following revisions have been made to the Structure Plans:

On Sheet No. S-3, a note was added concerning access to the causeway. On Sheet No. S-4 the location of the temporary access road was revised. Please void Sheet No. S-3 and S-4 in your plans and staple the revised Sheet Nos. S-3 and S-4 thereto.

The following revisions have been made to the proposal form:

On Page No. 43, the Project Special Provision entitled "Temporary Shoring For Maintenance of Traffic" has been revised. Please void Page No. 43 and staple the revised Page No. 43 thereto.

**MAILING ADDRESS:**  
NC DEPARTMENT OF TRANSPORTATION  
DESIGN SERVICES UNIT  
1591 MAIL SERVICE CENTER  
RALEIGH NC 27699-1591

TELEPHONE: 919-250-4128  
FAX: 919-250-4119

WEBSITE: [WWW.DOH.DOT.STATE.NC.US](http://WWW.DOH.DOT.STATE.NC.US)

**LOCATION:**  
CENTURY CENTER COMPLEX  
ENTRANCE B2  
1020 BIRCH RIDGE DRIVE  
RALEIGH NC

**Page No. 2 (C201180)**  
**Mitchell-Yancey Counties**

Page No. 44 thru 68 are hereby deleted. The Table of Contents has been revised to reflect this deletion. Please void the Table of Contents in your proposal and staple the revised Table of Contents thereto.

On Page No. 1 of the item sheets, line item “2-0000400000-N-801 Construction Surveying” is hereby deleted. On Page No. 3 of the item sheets line item “46-2529000000-E-SP Temporary Soil Nail Wall” is hereby deleted. The Contractor’s bid shall not include these two pay items. The Contract will be prepared accordingly.

On Page No. 7 of the new item sheets, the following new pay items is hereby added: “160-2529000000-E-SP Temporary Shoring, Contractor Designed” (Quantity=1,550 SF). The Contractor’s bid shall include this new pay item. The Contract will be prepared accordingly.

The Expedite file has been updated to reflect these revisions. Please download the Expedite addendum file and follow the instructions for applying the addendum. Bid Express will not accept your bid unless the addendum has been applied.

Sincerely,



R. A. Garris, PE  
Contract Officer

RAG/jag/pa  
Attachment

cc: Mr. W. S. Varnedoe, PE  
Mr. E. C. Powell, PE  
Mr. J. J. Swain, PE  
Ms. D. M. Barbour, PE  
Mr. Art McMillan, PE  
Mr. G. R. Perfetti, PE  
Mr. Victor Barbour, PE  
Mr. Mark Staley (2)  
Mr. Robert Memory  
Mr. R. E. Davenport, Jr., PE  
Ms. Norma Smith  
Ms. Marsha Byrd  
Mr. Ronnie Higgins  
Ms. Taylor Mishoe  
Project File (2)

*Temporary Shoring – Contractor Designed* (11+65 -Y- to 13+35 -Y-) will be measured and paid for as the actual number of square feet of exposed face of the shoring measured from the bottom of the excavation or embankment to the top of the shoring, with the upper limit for pay purposes not to exceed 1 foot above the retained ground elevation. Payment for temporary shoring will be made only at locations where it is required in order to maintain traffic.

Such payment will include, but not limited to boring, furnishing all labor, tools, equipment, and all incidentals necessary to install shoring and complete the work. Trench boxes are not considered temporary shoring for the maintenance of traffic and will not be paid for under this special provision.

Payment will be made under:

<b>Pay Item</b>	<b>Pay Unit</b>
Temporary Shoring	Square Feet
Temporary Shoring - Barrier Supported	Square Feet
Temporary Shoring – Contractor Designed	Square Feet

**CHANGEABLE MESSAGE SIGNS**

(11-21-06)

SP11 R11

Revise the *2006 Standard Specifications* as follows:

Page 11-9, Article 1120-3, Replace the 3rd sentence with the following:

Sign operator will adjust flash rate so that no more than two messages will be displayed and be legible to a driver when approaching the sign at the posted speed.

**PAVEMENT MARKING LINES MEASUREMENT AND PAYMENT:**

(11-21-06)

SP 12 R01

Revise the *2006 Standard Specifications* as follows:

Page 12-14, Subarticle 1205-10, delete the first sentence of the first paragraph and replace with the following:

*Pavement Marking Lines* will be measured and paid for as the actual number of linear feet of pavement marking lines per application that has been satisfactorily placed and accepted by the Engineer.

**TABLE OF CONTENTS**

**COVER SHEET  
PROPOSAL SHEETS**

<b><u>PROJECT SPECIAL PROVISIONS</u></b> (WHITE SHEETS)	<i>PAGE No.</i>
Contract Time and Liquidated Damages.....	1
Intermediate Contract Time(s).....	1-2
Pre-Bid Conference.....	3
Metric / English Conversions.....	3
Comprehensive Grading.....	3
Major Contract Items.....	3
Specialty Items.....	4
Fuel Price Adjustment.....	4-5
Schedule of Estimated Completion Progress.....	5
Disadvantaged Business Enterprises.....	5-15
Certification for Federal-Aid Contracts.....	15
Contractor Licenses Requirements.....	16
U. S. Department of Transportation Hotline.....	16
Submission of Records – Federal-Aid Projects .....	16
Subsurface Information.....	16
Twelve Month Guarantee.....	17
Outsourcing Outside U.S.A.....	17
Act of God.....	18
Erosion & Sediment Control / Storm Water Certification.....	18-23
Roadway.....	24-43
(DELETED) .....	44-68
Utility Conflicts.....	69
Erosion Control.....	70-82
Signals and Intelligent Transportation Systems.....	83-96
Railroad Insurance (Roadway).....	97-99
Project Special Provisions Structure .....	100-170

**PERMITS** (PINK SHEETS)..... 171-273

**STANDARD SPECIAL PROVISIONS** (YELLOW SHEETS)

Availability of Funds – Termination of Contracts.....	1
General Seed Specification for Seed Quality.....	2-4
Errata.....	5-7
Plant and Pest Quarantines.....	8
Award of Contract.....	9
Minority and Female Employment Requirements.....	10-12
Required Contract Provisions Federal-Aid Construction Contracts.....	13-22
Wage Rates.....	23-26

**PROPOSAL ITEM SHEET AND SIGNATURE SHEET**

- Item Sheets
- Signature Sheet (Bid Acceptance by Department)