

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION	3,800 CY		
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (15 + 25.00)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	20 CY		
0007	0234000000-E	SP	GENERIC GRADING ITEM SELECT MATERIAL, CLASS III	375 CY		
0008	0241000000-E	SP	GENERIC GRADING ITEM FABRIC FOR REINFORCED SLOPE	1,000 SY		
0009	0255000000-E	SP	GENERIC GRADING ITEM PLAIN RIP RAP, CLASS II	150 TON		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	120 TON		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	28 LF		
0012	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	40 LF		
0013	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	60 LF		
0014	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	24 LF		
0015	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0016	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	2 EA		
0017	0995000000-E	340	PIPE REMOVAL	24 LF		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1121000000-E	520	AGGREGATE BASE COURSE	180 TON		
001E	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
002C	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	270 TON		
0021	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	320 TON		
0022	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	275 TON		
0023	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	45 TON		
0024	2000000000-N	806	RIGHT OF WAY MARKERS	14 EA		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	9 EA		
002E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2 EA		
0027	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
002E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1 EA		
002E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	3 EA		
003C	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0031	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	345 LF		
0032	2556000000-E	846	SHOULDER BERM GUTTER	70 LF		
003E	2612000000-E	848	6" CONCRETE DRIVEWAY	10 SY		
0034	3030000000-E	862	STEEL BM GUARDRAIL	237.5 LF		
003E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	
0037	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4	EA	
0038	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	220	LF	
0039	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	14	EA	
0040	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	3	EA	
0041	3649000000-E	876	RIP RAP, CLASS B	5	TON	
0042	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	20	SY	
0043	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1	EA	
0044	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	274	SF	
0045	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	70	SF	
0046	4445000000-E	1145	BARRICADES (TYPE III)	56	LF	
0047	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	5,000	LF	
0048	5325600000-E	1510	6" WATER LINE	709	LF	
0049	5326600000-E	1510	16" WATER LINE	459	LF	
0050	5540000000-E	1515	6" VALVE	1	EA	
0051	5558600000-E	1515	16" VALVE	2	EA	
0052	5672000000-N	1515	RELOCATE FIRE HYDRANT	1	EA	
0053	5802000000-E	1530	ABANDON 10" UTILITY PIPE	229	LF	

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	5810000000-E	1530	ABANDON 16" UTILITY PIPE	453 LF		
0055	5816000000-N	1530	ABANDON UTILITY MANHOLE	2 EA		
0056	5871400000-E	1550	TRENCHLESS INSTALLATION OF 6" IN SOIL	198 LF		
0057	5871410000-E	1550	TRENCHLESS INSTALLATION OF 6" NOT IN SOIL	198 LF		
0058	5871900000-E	1550	TRENCHLESS INSTALLATION OF 16" IN SOIL	151 LF		
0059	5871910000-E	1550	TRENCHLESS INSTALLATION OF 16" NOT IN SOIL	152 LF		
0060	6000000000-E	1605	TEMPORARY SILT FENCE	710 LF		
0061	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0062	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	125 TON		
0063	6012000000-E	1610	SEDIMENT CONTROL STONE	350 TON		
0064	6015000000-E	1615	TEMPORARY MULCHING	4 ACR		
0065	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0066	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.75 TON		
0067	6029000000-E	SP	SAFETY FENCE	200 LF		
0068	6030000000-E	1630	SILT EXCAVATION	305 CY		
0069	6036000000-E	1631	MATTING FOR EROSION CONTROL	355 SY		
0070	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	125 SY		
0071	6042000000-E	1632	1/4" HARDWARE CLOTH	160 LF		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	6070000000-N	SP	SPECIAL STILLING BASINS	12	EA	
0073	6071030000-E	SP	COIR FIBER BAFFLES	125	LF	
0074	6084000000-E	1660	SEEDING & MULCHING	2.5	ACR	
007E	6087000000-E	1660	MOWING	2.5	ACR	
007E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0077	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
007E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100	LB	
007E	6108000000-E	1665	FERTILIZER TOPDRESSING	3	TON	
008C	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
0081	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8	EA	

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

0082	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	504	LF	
AA1						

*** OR ***

0083	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	392	LF	
AA2						

0084	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	112	LF	
AA2						

*** OR ***

0085	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	392	LF	
AA3						

008E	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (15", 0.064")	112	LF	
AA3						

***** END SCHEDULE AA *****

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0087	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15 + 25.00 -L-)	Lump Sum	L.S.	
008E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (15 + 25.00 -L-)	Lump Sum	L.S.	
008E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	42 CY		
009C	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15 + 25.00 -L-)	Lump Sum	L.S.	
0091	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,716 LB		
0092	8384000000-E	450	HP14X73 STEEL PILES	450 LF		
009E	8503000000-E	460	CONCRETE BARRIER RAIL	205.48 LF		
0094	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	120 TON		
009E	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	133 SY		
009E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0097	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	1,438.35 LF		
<p>1112/Jan10/Q29350.33/D386696750000/E97 Total Amount Of Bid For Entire Project :</p>						

Contract No: C 200807

County: Burke

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General