

County : Franklin

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|---|-------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0248000000-N | SP | GENERIC GRADING ITEM EXCAVATION & EMBANKMENT | Lump Sum | L.S. | |
| 0003 | 0318000000-E | 300 | FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS | 9 TON | | |
| 0004 | 0582000000-E | 310 | 15" CS PIPE CULVERTS, 0.064" THICK | 84 LF | | |
| 0005 | 0636000000-E | 310 | *** CS PIPE ELBOWS, ***** THICK (15", 0.064") | 8 EA | | |
| 0006 | 1489000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 170 TON | | |
| 0007 | 1519000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE S9.5B | 765 TON | | |
| 0008 | 2000000000-N | 806 | RIGHT OF WAY MARKERS | 4 EA | | |
| 0009 | 2286000000-N | 840 | MASONRY DRAINAGE STRUCTURES | 4 EA | | |
| 0010 | 2367000000-N | 840 | FRAME WITH TWO GRATES, STD 840.29 | 4 EA | | |
| 0011 | 2556000000-E | 846 | SHOULDER BERM GUTTER | 110 LF | | |
| 0012 | 3422000000-N | SP | GENERIC GUARDRAIL ITEM STEEL BM GUARDRAIL | Lump Sum | L.S. | |
| 0013 | 3635000000-E | 876 | RIP RAP, CLASS II | 529 TON | | |
| 0014 | 3649000000-E | 876 | RIP RAP, CLASS B | 4 TON | | |
| 0015 | 3656000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 575 SY | | |
| 0016 | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 1,980 LF | | |
| 0017 | 6133000000-N | SP | GENERIC EROSION CONTROL ITEM EROSION CONTROL | Lump Sum | L.S. | |

County : Franklin

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|-------------|-----------|--------|
| 0018 | 8017000000-N | SP | CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (13+45.42) | Lump Sum | L.S. | |
| 0019 | 8035000000-N | 402 | REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+45.42) | Lump Sum | L.S. | |
| 0020 | 8035000000-N | 402 | REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+35.39) | Lump Sum | L.S. | |
| 0021 | 8105500000-E | SP | ***-*** DIA DRILLED PIERS IN SOIL (4'-6") | 210.8 LF | | |
| 0022 | 8105540000-E | SP | 3'-6" DIA DRILLED PIERS IN SOIL | 42.3 LF | | |
| 0023 | 8105600000-E | SP | ***-*** DIA DRILLED PIERS NOT IN SOIL (4'-6") | 26 LF | | |
| 0024 | 8105640000-E | SP | 3'-6" DIA DRILLED PIERS NOT IN SOIL | 27 LF | | |
| 0025 | 8111000000-E | SP | PERMANENT STEEL CASING FOR ***-*** DIA DRILLED PIER (4'-6") | 181.6 LF | | |
| 0026 | 8111400000-E | SP | PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER | 21 LF | | |
| 0027 | 8121000000-N | 412 | UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (13+45.42) | Lump Sum | L.S. | |
| 0028 | 8210000000-N | 422 | BRIDGE APPROACH SLABS, STATION ***** (13+45.42) | Lump Sum | L.S. | |
| 0029 | 8364000000-E | 450 | HP12X53 STEEL PILES | 1,075 LF | | |
| 0030 | 8765000000-N | SP | CONSTRUCTION OF SUBSTRUCTURE (13+45.42) | Lump Sum | L.S. | |
| 0031 | 8765000000-N | SP | CONSTRUCTION OF SUBSTRUCTURE (16+35.39) | Lump Sum | L.S. | |
| 0032 | 8766000000-N | SP | CONSTRUCTION OF SUPERSTRUCTURE (13+45.42) | Lump Sum | L.S. | |

County : Franklin

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|----------|-----------|--------|
| 0033 | 8766000000-N | SP | CONSTRUCTION OF SUPERSTRUCTURE (16+35.39) | Lump Sum | L.S. | |

1531/Jan18/Q5842.7/D172984780000/E33

Total Amount Of Bid For Entire Project :

C201716
COUNTY: FRANKLIN

2/16/99

Contract No: C201716
County: Franklin

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General