

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	1,375 TON		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	23.75 SMI		
0004	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 3")	21,000 SY		
0005	1330000000-E	607	INCIDENTAL MILLING	1,370 SY		
0006	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,574 TON		
0007	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	38,211 TON		
0008	1520000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE)	4,673 TON		
0009	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	2,649 TON		
001C	1704000000-E	SP	PATCHING EXISTING PAVEMENT	4,037 TON		
0011	2830000000-N	858	ADJUSTMENT OF MANHOLES	30 EA		
0012	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	24 EA		
0013	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	98,140 LF		
0014	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	94,373 LF		
0015	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	550 LF		
0016	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	12 EA		
0017	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	201 EA		

County : Iredell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	458,715 LF		
001S	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	250 EA		
002C	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,375 EA		
0021	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
1139/Jan03/Q728584.75/D61967100000/E21			Total Amount Of Bid For Entire Project :			

Contract No: C 201720

County: Iredell

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General