

TIP#
Date:
Revised Date:

POLICE

DESCRIPTION.

Furnish Police Officers and marked Police Vehicles to direct traffic in accordance with the plans and specifications.

CONSTRUCTION METHODS.

Utilize Police Officers who are outfitted with police uniforms.

Utilize marked Police Vehicles, which are equipped with police lights mounted on top of the vehicle, and police vehicle emblems.

Utilize Police Officers and marked Police Vehicles to direct or control traffic as required by the plans or by the Engineer.

METHOD OF MEASUREMENT.

The quantity of Police Officers and marked Police Vehicles to be paid for will be the actual number of hours that each Police Officer/marked Police Vehicle is provided during the life of the project as approved by the Engineer.

There will be no direct payment for marked Police Vehicles as they are considered incidental to the pay item in this special provision.

BASIS OF PAYMENT.

The quantity of Police Officers and marked Police Vehicles measured as provided above, will be paid for at the contract unit price per hour for "Police".

Payment will be made under:

Police.....Hour

NORTH CAROLINA MOVING AHEAD SIGNS:

(7-18-06)

RWZ-6

Description

The Department will furnish the Contractor with the North Carolina Moving Ahead (NCMA) logo signs. The Contractor shall procure these signs from either the local Traffic Services office or directly from the Bunn Sign Plant. NCMA signs shall be installed as shown elsewhere in the contract and shall be left in place at the completion of the project. The NCMA signs and supports shall remain the property of NCDOT and will be removed by Division forces.

The Contractor shall have a sign fabricated with the name of his company, which will be mounted under the NCMA logo sign. The Contractor shall remove and keep the signs with the name of his company after final project acceptance, leaving the supports and NCMA logo signs in place.

The Contractor shall furnish all material, labor, hardware and supports necessary to erect the NCMA logo and Prime Contractor's name signs. There will only be one set of NCMA logo and Prime Contractor name signs in each direction on the mainline unless the Department identifies extenuating circumstances. These signs shall be erected prior to any work beginning on the project and shall not be installed more than three days prior to the beginning of work. After construction begins, the Contractor shall cover the NCMA signs if inactivity on the project site occurs for at least 7 days. All other required standard work zone signs shall be provided as described in Section 1110 of the *Standard Specifications* and elsewhere in the contract.

Materials

The materials for the Contractor's Company name sign and standard work zone signing shall meet the requirements of Article 1110 of the *Standard Specifications*.

The sign sheeting for the Contractor's Name Sign shall be black on orange Type I (Engineer's Grade) with 4 inch C Copy lettering. When the name of the Contractor with 4 inch C Copy lettering exceeds the maximum 60 inch width of the sign, the size of the letters shall be reduced to meet this maximum 60 inch width requirement.

Construction Methods

Construction of signs shall conform to the requirements of Article 1110-3 of the *Standard Specifications*.

Maintenance

Maintenance of the signs shall conform to the requirements of Article 1105-4 of the *Standard Specifications*. Maintenance for the NCMA signs will end upon final acceptance of the project.

Measurement and Payment

There will be no measurement and payment for the NCMA signs or the Contractor's Company name signs. All material, hardware, supports, and labor necessary shall be incidental to other items in the contract.