

County : Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	3 ACR		
0004	0022000000-E	225	UNCLASSIFIED EXCAVATION	64,500 CY		
0005	0036000000-E	225	UNDERCUT EXCAVATION	5,000 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	500 TON		
0007	0106000000-E	230	BORROW EXCAVATION	29,000 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	4,000 CY		
0009	0141000000-E	240	BERM DITCH CONSTRUCTION	550 LF		
0010	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	950 SY		
0011	0195000000-E	265	SELECT GRANULAR MATERIAL	2,000 CY		
0012	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	2,000 SY		
0013	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	1,000 TON		
0014	0343000000-E	310	15" SIDE DRAIN PIPE	1,232 LF		
0015	0344000000-E	310	18" SIDE DRAIN PIPE	576 LF		
0016	0345000000-E	310	24" SIDE DRAIN PIPE	32 LF		
0017	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	64 LF		
0018	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	228 LF		
0019	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	88 LF		

County : Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	0408000000-E	310	54" RC PIPE CULVERTS, CLASS III	104 LF		
0021	0414000000-E	310	60" RC PIPE CULVERTS, CLASS III	100 LF		
0022	0536000000-E	SP	**** HDPE PIPE CULVERTS (12")	30 LF		
0023	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	1,080 LF		
0024	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	296 LF		
0025	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	58 EA		
0026	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	6 EA		
0027	0973100000-E	330	*** WELDED STEEL PIPE IN SOIL (18")	148 LF		
0028	0973100000-E	330	*** WELDED STEEL PIPE IN SOIL (24")	161 LF		
0029	0973100000-E	330	*** WELDED STEEL PIPE IN SOIL (30")	100 LF		
0030	0995000000-E	340	PIPE REMOVAL	2,821 LF		
0031	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0032	1022000000-E	SP	SEALING EXISTING PAVEMENT CRACKS	4,500 LB		
0033	1077000000-E	SP	#57 STONE	20 TON		
0034	1110000000-E	510	STABILIZER AGGREGATE	450 TON		
0035	1121000000-E	520	AGGREGATE BASE COURSE	700 TON		
0036	1220000000-E	545	INCIDENTAL STONE BASE	1,000 TON		

County : Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2")	1,500 SY		
0038	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	62,000 SY		
0039	1330000000-E	607	INCIDENTAL MILLING	1,000 SY		
0040	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	11,000 TON		
0041	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	22,000 TON		
0042	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	22,000 TON		
0043	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	2,830 TON		
0044	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	250 TON		
0045	2000000000-N	806	RIGHT OF WAY MARKERS	117 EA		
0046	2022000000-E	815	SUBDRAIN EXCAVATION	450 CY		
0047	2033000000-E	815	SUBDRAIN FINE AGGREGATE	350 CY		
0048	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	2,000 LF		
0049	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	60 EA		
0050	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	4 EA		
0051	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	24 LF		
0052	2209000000-E	838	ENDWALLS	16 CY		
0053	2220000000-E	838	REINFORCED ENDWALLS	22.5 CY		
0054	2253000000-E	840	PIPE COLLARS	27 CY		

County : Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	2264000000-E	840	PIPE PLUGS	0.6 CY		
0056	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	81 EA		
0057	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	38.4 CY		
0058	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	37 LF		
0059	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	13 EA		
0060	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	19 EA		
0061	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	27 EA		
0062	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	3 EA		
0063	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	7 EA		
0064	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	6 EA		
0065	2396000000-N	840	FRAME WITH COVER, STD 840.54	9 EA		
0066	2535000000-E	846	***X *** CONCRETE CURB (8" X 18")	1,275 LF		
0067	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	3,400 LF		
0068	2556000000-E	846	SHOULDER BERM GUTTER	8,300 LF		
0069	2591000000-E	848	4" CONCRETE SIDEWALK	2,150 SY		
0070	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	8 EA		
0071	2612000000-E	848	6" CONCRETE DRIVEWAY	350 SY		
0072	2619000000-E	850	4" CONCRETE PAVED DITCH	15 SY		

County : Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	60 SY		
0074	2745000000-E	SP	GENERIC PAVING ITEM CONCRETE STEPS	10 CY		
0075	2830000000-N	858	ADJUSTMENT OF MANHOLES	4 EA		
0076	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	20 EA		
0077	3030000000-E	862	STEEL BM GUARDRAIL	11,887.5 LF		
0078	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	100 LF		
0079	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0080	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0081	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	61 EA		
0082	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	170 LF		
0083	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	7 EA		
0084	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	10 EA		
0085	3557000000-E	866	ADDITIONAL BARBED WIRE	100 LF		
0086	3559000000-E	866	** STRAND BARBED WIRE FENCE WITH POSTS (4)	800 LF		
0087	3628000000-E	876	RIP RAP, CLASS I	1,500 TON		
0088	3642000000-E	876	RIP RAP, CLASS A	10 TON		
0089	3649000000-E	876	RIP RAP, CLASS B	650 TON		
0090	3651000000-E	SP	BOULDERS	81 TON		

County : Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	6,850	SY	
0092	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2	EA	
0093	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	805	SF	
0094	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	512	SF	
0095	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	74	SF	
0096	4430000000-N	1130	DRUMS	280	EA	
0097	4435000000-N	1135	CONES	25	EA	
0098	4445000000-E	1145	BARRICADES (TYPE III)	72	LF	
0099	4450000000-N	1150	FLAGGER	4,928	HR	
0100	4480000000-N	1165	TMIA	2	EA	
0101	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	705	EA	
0102	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	55,225	LF	
0103	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	68,061	LF	
0104	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	500	LF	
0105	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	250	LF	
0106	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	52	EA	
0107	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	493,145	LF	
0108	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	2,000	LF	

County : Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0109	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,000 LF		
0110	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	104 EA		
0111	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	900 LF		
0112	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	685 EA		
0113	5882000000-N	SP	GENERIC UTILITY ITEM 10" GATE VALVE & VALVE BOX, 200# WP	4 EA		
0114	5882000000-N	SP	GENERIC UTILITY ITEM 10" TRANSITION COUPLING, PVC TO AC	1 EA		
0115	5882000000-N	SP	GENERIC UTILITY ITEM 10" X 3/4" TAPPING SADDLE	8 EA		
0116	5882000000-N	SP	GENERIC UTILITY ITEM 2" GATE VALVE & VALVE BOX, 200# WP	1 EA		
0117	5882000000-N	SP	GENERIC UTILITY ITEM 3/4" CORPORATION STOP	8 EA		
0118	5882000000-N	SP	GENERIC UTILITY ITEM 4" GATE VALVE & VALVE BOX, 200# WP	1 EA		
0119	5882000000-N	SP	GENERIC UTILITY ITEM 6" FLEXIBLE COUPLING, DI TO TC	2 EA		
0120	5882000000-N	SP	GENERIC UTILITY ITEM 6" GATE VALVE & VALVE BOX, 200# WP	4 EA		
0121	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE EXISTING FIRE HYDRANT	2 EA		
0122	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE EXISTING WATER METER	14 EA		
0123	5882000000-N	SP	GENERIC UTILITY ITEM THRUST COLLAR	2 EA		

County : Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0124	5888000000-E	SP	GENERIC UTILITY ITEM 10" PVC WATER PIPE, SDR 21, 200# WP	1,740 LF		
0125	5888000000-E	SP	GENERIC UTILITY ITEM 2" PVC WATER PIPE, SDR 21, 200# WP	17 LF		
0126	5888000000-E	SP	GENERIC UTILITY ITEM 3/4" COPPER WATER PIPE, TYPE K	345 LF		
0127	5888000000-E	SP	GENERIC UTILITY ITEM 4" DI FORCE MAIN SEWER PIPE, PC 350	40 LF		
0128	5888000000-E	SP	GENERIC UTILITY ITEM 4" PVC FORCE MAIN SEWER PIPE, SDR 21, 200# WP	956 LF		
0129	5888000000-E	SP	GENERIC UTILITY ITEM 4" PVC WATER PIPE, SDR 21, 200# WP	65 LF		
0130	5888000000-E	SP	GENERIC UTILITY ITEM 6" DI RESTRAINED JOINT WATER PIPE, CLASS 50	17 LF		
0131	5888000000-E	SP	GENERIC UTILITY ITEM 6" DI SEWER PIPE, PC 350	10 LF		
0132	5888000000-E	SP	GENERIC UTILITY ITEM 6" PVC WATER PIPE, SDR 21, 200# WP	51 LF		
0133	5888000000-E	SP	GENERIC UTILITY ITEM 8" DI SEWER PIPE, PC 350	10 LF		
0134	5888000000-E	SP	GENERIC UTILITY ITEM CEMENT GROUT FOR FILLING 10" AC ABANDONED WATER PIPE	1,703 LF		
0135	5900000000-E	SP	GENERIC UTILITY ITEM BEDDING MATERIAL, UTILITIES CLASS IV	50 TON		
0136	5900000000-E	SP	GENERIC UTILITY ITEM FOUNDATION CONDITIONING MATERIAL UTILITIES CLASS (VI)	50 TON		
0137	5900000000-E	SP	GENERIC UTILITY ITEM PAVEMENT REPAIR FOR UTILITY WORK	75 TON		

County : Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0138	5906000000-E	SP	GENERIC UTILITY ITEM DUCTILE IRON RESTRAINED JOINT WATER PIPE FITTINGS, 250# MIN WP	365 LB		
0139	5906000000-E	SP	GENERIC UTILITY ITEM DUCTILE IRON SEWER PIPE FITTINGS, 250# MIN WP	165 LB		
0140	5906000000-E	SP	GENERIC UTILITY ITEM DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP	2,540 LB		
0141	6000000000-E	1605	TEMPORARY SILT FENCE	12,500 LF		
0142	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	1,250 TON		
0143	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	8,480 TON		
0144	6012000000-E	1610	SEDIMENT CONTROL STONE	3,900 TON		
0145	6015000000-E	1615	TEMPORARY MULCHING	54.5 ACR		
0146	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	1,950 LB		
0147	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	7.75 TON		
0148	6024000000-E	1622	TEMPORARY SLOPE DRAINS	3,500 LF		
0149	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	66 EA		
0150	6029000000-E	SP	SAFETY FENCE	2,400 LF		
0151	6030000000-E	1630	SILT EXCAVATION	30,100 CY		
0152	6036000000-E	1631	MATTING FOR EROSION CONTROL	36,500 SY		
0153	6037000000-E	SP	COIR FIBER MAT	150 SY		
0154	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	2,600 SY		
0155	6042000000-E	1632	1/4" HARDWARE CLOTH	1,250 LF		

County : Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0156	6045000000-E	SP	*** TEMPORARY PIPE (18")	240	LF	
0157	6045000000-E	SP	*** TEMPORARY PIPE (24")	250	LF	
0158	6070000000-N	SP	SPECIAL STILLING BASINS	12	EA	
0159	6071030000-E	SP	COIR FIBER BAFFLES	1,325	LF	
0160	6071050000-E	SP	*** SKIMMER (2")	25	EA	
0161	6084000000-E	1660	SEEDING & MULCHING	53.5	ACR	
0162	6087000000-E	1660	MOWING	32	ACR	
0163	6090000000-E	1661	SEED FOR REPAIR SEEDING	500	LB	
0164	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1.25	TON	
0165	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	1,300	LB	
0166	6108000000-E	1665	FERTILIZER TOPDRESSING	40.25	TON	
0167	6111000000-E	SP	IMPERVIOUS DIKE	525	LF	
0168	6114000000-N	SP	SPECIALIZED HAND MOWING	30	HR	
0169	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	36	EA	
0170	6123000000-E	1670	REFORESTATION	0.3	ACR	
0171	6126000000-E	SP	STREAMBANK REFORESTATION	1.23	ACR	

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

0172	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	3,100	LF	
AA1						
0173	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,240	LF	
AA1						

County : Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0174 AA1	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	972	LF	
*** OR ***						
0175 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	2,744	LF	
0176 AA2	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	744	LF	
0177 AA2	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	432	LF	
0178 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	356	LF	
0179 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	496	LF	
0180 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	540	LF	
*** OR ***						
0181 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	2,744	LF	
0182 AA3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	744	LF	
0183 AA3	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	432	LF	
0184 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (15", 0.064")	356	LF	
0185 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (18", 0.064")	496	LF	
0186 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (24", 0.064")	540	LF	

***** END SCHEDULE AA *****

County : Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
CULVERT ITEMS						
0187	8126000000-N	414	CULVERT EXCAVATION, STA ***** (119+06.31 -L-)	Lump Sum	L.S.	
0188	8126000000-N	414	CULVERT EXCAVATION, STA ***** (141+90.62 -L-)	Lump Sum	L.S.	
0189	8126000000-N	414	CULVERT EXCAVATION, STA ***** (171+37.35 -L-)	Lump Sum	L.S.	
0190	8126000000-N	414	CULVERT EXCAVATION, STA ***** (79+43.01 -L-)	Lump Sum	L.S.	
0191	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	167 TON		
0192	8196000000-E	420	CLASS A CONCRETE (CULVERT)	430.1 CY		
0193	8245000000-E	425	REINFORCING STEEL (CULVERT)	57,093 LB		
0194	8590000000-E	876	RIP RAP, CLASS ** (I)	42 TON		
0195	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	48 SY		

1355/Jan11/Q1107418.88/D687481480000/E195

Total Amount Of Bid For Entire Project :

Contract No: C 201188

County: Yadkin

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General