

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	400 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	20 TON		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	520 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	400 SY		
0009	0241000000-E	SP	GENERIC GRADING ITEM GEOGRID REINFORCEMENT	240 SY		
0010	0241000000-E	SP	GENERIC GRADING ITEM PERM SOIL REINFORCEMENT MAT	115 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	220 TON		
0012	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	500 LF		
0013	0995000000-E	340	PIPE REMOVAL	310 LF		
0014	1220000000-E	545	INCIDENTAL STONE BASE	400 TON		
0015	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	2,500 SY		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	3,500 TON		
0017	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	2,250 TON		
0018	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,000 TON		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	377 TON		
0020	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	45 TON		
0021	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0022	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
0023	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0024	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0025	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0026	2132000000-N	816	CONCRETE PAD FOR SHOULDER DRAIN PIPE OUTLET	1 EA		
0027	2253000000-E	840	PIPE COLLARS	1 CY		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	38 EA		
0029	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	4 LF		
0030	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	15 EA		
0031	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	3 EA		
0032	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	10 EA		
0033	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	5 EA		
0034	2396000000-N	840	FRAME WITH COVER, STD 840.54	3 EA		
0035	2535000000-E	846	***X *** CONCRETE CURB (8" X 18")	310 LF		
0036	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	3,150 LF		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2612000000-E	848	6" CONCRETE DRIVEWAY	480 SY		
0038	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	100 SY		
0039	2830000000-N	858	ADJUSTMENT OF MANHOLES	17 EA		
0040	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	1 EA		
0041	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	2 EA		
0042	2950000000-N	SP	CONVERT EXISTING JUNCTION BOX TO DROP INLET	1 EA		
0043	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	75 LF		
0044	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	6 EA		
0045	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	2 EA		
0046	3554000000-E	866	METAL GATE POSTS FOR *** CHAIN LINK FENCE, DOUBLE GATE (48")	2 EA		
0047	3565000000-E	866	DOUBLE GATES, *** HIGH, *** WIDE, *** OPENING (48", 4' ,8')	1 EA		
0048	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	300 SY		
0049	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	249 LF		
0050	4096000000-N	904	SIGN ERECTION, TYPE D	1 EA		
0051	4102000000-N	904	SIGN ERECTION, TYPE E	23 EA		
0052	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	12 EA		
0053	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	1 EA		
0054	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	192 SF		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	192 SF		
0056	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0057	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
0058	4430000000-N	1130	DRUMS	94 EA		
0059	4435000000-N	1135	CONES	54 EA		
0060	4445000000-E	1145	BARRICADES (TYPE III)	24 LF		
0061	4455000000-N	1150	FLAGGER	60 MD		
0062	4480000000-N	1165	TMIA	2 EA		
0063	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	50 EA		
0064	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	5,193 LF		
0065	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	500 LF		
0066	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	37 EA		
0067	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") 4	90 LF		
0068	4795000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (24") 4	40 LF		
0069	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	57,424 LF		
0070	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,513 LF		
0071	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	100 EA		
0072	5325200000-E	1510	2" WATER LINE	70 LF		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	5325800000-E	1510	8" WATER LINE (DI)	48 LF		
0074	5325800000-E	1510	8" WATER LINE (PVC)	1,704 LF		
0075	5546000000-E	1515	8" VALVE	4 EA		
0076	5571800000-E	1515	8" TAPPING VALVE	2 EA		
0077	5606000000-E	1515	2" BLOW OFF	1 EA		
0078	5648000000-N	1515	RELOCATE WATER METER	17 EA		
0079	5672000000-N	1515	RELOCATE FIRE HYDRANT	2 EA		
0080	6000000000-E	1605	TEMPORARY SILT FENCE	3,300 LF		
0081	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	100 TON		
0082	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	180 TON		
0083	6012000000-E	1610	SEDIMENT CONTROL STONE	210 TON		
0084	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0085	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0086	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0087	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
0088	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0089	6030000000-E	1630	SILT EXCAVATION	170 CY		
0090	6036000000-E	1631	MATTING FOR EROSION CONTROL	360 SY		
0091	6042000000-E	1632	1/4" HARDWARE CLOTH	800 LF		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	6084000000-E	1660	SEEDING & MULCHING	2.5	ACR	
0093	6087000000-E	1660	MOWING	1.5	ACR	
0094	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0095	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0096	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0097	6108000000-E	1665	FERTILIZER TOPDRESSING	2	TON	
0098	6114000000-N	SP	SPECIALIZED HAND MOWING	1	HR	
0099	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8	EA	

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

0100	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,560	LF	
------	--------------	-----	---------------------------------	-------	----	--

AA1

*** OR ***

0101	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,328	LF	
------	--------------	-----	---------------------------------	-------	----	--

AA2

0102	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15",0.064")	232	LF	
------	--------------	----	---	-----	----	--

AA2

*** OR ***

0103	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,328	LF	
------	--------------	-----	---------------------------------	-------	----	--

AA3

0104	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	232	LF	
------	--------------	----	-------------------------------	-----	----	--

AA3

***** END SCHEDULE AA *****

Contract No: C201245

County: Cumberland

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General