

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0005	0134000000-E	240	DRAINAGE DITCH EXCAVATION	480 CY		
0006	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	140 TON		
0007	0344000000-E	310	18" SIDE DRAIN PIPE	48 LF		
0008	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,004 LF		
0009	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	28 LF		
0010	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	60 LF		
0011	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0012	0995000000-E	340	PIPE REMOVAL	473 LF		
0013	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
0014	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	3,470 TON		
0015	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	500 TON		
0016	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	2,800 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	175 TON		
0018	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	170 TON		

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	350 TON		
0020	2000000000-N	806	RIGHT OF WAY MARKERS	22 EA		
0021	2253000000-E	840	PIPE COLLARS	1 CY		
0022	2275000000-E	SP	FLOWABLE FILL	20 CY		
0023	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	18 EA		
0024	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	3 LF		
0025	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0026	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	4 EA		
0027	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	7 EA		
0028	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	6 EA		
0029	2535000000-E	846	***X *** CONCRETE CURB (8" X 12")	75 LF		
0030	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	3,470 LF		
0031	2612000000-E	848	6" CONCRETE DRIVEWAY	280 SY		
0032	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	6 SY		
0033	2830000000-N	858	ADJUSTMENT OF MANHOLES	6 EA		
0034	3030000000-E	862	STEEL BM GUARDRAIL	475 LF		
0035	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	12.5 LF		
0036	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		
0038	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	5 EA		
0039	3360000000-E	863	REMOVE EXISTING GUARDRAIL	405 LF		
0040	3628000000-E	876	RIP RAP, CLASS I	45 TON		
0041	3649000000-E	876	RIP RAP, CLASS B	65 TON		
0042	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	140 SY		
0043	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	78 SF		
0044	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	168 SF		
0045	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	18 SF		
0046	4430000000-N	1130	DRUMS	275 EA		
0047	4445000000-E	1145	BARRICADES (TYPE III)	50 LF		
0048	4450000000-N	1150	FLAGGER	1,500 HR		
0049	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0050	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	2 EA		
0051	4485000000-E	1170	PORTABLE CONCRETE BARRIER	142 LF		
0052	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	55 LF		
0053	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	13,855 LF		
0054	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	142 LF		
0055	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	180 LF		

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	12 EA		
0057	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	19 EA		
0058	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (TYPE 4)	1,180 LF		
0059	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	55,660 LF		
0060	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	120 LF		
0061	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	164 LF		
0062	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	4 EA		
0063	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	90 LF		
0064	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	136 EA		
0065	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0066	5325800000-E	1510	8" WATER LINE	2,380 LF		
0067	5546000000-E	1515	8" VALVE	3 EA		
0068	5648000000-N	1515	RELOCATE WATER METER	6 EA		
0069	5666000000-E	1515	FIRE HYDRANT	2 EA		
0070	5691300000-E	1520	8" SANITARY GRAVITY SEWER	20 LF		
0071	5798000000-E	1530	ABANDON *** UTILITY PIPE (8")	2,300 LF		
0072	5835000000-E	1540	*** ENCASEMENT PIPE (14")	20 LF		
0073	6000000000-E	1605	TEMPORARY SILT FENCE	3,900 LF		

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	11 TON		
0075	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	60 TON		
0076	6012000000-E	1610	SEDIMENT CONTROL STONE	76 TON		
0077	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0078	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0079	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
0080	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0081	6030000000-E	1630	SILT EXCAVATION	380 CY		
0082	6036000000-E	1631	MATTING FOR EROSION CONTROL	300 SY		
0083	6042000000-E	1632	1/4" HARDWARE CLOTH	720 LF		
0084	6045000000-E	SP	*** TEMPORARY PIPE (18")	84 LF		
0085	6069000000-E	1638	STILLING BASINS	120 CY		
0086	6084000000-E	1660	SEEDING & MULCHING	4 ACR		
0087	6090000000-E	1661	SEED FOR REPAIR SEEDING	20 LB		
0088	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.1 TON		
0089	6111000000-E	SP	IMPERVIOUS DIKE	55 LF		
0090	6114000000-N	SP	SPECIALIZED HAND MOWING	3 HR		
0091	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	4 EA		
0092	8126000000-N	414	CULVERT EXCAVATION, STA ***** (STA 43+15.57)	Lump Sum	L.S.	

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	8196000000-E	420	CLASS A CONCRETE (CULVERT)	71.8	CY	
0094	8245000000-E	425	REINFORCING STEEL (CULVERT)	10,911	LB	
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0095	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	44	LF	
AA1						
0096	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	176	LF	
AA1						
*** OR ***						
0097	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	24	LF	
AA2						
0098	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	132	LF	
AA2						
0099	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	20	LF	
AA2						
0100	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	44	LF	
AA2						
*** OR ***						
0101	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	24	LF	
AA3						
0102	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	132	LF	
AA3						
0103	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18", 0.064")	20	LF	
AA3						
0104	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24", 0.064")	44	LF	
AA3						

***** END SCHEDULE AA *****

Contract No: C201671

County: McDowell

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General