

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0015000000-N	205	SEALING ABANDONED WELLS	2 EA		
0006	0022000000-E	225	UNCLASSIFIED EXCAVATION	2,700 CY		
0007	0036000000-E	225	UNDERCUT EXCAVATION	1,750 CY		
0008	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	325 TON		
0009	0106000000-E	230	BORROW EXCAVATION	19,900 CY		
0010	0134000000-E	240	DRAINAGE DITCH EXCAVATION	1,500 CY		
0011	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	4,550 SY		
0012	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	3,850 SY		
0013	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0014	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0015	0199000000-E	SP	TEMPORARY SHORING	1,930 SF		
0016	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	425 TON		
0017	0343000000-E	310	15" SIDE DRAIN PIPE	24 LF		
0018	0986000000-E	SP	GENERIC PIPE ITEM 10" PVC PIPE	48 LF		
0019	0995000000-E	340	PIPE REMOVAL	768 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0021	1110000000-E	510	STABILIZER AGGREGATE	200 TON		
0022	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0023	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	3,300 SY		
0024	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	1,900 SY		
0025	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (4")	2,100 SY		
0026	1330000000-E	607	INCIDENTAL MILLING	300 SY		
0027	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	6,950 TON		
0028	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	5,475 TON		
0029	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4,550 TON		
0030	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	830 TON		
0031	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	230 TON		
0032	2000000000-N	806	RIGHT OF WAY MARKERS	25 EA		
0033	2022000000-E	815	SUBDRAIN EXCAVATION	112 CY		
0034	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84 CY		
0035	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0036	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0038	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0039	2209000000-E	838	ENDWALLS	4.5 CY		
0040	2253000000-E	840	PIPE COLLARS	2 CY		
0041	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	48 EA		
0042	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	28 LF		
0043	2352000000-N	840	FRAME WITH GRATE, STD 840.**** (840.16)	9 EA		
0044	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0045	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	5 EA		
0046	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	13 EA		
0047	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	17 EA		
0048	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	5,300 LF		
0049	2591000000-E	848	4" CONCRETE SIDEWALK	500 SY		
0050	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	8 EA		
0051	2612000000-E	848	6" CONCRETE DRIVEWAY	350 SY		
0052	2619000000-E	850	4" CONCRETE PAVED DITCH	70 SY		
0053	2830000000-N	858	ADJUSTMENT OF MANHOLES	40 EA		
0054	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	40 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	3628000000-E	876	RIP RAP, CLASS I	115 TON		
0056	3649000000-E	876	RIP RAP, CLASS B	75 TON		
0057	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	745 SY		
0058	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0059	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	353 LF		
0060	4102000000-N	904	SIGN ERECTION, TYPE E	8 EA		
0061	4108000000-N	904	SIGN ERECTION, TYPE F	3 EA		
0062	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (TYPE E)	2 EA		
0063	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	20 EA		
0064	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	588 SF		
0065	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	148 SF		
0066	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	219 SF		
0067	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	1 EA		
0068	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	9 EA		
0069	4445000000-E	1145	BARRICADES (TYPE III)	184 LF		
0070	4455000000-N	1150	FLAGGER	600 MD		
0071	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4 EA		
0072	4485000000-E	1170	PORTABLE CONCRETE BARRIER	1,000 LF		
0073	4507000000-E	SP	WATER FILLED BARRIER	798 LF		
0074	4508000000-E	SP	RESET WATER FILLED BARRIER	1,809 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	4510000000-N	SP	POLICE	60 HR		
0076	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	647 EA		
0077	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	636 LF		
0078	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	11,290 LF		
0079	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	315 LF		
0080	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	157 LF		
0081	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	16 EA		
0082	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	31 EA		
0083	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	66,251 LF		
0084	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	2,465 LF		
0085	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	405 LF		
0086	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	24 EA		
0087	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	53 EA		
0088	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	23,390 LF		
0089	4855000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (6")	87 LF		
0090	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	1,794 LF		
0091	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	54 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	20 EA		
0093	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	379 EA		
0094	5882000000-N	SP	GENERIC UTILITY ITEM 6" GATE VALVE & VALVE BOX, 200# WP	1 EA		
0095	5882000000-N	SP	GENERIC UTILITY ITEM 8" DOUBLE DETECTOR CHECK VALVE ASSEMBLY & VAULT	1 EA		
0096	5882000000-N	SP	GENERIC UTILITY ITEM 8" WATER METER ASSEMBLY & VAULT	1 EA		
0097	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE EXISTING FIRE HYDRANT	7 EA		
0098	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE EXISTING WATER METER	2 EA		
0099	5888000000-E	SP	GENERIC UTILITY ITEM 16" DI WATER PIPE, PC 250	60 LF		
0100	5888000000-E	SP	GENERIC UTILITY ITEM 3/4" COPPER WATER PIPE, TYPE K	68 LF		
0101	5888000000-E	SP	GENERIC UTILITY ITEM 6" DI WATER PIPE, PC 350	121 LF		
0102	5888000000-E	SP	GENERIC UTILITY ITEM 8" DI WATER PIPE, PC 350	60 LF		
0103	5900000000-E	SP	GENERIC UTILITY ITEM BEDDING MATERIAL, UTILITIES CLASS VI	12 TON		
0104	5900000000-E	SP	GENERIC UTILITY ITEM FOUNDATION CONDITIONING MATE- RIAL, UTILITIES CLASS VI	12 TON		
0105	5906000000-E	SP	GENERIC UTILITY ITEM DUCTILE IRON WATER PIPE FIT- TINGS, 250# WP	1,975 LB		
0106	6000000000-E	1605	TEMPORARY SILT FENCE	5,155 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	495 TON		
0108	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,070 TON		
0109	6012000000-E	1610	SEDIMENT CONTROL STONE	940 TON		
0110	6015000000-E	1615	TEMPORARY MULCHING	4 ACR		
0111	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0112	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0113	6024000000-E	1622	TEMPORARY SLOPE DRAINS	350 LF		
0114	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	3 EA		
0115	6029000000-E	SP	SAFETY FENCE	350 LF		
0116	6030000000-E	1630	SILT EXCAVATION	9,235 CY		
0117	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,960 SY		
0118	6037000000-E	SP	COIR FIBER MAT	60 SY		
0119	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	85 SY		
0120	6042000000-E	1632	1/4" HARDWARE CLOTH	1,060 LF		
0121	6045000000-E	SP	*** TEMPORARY PIPE (24")	235 LF		
0122	6069000000-E	1638	STILLING BASINS	100 CY		
0123	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
0124	6087000000-E	1660	MOWING	2.5 ACR		
0125	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0126	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0127	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0128	6108000000-E	1665	FERTILIZER TOPDRESSING	3.75 TON		
0129	6111000000-E	SP	IMPERVIOUS DIKE	100 LF		
0130	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0131	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	30 EA		
0132	6132000000-N	SP	GENERIC EROSION CONTROL ITEM 3" FAIRCLOTH SKIMMER	2 EA		
0133	7060000000-E	1705	SIGNAL CABLE	685 LF		
0134	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	3 EA		
0135	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	3 EA		
0136	7264000000-E	1710	MESSENGER CABLE (3/8")	325 LF		
0137	7288000000-E	1715	PAVED TRENCHING (***** (1, 2")	50 LF		
0138	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	550 LF		
0139	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	5 EA		
0140	7360000000-N	1720	WOOD POLE	4 EA		
0141	7372000000-N	1721	GUY ASSEMBLY	6 EA		
0142	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0143	7420000000-E	1722	2" RISER WITH WEATHERHEAD	4 EA		
0144	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	605 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0145	7456000000-E	1726	LEAD-IN CABLE (*****) (18-2)	1,885	LF	
0146	7552000000-N	1731	INTERCONNECT CENTER	1	EA	
0147	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1	EA	
0148	7980000000-N	SP	GENERIC SIGNAL ITEM 2070L CONTROLLER, CARY COMPAT- IBLE	1	EA	
0149	7980000000-N	SP	GENERIC SIGNAL ITEM NEMA TS-2 CABINET (BASE MOUNTED) CARY COMPATIBLE	1	EA	
0150	7980000000-N	SP	GENERIC SIGNAL ITEM NEMA TS-2 DETECTOR CARD	8	EA	
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0151	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,960	LF	
AA1						
0152	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,332	LF	
AA1						
0153	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	452	LF	
AA1						
0154	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	168	LF	
AA1						
*** OR ***						
0155	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,672	LF	
AA2						
0156	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,200	LF	
AA2						
0157	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	360	LF	
AA2						
0158	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	64	LF	
AA2						
0159	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	288	LF	
AA2						

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0160 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	132 LF		
0161 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	92 LF		
0162 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (42")	104 LF		
*** OR ***						
0163 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,672 LF		
0164 AA3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,200 LF		
0165 AA3	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	360 LF		
0166 AA3	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	64 LF		
0167 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064" THICK)	288 LF		
0168 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18", 0.064" THICK)	132 LF		
0169 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24", 0.064" THICK)	92 LF		
0170 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (42", 0.109" THICK)	104 LF		
***** END SCHEDULE AA *****						
0177	4430000000-N	1130	DRUMS	120 EA		
0178	4435000000-N	1135	CONES	100 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
CULVERT ITEMS						
0171	8126000000-N	414	CULVERT EXCAVATION, STA ***** (37+40.00 -L-)	Lump Sum	L.S.	
0172	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	87 TON		
0173	8196000000-E	420	CLASS A CONCRETE (CULVERT)	119.6 CY		
0174	8245000000-E	425	REINFORCING STEEL (CULVERT)	16,512 LB		
0175	8590000000-E	876	RIP RAP, CLASS ** (1)	33 TON		
0176	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	36 SY		
1124/Mar12/Q243397.1/D684846600000/E178			Total Amount Of Bid For Entire Project :			

Contract No: C 201744

County: Wake

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General