

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000900000-N	SP	GENERIC MISCELLANEOUS ITEM CONSTRUCTION SURVEYING (ICW STRUCTURE ONLY)	Lump Sum	L.S.	
0003	0000995000-E	SP	GENERIC MISCELLANEOUS ITEM DISPOSAL OF CONTAMINATED SOIL	75 TON		
0004	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0005	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	3 ACR		
0006	0022000000-E	225	UNCLASSIFIED EXCAVATION	4,700 CY		
0007	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (21 + 50.00-L-)	Lump Sum	L.S.	
0008	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (58 + 00.00-L-)	Lump Sum	L.S.	
0009	0036000000-E	225	UNDERCUT EXCAVATION	43,177 CY		
0010	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	1,000 TON		
0011	0106000000-E	230	BORROW EXCAVATION	670,500 CY		
0012	0134000000-E	240	DRAINAGE DITCH EXCAVATION	5,293 CY		
0013	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	4,900 SY		
0014	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	3,100 SY		
0015	0192000000-N	260	PROOF ROLLING	34 HR		
0016	0195000000-E	265	SELECT GRANULAR MATERIAL	54,000 CY		
0017	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,000 SY		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0199000000-E	SP	TEMPORARY SHORING	18,350	SF	
001E	0234000000-E	SP	GENERIC GRADING ITEM SELECT MATERIAL, CLASS III	3,500	CY	
002C	0241000000-E	SP	GENERIC GRADING ITEM FABRIC FOR REINFORCED SLOPE	9,000	SY	
0021	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	1,415	TON	
0022	0343000000-E	310	15" SIDE DRAIN PIPE	84	LF	
0023	0344000000-E	310	18" SIDE DRAIN PIPE	68	LF	
0024	0360000000-E	310	12" RC PIPE CULVERTS, CLASS III	20	LF	
002E	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	4,780	LF	
002E	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	392	LF	
0027	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	176	LF	
002E	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	1,392	LF	
002E	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	2,920	LF	
003C	0408000000-E	310	54" RC PIPE CULVERTS, CLASS III	54	LF	
0031	0414000000-E	310	60" RC PIPE CULVERTS, CLASS III	368	LF	
0032	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	144	LF	
0033	0962000000-E	320	*** X *** CAA STRUCTURAL PLATE PIPE ARCH, ***** THICK (60" x 46", 0.109")	1,008	LF	

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	0986000000-E	SP	GENERIC PIPE ITEM STORM CHAMBER	170.8 LF		
003E	0992000000-E	SP	GENERIC PIPE ITEM 15" HDPE PIPE ELBOWS	6 EA		
003E	0995000000-E	340	PIPE REMOVAL	372 LF		
0037	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
003E	1110000000-E	510	STABILIZER AGGREGATE	16,000 TON		
003E	1121000000-E	520	AGGREGATE BASE COURSE	73,000 TON		
004C	1220000000-E	545	INCIDENTAL STONE BASE	250 TON		
0041	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	1,330 SY		
0042	1330000000-E	607	INCIDENTAL MILLING	500 SY		
0043	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,300 TON		
0044	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	2,150 TON		
004E	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	17,700 TON		
004E	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	650 TON		
0047	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	25,500 TON		
004E	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	2,325 TON		
004E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	2,670 TON		
005C	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	155 TON		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0051	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	545 TON		
0052	2022000000-E	815	SUBDRAIN EXCAVATION	68 CY		
0053	2033000000-E	815	SUBDRAIN FINE AGGREGATE	34 CY		
0054	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0055	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0056	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0057	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0058	2209000000-E	838	ENDWALLS	24.4 CY		
0059	2220000000-E	838	REINFORCED ENDWALLS	7.9 CY		
006C	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	72 EA		
0061	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	23 CY		
0062	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	44 EA		
0063	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	5 EA		
0064	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	22 EA		
006E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	1 EA		
0066	2396000000-N	840	FRAME WITH COVER, STD 840.54	7 EA		
0067	2474000000-N	SP	GENERIC DRAINAGE ITEM ALUMINUM ENDWALLS FOR FIVE PIPE CULVERT	Lump Sum	L.S.	

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
006E	2474000000-N	SP	GENERIC DRAINAGE ITEM ALUMINUM ENDWALLS FOR FOUR PIPE CULVERT	Lump Sum	L.S.	
006E	2535000000-E	846	***X *** CONCRETE CURB (8" X 18")	275 LF		
007C	2538000000-E	846	***-*** CONCRETE CURB & GUTTER (2'- 9")	7,875 LF		
0071	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	24,375 LF		
0072	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	410 LF		
0073	2556000000-E	846	SHOULDER BERM GUTTER	1,600 LF		
0074	2591000000-E	848	4" CONCRETE SIDEWALK	1,075 SY		
007E	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	4 EA		
007E	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	1,800 SY		
0077	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	1 EA		
007E	3030000000-E	862	STEEL BM GUARDRAIL	2,850 LF		
007E	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	62.5 LF		
008C	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0081	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0082	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	8 EA		
008E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	11 EA		
0084	3345000000-E	864	REMOVE & RESET EXISTING GUARD- RAIL	337.5 LF		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	40,600 LF		
008E	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	2,650 EA		
0087	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	520 EA		
008E	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	3,700 LF		
008E	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	310 EA		
009C	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	25 EA		
0091	3551000000-E	866	METAL GATE POSTS FOR *** CHAIN LINK FENCE, SINGLE GATE (48")	10 EA		
0092	3557000000-E	866	ADDITIONAL BARBED WIRE	100 LF		
009E	3564000000-E	866	SINGLE GATES, *** HIGH, *** WIDE, *** OPENING (48" HIGH, 12' WIDE, 12' OPEN)	5 EA		
0094	3564000000-E	866	SINGLE GATES, *** HIGH, *** WIDE, *** OPENING (48" HIGH, 16' WIDE, 16' OPEN)	4 EA		
009E	3565000000-E	866	DOUBLE GATES, *** HIGH, *** WIDE, *** OPENING (48" HIGH, 10' WIDE, 20' OPEN)	1 EA		
009E	3628000000-E	876	RIP RAP, CLASS I	125 TON		
0097	3635000000-E	876	RIP RAP, CLASS II	1,610 TON		
009E	3649000000-E	876	RIP RAP, CLASS B	65 TON		
009E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	4,020 SY		
010C	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0101	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	1,310 LF		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0102	4096000000-N	904	SIGN ERECTION, TYPE D	6 EA		
0103	4102000000-N	904	SIGN ERECTION, TYPE E	56 EA		
0104	4108000000-N	904	SIGN ERECTION, TYPE F	6 EA		
010E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	19 EA		
010E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	1,096 SF		
0107	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	552 SF		
010E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	210 SF		
010E	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
011C	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	4 EA		
0111	4430000000-N	1130	DRUMS	430 EA		
0112	4435000000-N	1135	CONES	42 EA		
0113	4445000000-E	1145	BARRICADES (TYPE III)	376 LF		
0114	4450000000-N	1150	FLAGGER	10,000 HR		
011E	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	8 EA		
011E	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	2 EA		
0117	4480000000-N	1165	TMIA	2 EA		
011E	4485000000-E	1170	PORTABLE CONCRETE BARRIER	670 LF		
011E	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	220 LF		
012C	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	400 LF		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0121	4510000000-N	SP	POLICE	200 HR		
0122	4516000000-N	1180	SKINNY DRUM	84 EA		
0123	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	623 EA		
0124	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (4)	652 LF		
0125	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	197,322 LF		
0126	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	340 LF		
0127	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,740 LF		
0128	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	16 EA		
0129	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	122 EA		
0130	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS)	95,764 LF		
0131	4847110000-E	1205	POLYUREA PAVEMENT MARKING LINES (8", *****) (STANDARD GLASS BEADS)	74 LF		
0132	4847140000-E	1205	POLYUREA PAVEMENT MARKING LINES (24", *****) (STANDARD GLASS BEADS)	418 LF		
0133	4847200000-N	1205	POLYUREA PAVEMENT MARKING CHARACTER (*****) (STANDARD GLASS BEADS)	16 EA		
0134	4847220000-N	1205	POLYUREA PAVEMENT MARKING SYMBOL (*****) (STANDARD GLASS BEADS)	76 EA		
0135	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	3,119 LF		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0136	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	84 LF		
0137	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	86 LF		
013E	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	3 EA		
013E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	27 EA		
014C	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	888 EA		
0141	5325000000-E	1510	*** WATER LINE (14")	248 LF		
0142	5325400000-E	1510	4" WATER LINE	270 LF		
014E	5325800000-E	1510	8" WATER LINE	55 LF		
0144	5326200000-E	1510	12" WATER LINE	4,660 LF		
014E	5538000000-E	1515	4" VALVE	2 EA		
014E	5546000000-E	1515	8" VALVE	1 EA		
0147	5558000000-E	1515	12" VALVE	11 EA		
014E	5649000000-N	1515	RECONNECT WATER METER	21 EA		
014E	5672000000-N	1515	RELOCATE FIRE HYDRANT	8 EA		
015C	5800000000-E	1530	ABANDON 6" UTILITY PIPE	196 LF		
0151	5801000000-E	1530	ABANDON 8" UTILITY PIPE	2,096 LF		
0152	5804000000-E	1530	ABANDON 12" UTILITY PIPE	2,123 LF		
015E	5805000000-E	1530	ABANDON 14" UTILITY PIPE	275 LF		
0154	5871700000-E	1550	TRENCHLESS INSTALLATION OF 12" IN SOIL	450 LF		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
015E	6000000000-E	1605	TEMPORARY SILT FENCE	47,000 LF		
015E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	550 TON		
0157	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	5,040 TON		
015E	6012000000-E	1610	SEDIMENT CONTROL STONE	3,120 TON		
015E	6015000000-E	1615	TEMPORARY MULCHING	40 ACR		
016C	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	1,350 LB		
0161	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	5.5 TON		
0162	6024000000-E	1622	TEMPORARY SLOPE DRAINS	2,650 LF		
016E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	87 EA		
0164	6029000000-E	SP	SAFETY FENCE	17,930 LF		
016E	6030000000-E	1630	SILT EXCAVATION	7,755 CY		
016E	6036000000-E	1631	MATTING FOR EROSION CONTROL	5,000 SY		
0167	6037000000-E	SP	COIR FIBER MAT	10 SY		
016E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	350 SY		
016E	6042000000-E	1632	1/4" HARDWARE CLOTH	5,400 LF		
017C	6045000000-E	SP	*** TEMPORARY PIPE (24")	130 LF		
0171	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	175 SY		
0172	6069000000-E	1638	STILLING BASINS	300 CY		
017E	6070000000-N	SP	SPECIAL STILLING BASINS	32 EA		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0174	6071030000-E	SP	COIR FIBER BAFFLES	140 LF		
017E	6071050000-E	SP	*** SKIMMER (2")	1 EA		
0176	6084000000-E	1660	SEEDING & MULCHING	82 ACR		
0177	6087000000-E	1660	MOWING	22.5 ACR		
017E	6090000000-E	1661	SEED FOR REPAIR SEEDING	350 LB		
017E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.75 TON		
018C	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	900 LB		
0181	6108000000-E	1665	FERTILIZER TOPDRESSING	61.25 TON		
0182	6111000000-E	SP	IMPERVIOUS DIKE	30 LF		
0183	6114000000-N	SP	SPECIALIZED HAND MOWING	7.5 HR		
0184	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	36 EA		
018E	6123000000-E	1670	REFORESTATION	0.5 ACR		
018E	7060000000-E	1705	SIGNAL CABLE	2,264 LF		
0187	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	8 EA		
018E	7264000000-E	1710	MESSENGER CABLE (3/8")	471 LF		
018E	7288000000-E	1715	PAVED TRENCHING (***** (1, 2")	189 LF		
019C	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	2,299 LF		
0191	7301000000-E	1715	DIRECTIONAL DRILL (***** (2, 2")	482 LF		
0192	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	19 EA		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0193	7360000000-N	1720	WOOD POLE	5 EA		
0194	7372000000-N	1721	GUY ASSEMBLY	8 EA		
0195	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0196	7420000000-E	1722	2" RISER WITH WEATHERHEAD	6 EA		
0197	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	3,331 LF		
0198	7456000000-E	1726	LEAD-IN CABLE (***** (18-2)	4,820 LF		
0199	7456000000-E	1726	LEAD-IN CABLE (***** (18-4)	120 LF		
020C	7484000000-N	SP	MICROWAVE VEHICLE DETECTOR	2 EA		
0201	7588000000-N	SP	METAL POLE WITH SINGLE MAST ARM	8 EA		
0202	7613000000-N	SP	SOIL TEST	8 EA		
0203	7614100000-E	SP	DRILLED PIER FOUNDATION	60 CY		
0204	7631000000-N	SP	MAST ARM WITH METAL POLE DE- SIGN	8 EA		
020E	7636000000-N	1745	SIGN FOR SIGNALS	2 EA		
0206	7684000000-N	1750	SIGNAL CABINET FOUNDATION	2 EA		
0207	7688000000-N	1753	CABINET BASE ADAPTER	2 EA		
020E	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	2 EA		
020E	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	12 EA		
021C	7980000000-N	SP	GENERIC SIGNAL ITEM POLYCARBONATE VEHICLE SIGNAL HEAD, (12", 3 SECT)	14 EA		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0211	7980000000-N	SP	GENERIC SIGNAL ITEM POLYCARBONATE VEHICLE SIGNAL HEAD, (12", 5 SECT)	2 EA		

CULVERT ITEMS

0212	8126000000-N	414	CULVERT EXCAVATION, STA ***** (23+98.00 -Y7-)	Lump Sum	L.S.	
0213	8133000000-E	414	FOUNDATION CONDITIONING MATER- IAL, BOX CULVERT	47 TON		
0214	8196000000-E	420	CLASS A CONCRETE (CULVERT)	90.8 CY		
0215	8248000000-E	425	EPOXY COATED REINFORCING STEEL (CULVERT)	11,529 LB		

WALL ITEMS

0216	8832000000-N	SP	GENERIC RETAINING WALL ITEM REMOVAL OF EXISTING STRUCTURES AT STA 56+40.47 -L-	Lump Sum	L.S.	
0217	8892000000-E	SP	GENERIC STRUCTURE ITEM STEEL SHEET PILE BULKHEAD	1,976 SF		

STRUCTURE ITEMS

0218	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (58+00.00 -L-)	Lump Sum	L.S.	
0219	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (21+50.00 -L-)	Lump Sum	L.S.	
0220	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1, 58+00.00 -L-)	Lump Sum	L.S.	

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0221	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (4, 58+00.00 -L-)	Lump Sum	L.S.	
0222	8108000000-E	SP	***-*** DIA DRILLED PIERS (6'-0")	1,264 LF		
0223	8111000000-E	SP	PERMANENT STEEL CASING FOR ***-*** DIA DRILLED PIER (6'-0")	336.52 LF		
0224	8113000000-N	SP	SID INSPECTION	16 EA		
0225	8114000000-N	SP	SPT TESTING	16 EA		
0226	8115000000-N	SP	CROSSHOLE SONIC LOGGING	4 EA		
0227	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (21 + 50.00 -L-)	Lump Sum	L.S.	
0228	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	16,845 SF		
0229	8154000000-E	420	REINFORCED CONCRETE DECK SLAB (SAND LIGHTWEIGHT CONC)	49,701 SF		
0230	8156000000-E	SP	CONCRETE WEARING SURFACE	6,595 SF		
0231	8161000000-E	420	GROOVING BRIDGE FLOORS	64,672 SF		
0232	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	1,833.2 CY		
0233	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (21 + 50.00 -L-)	Lump Sum	L.S.	
0234	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (58 + 00.00 -L-)	Lump Sum	L.S.	
0235	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	547,913 LB		
0236	8226000000-E	425	EPOXY COATED SPIRAL COLUMN RE- INFORCING STEEL (BRIDGE)	49,670 LB		

County : Brunswick

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0237	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	53,300	LS	
0238	8333000000-E	450	16" PRESTRESSED CONC PILES	1,280	LF	
0239	8364000000-E	450	HP12X53 STEEL PILES	9,400	LF	
024C	8475000000-E	460	TWO BAR METAL RAIL	2,254.41	LF	
0241	8517000000-E	460	1'-***X ***** CONCRETE PARA-PET (1'-2" X 2'-6")	2,119.54	LF	
0242	8517000000-E	460	1'-***X ***** CONCRETE PARA-PET (1'-2" X 3'-1-1/2")	164.88	LF	
0243	8531000000-E	462	4" SLOPE PROTECTION	1,660	SY	
0244	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,549	TON	
0245	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,715	SY	
0246	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0247	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0248	8744000000-N	SP	SOLAR ARRAY SUPPORT PLATFORM	Lump Sum	L.S.	
0249	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	2,634	LF	
025C	8860000000-N	SP	GENERIC STRUCTURE ITEM POST-TENSIONING TENDONS	Lump Sum	L.S.	
0251	8867000000-E	SP	GENERIC STRUCTURE ITEM 78" POST-TENSIONED PRESTRESSED CONCRETE GIRDERS	5,768	LF	
0252	8867000000-E	SP	GENERIC STRUCTURE ITEM 78" PRESTRESSED CONCRETE GIRDERS	1,972	LF	

Contract No: C 201550

County: Brunswick

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

