

County : Cleveland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+31.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	350 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	88 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	350 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	10 TON		
0010	0343000000-E	310	15" SIDE DRAIN PIPE	36 LF		
0011	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	52 LF		
0012	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	4 EA		
0013	0995000000-E	340	PIPE REMOVAL	26 LF		
0014	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	380 TON		
0016	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	370 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	41 TON		

County : Cleveland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2	EA	
001E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2	EA	
002C	2556000000-E	846	SHOULDER BERM GUTTER	85	LF	
0021	3030000000-E	862	STEEL BM GUARDRAIL	325	LF	
0022	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0023	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4	EA	
0024	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	
002E	3649000000-E	876	RIP RAP, CLASS B	4	TON	
002E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	390	SY	
0027	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	337	SF	
002E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94	SF	
002E	4445000000-E	1145	BARRICADES (TYPE III)	64	LF	
003C	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	8,800	LF	
0031	6000000000-E	1605	TEMPORARY SILT FENCE	520	LF	
0032	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75	TON	
0033	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	175	TON	
0034	6012000000-E	1610	SEDIMENT CONTROL STONE	140	TON	
003E	6015000000-E	1615	TEMPORARY MULCHING	2.5	ACR	

County : Cleveland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0037	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0038	6024000000-E	1622	TEMPORARY SLOPE DRAINS	30 LF		
0039	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
0040	6029000000-E	SP	SAFETY FENCE	200 LF		
0041	6030000000-E	1630	SILT EXCAVATION	465 CY		
0042	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,450 SY		
0043	6037000000-E	SP	COIR FIBER MAT	20 SY		
0044	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
0045	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		
0046	6071030000-E	SP	COIR FIBER BAFFLES	125 LF		
0047	6071050000-E	SP	*** SKIMMER (2")	2 EA		
0048	6084000000-E	1660	SEEDING & MULCHING	2.5 ACR		
0049	6087000000-E	1660	MOWING	1.5 ACR		
0050	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0051	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0052	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0053	6108000000-E	1665	FERTILIZER TOPDRESSING	1.75 TON		
0054	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		

County : Cleveland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		
STRUCTURE ITEMS						
005E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18 + 31.00 -L-)	Lump Sum	L.S.	
0057	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	23 LF		
005E	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	14 LF		
005E	8113000000-N	SP	SID INSPECTION	2 EA		
006C	8114000000-N	SP	SPT TESTING	2 EA		
0061	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0062	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (18 + 31.00 -L-)	Lump Sum	L.S.	
006E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	57 CY		
0064	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18 + 31.00 -L-)	Lump Sum	L.S.	
006E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	12,713 LB		
006E	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,213 LB		
0067	8364000000-E	450	HP12X53 STEEL PILES	440 LF		
006E	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	355.5 LF		
006E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	240 TON		
007C	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	267 SY		

County : Cleveland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0072	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	1,953.88 LF		
1420/Mar05/Q32778.38/D346988560000/E72			Total Amount Of Bid For Entire Project :			

Contract No: C201497

County: Cleveland

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General