

County : Craven

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (STA 21+45 -L-)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	60 TON		
0009	0345000000-E	310	24" SIDE DRAIN PIPE	24 LF		
0010	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0011	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	580 TON		
0012	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	500 TON		
0013	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	60 TON		
0014	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0015	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
0016	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0017	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0018	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		

County : Craven

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0020	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0021	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0022	2556000000-E	846	SHOULDER BERM GUTTER	42 LF		
0023	3030000000-E	862	STEEL BM GUARDRAIL	675 LF		
0024	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0025	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0026	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0027	3649000000-E	876	RIP RAP, CLASS B	3 TON		
0028	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	185 SY		
0029	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	355 SF		
0030	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0031	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0032	4430000000-N	1130	DRUMS	5 EA		
0033	4435000000-N	1135	CONES	36 EA		
0034	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0035	4450000000-N	1150	FLAGGER	80 HR		
0036	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	6,400 LF		
0037	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	10 EA		

County : Craven

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	5325600000-E	1510	6" WATER LINE	498 LF		
0039	5540000000-E	1515	6" VALVE	2 EA		
0040	5649000000-N	1515	RECONNECT WATER METER	2 EA		
0041	5912000000-N	SP	GENERIC UTILITY ITEM PIER ADJUSTMENTS	Lump Sum	L.S.	
0042	6000000000-E	1605	TEMPORARY SILT FENCE	1,175 LF		
0043	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	50 TON		
0044	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	20 TON		
0045	6012000000-E	1610	SEDIMENT CONTROL STONE	50 TON		
0046	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0047	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0048	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0049	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
0050	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0051	6029000000-E	SP	SAFETY FENCE	200 LF		
0052	6030000000-E	1630	SILT EXCAVATION	20 CY		
0053	6036000000-E	1631	MATTING FOR EROSION CONTROL	175 SY		
0054	6042000000-E	1632	1/4" HARDWARE CLOTH	225 LF		
0055	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0056	6087000000-E	1660	MOWING	1 ACR		
0057	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		

County : Craven

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0059	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0060	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
0061	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0062	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		
0063	6123000000-E	1670	REFORESTATION	0.1 ACR		

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

0064	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	48 LF		
------	--------------	-----	---------------------------------	----------	--	--

AA1

*** OR ***

0065	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	32 LF		
------	--------------	-----	---------------------------------	----------	--	--

AA2

0066	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	16 LF		
------	--------------	----	-------------------------------	----------	--	--

AA2

*** OR ***

0067	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	32 LF		
------	--------------	-----	---------------------------------	----------	--	--

AA3

0068	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18", 0.064")	16 LF		
------	--------------	----	--	----------	--	--

AA3

***** END SCHEDULE AA *****

STRUCTURE ITEMS

0069	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (21+45.00 -L-)	Lump Sum	L.S.	
------	--------------	-----	---	----------	------	--

0070	8112730000-N	SP	PDA TESTING	1 EA		
------	--------------	----	-------------	---------	--	--

0071	8112740000-N	SP	PDA ASSISTANCE	1 EA		
------	--------------	----	----------------	---------	--	--

County : Craven

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (21+45.00 -L-)	Lump Sum	L.S.	
0073	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (21+45.00 -L-)	Lump Sum	L.S.	
0074	8364000000-E	450	HP12X53 STEEL PILES	720 LF		
0075	8384000000-E	450	HP14X73 STEEL PILES	320 LF		
0076	8393000000-N	450	PILE REDRIVES	23 EA		
0077	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	215 TON		
0078	8765000000-N	SP	CONSTRUCTION OF SUBSTRUCTURE	Lump Sum	L.S.	
0079	8766000000-N	SP	CONSTRUCTION OF SUPERSTRUCTURE	Lump Sum	L.S.	
1450/Mar05/Q14004.6/D336859170000/E79			Total Amount Of Bid For Entire Project :			

Contract No: C201620

County: Craven

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General