

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000930000-E	SP	GENERIC MISCELLANEOUS ITEM STEEL PIPE HANDRAIL FOR RETAINING WALL	70 LF		
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
000E	0057000000-E	226	UNDERCUT EXCAVATION	1,500 CY		
000E	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	325 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	2 CY		
000E	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
000E	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
001C	0255000000-E	SP	GENERIC GRADING ITEM DISPOSAL OF CONTAMINATED SOIL	495 TON		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	258 TON		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,040 LF		
0013	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	56 LF		
0014	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	824 LF		
001E	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	336 LF		
001E	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	48 LF		
0017	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	6 EA		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0995000000-E	340	PIPE REMOVAL	1,200 LF		
001E	1022000000-E	SP	SEALING EXISTING PAVEMENT CRACKS	500 LB		
002C	1110000000-E	510	STABILIZER AGGREGATE	500 TON		
0021	1121000000-E	520	AGGREGATE BASE COURSE	184 TON		
0022	1220000000-E	545	INCIDENTAL STONE BASE	75 TON		
0023	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (2-1/2" TO 3")	5,320 SY		
0024	1330000000-E	607	INCIDENTAL MILLING	2,320 SY		
002E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	2,190 TON		
002E	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	3,110 TON		
0027	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	3,210 TON		
002E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	433 TON		
002E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	573 TON		
003C	2000000000-N	806	RIGHT OF WAY MARKERS	36 EA		
0031	2022000000-E	815	SUBDRAIN EXCAVATION	112 CY		
0032	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84 CY		
0033	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0034	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
003E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0037	2190000000-N	828	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	3 EA		
0038	2253000000-E	840	PIPE COLLARS	1 CY		
0039	2264000000-E	840	PIPE PLUGS	1 CY		
004C	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	38 EA		
0041	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	10 EA		
0042	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	13 EA		
0043	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	11 EA		
0044	2396000000-N	840	FRAME WITH COVER, STD 840.54	4 EA		
004E	2535000000-E	846	***X *** CONCRETE CURB (8" x 18")	360 LF		
0046	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	4,000 LF		
0047	2591000000-E	848	4" CONCRETE SIDEWALK	1,850 SY		
0048	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	27 EA		
0049	2612000000-E	848	6" CONCRETE DRIVEWAY	455 SY		
005C	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	645 SY		
0051	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	2 EA		
0052	2830000000-N	858	ADJUSTMENT OF MANHOLES	22 EA		
0053	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	3 EA		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	25 LF		
005E	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	2 EA		
005E	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	2 EA		
0057	3649000000-E	876	RIP RAP, CLASS B	10 TON		
005E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	255 SY		
005E	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (D)	78.58 SF		
006C	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	165.65 SF		
0061	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (F)	120.81 SF		
0062	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	865 LF		
006E	4096000000-N	904	SIGN ERECTION, TYPE D	6 EA		
0064	4102000000-N	904	SIGN ERECTION, TYPE E	31 EA		
006E	4108000000-N	904	SIGN ERECTION, TYPE F	6 EA		
006E	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	8 EA		
0067	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	30 EA		
006E	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	7 EA		
006E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	436 SF		
007C	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	346 SF		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	88	SF	
0072	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2	EA	
0073	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	1	DAY	
0074	4430000000-N	1130	DRUMS	130	EA	
0075	4435000000-N	1135	CONES	110	EA	
0076	4445000000-E	1145	BARRICADES (TYPE III)	270	LF	
0077	4455000000-N	1150	FLAGGER	180	MD	
0078	4510000000-N	SP	POLICE	8	HR	
0079	4520000000-N	1266	TUBULAR MARKERS (FIXED)	35	EA	
0080	4590000000-E	SP	GENERIC TRAFFIC CONTROL ITEM DEPARTMENT FURNISHED WATER-FILLED BARRIER	650	LF	
0081	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM DEPARTMENT FURNISHED CMS'S	2	EA	
0082	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	266	EA	
0083	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	325	LF	
0084	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	5,423	LF	
0085	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	53	LF	
0086	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	1,185	LF	
0087	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	172	LF	

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	402 LF		
008E	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	12 EA		
009C	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	37 EA		
0091	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	41,021 LF		
0092	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	475 LF		
0093	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	946 LF		
0094	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,472 LF		
009E	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	52 EA		
009E	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	78 EA		
0097	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	6,792 LF		
009E	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	593 LF		
009E	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	244 LF		
010C	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	12 EA		
0101	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	170 EA		
0102	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0103	5326200000-E	1510	12" WATER LINE	48 LF		
0104	5648000000-N	1515	RELOCATE WATER METER	24 EA		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
010E	5672000000-N	1515	RELOCATE FIRE HYDRANT	2 EA		
010E	5882000000-N	SP	GENERIC UTILITY ITEM INSTALL NEW METER BOX	3 EA		
0107	5882000000-N	SP	GENERIC UTILITY ITEM INSTALL NEW VALVE BOX	1 EA		
010E	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE SANITARY SEWER CLEANOUT	6 EA		
010E	6000000000-E	1605	TEMPORARY SILT FENCE	2,200 LF		
011C	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	115 TON		
0111	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	285 TON		
0112	6012000000-E	1610	SEDIMENT CONTROL STONE	370 TON		
011E	6015000000-E	1615	TEMPORARY MULCHING	4 ACR		
0114	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
011E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.75 TON		
011E	6030000000-E	1630	SILT EXCAVATION	135 CY		
0117	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,500 SY		
011E	6042000000-E	1632	1/4" HARDWARE CLOTH	1,100 LF		
011E	6084000000-E	1660	SEEDING & MULCHING	3.5 ACR		
012C	6087000000-E	1660	MOWING	2.5 ACR		
0121	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0122	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
012E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0124	6108000000-E	1665	FERTILIZER TOPDRESSING	2.75 TON		
012E	6114000000-N	SP	SPECIALIZED HAND MOWING	3 HR		
012E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		
0127	7000000000-E	1705	PEDESTRIAN SIGNAL HEAD (***, ** SECTION) (16", 1 SECTION WITH COUNTDOWN)	10 EA		
012E	7036000000-E	1705	PEDESTRIAN SIGNAL HEAD (12", 1 SECTION)	4 EA		
012E	7060000000-E	1705	SIGNAL CABLE	6,210 LF		
013C	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	39 EA		
0131	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	8 EA		
0132	7264000000-E	1710	MESSENGER CABLE (3/8")	1,125 LF		
013E	7279000000-E	1715	TRACER WIRE	180 LF		
0134	7300000000-E	1715	UNPAVED TRENCHING (*****) (2, 2")	1,510 LF		
013E	7301000000-E	1715	DIRECTIONAL DRILL (*****) (2, 2")	950 LF		
013E	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	33 EA		
0137	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEA- VY DUTY)	4 EA		
013E	7360000000-N	1720	WOOD POLE	12 EA		
013E	7372000000-N	1721	GUY ASSEMBLY	21 EA		
014C	7408000000-E	1722	1" RISER WITH WEATHERHEAD	2 EA		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0141	7420000000-E	1722	2" RISER WITH WEATHERHEAD	8	EA	
0142	7432000000-E	1722	2" RISER WITH HEAT SHRINK TUBING	2	EA	
0143	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	4,870	LF	
0144	7456000000-E	1726	LEAD-IN CABLE (*****) (18-2)	4,650	LF	
0145	7456000000-E	1726	LEAD-IN CABLE (*****) (18-4)	690	LF	
0146	7528000000-E	1730	DROP CABLE	450	LF	
0147	7575160000-E	1734	REMOVE EXISTING COMMUNICATIONS CABLE	50	LF	
0148	7588000000-N	SP	METAL POLE WITH SINGLE MAST ARM	6	EA	
0149	7590000000-N	SP	METAL POLE WITH DUAL MAST ARM	3	EA	
0150	7613000000-N	SP	SOIL TEST	9	EA	
0151	7614100000-E	SP	DRILLED PIER FOUNDATION	72	CY	
0152	7624000000-N	1743	SIGNAL PEDESTAL WITH FOUNDATION	3	EA	
0153	7631000000-N	SP	MAST ARM WITH METAL POLE DESIGN	9	EA	
0154	7636000000-N	1745	SIGN FOR SIGNALS	6	EA	
0155	7675000000-N	SP	LED BLANKOUT SIGN	1	EA	
0156	7676000000-N	SP	RELOCATE EXISTING BLANKOUT SIGN	1	EA	
0157	7684000000-N	1750	SIGNAL CABINET FOUNDATION	4	EA	
0158	7720000000-N	1751	CONTROLLER WITH CABINET (TYPE 170E, BASE MOUNTED)	4	EA	

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0158	7744000000-N	1751	DETECTOR CARD (TYPE 170)	13		
				EA		
016C	7901000000-N	1753	CABINET BASE EXTENDER	4		
				EA		
0161	7980000000-N	SP	GENERIC SIGNAL ITEM SYSTEM DETECTOR AMPLIFIER (2 CHANNEL)	8		
				EA		
0162	7980000000-N	SP	GENERIC SIGNAL ITEM SYSTEM MICROLOOP PROBE	4		
				EA		
0163	8436000000-E	453	GRAVITY RETAINING WALLS	410		
				SF		

0759/Mar09/Q124876.79/D715765590000/E163

Total Amount Of Bid For Entire Project :

Contract No: C201439

County: Durham

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General