

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+42.25)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	75 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	1,900 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,900 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	18 TON		
0010	0342000000-E	310	*** SIDE DRAIN PIPE (30")	24 LF		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	32 LF		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	32 LF		
0013	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	16 LF		
0014	0995000000-E	340	PIPE REMOVAL	24 LF		
0015	1121000000-E	520	AGGREGATE BASE COURSE	675 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0017	1275000000-E	600	PRIME COAT	490 GAL		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	325 TON		

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	869 TON		
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	71 TON		
0021	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	13 TON		
0022	2000000000-N	806	RIGHT OF WAY MARKERS	8 EA		
0023	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0024	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
0025	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0026	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0027	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0028	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0029	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0030	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	2 EA		
0031	2556000000-E	846	SHOULDER BERM GUTTER	45 LF		
0032	3030000000-E	862	STEEL BM GUARDRAIL	600 LF		
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0035	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0036	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	300 LF		

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (B-77)	4 EA		
0038	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	4 EA		
0039	3635000000-E	876	RIP RAP, CLASS II	185 TON		
0040	3649000000-E	876	RIP RAP, CLASS B	2 TON		
0041	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,010 SY		
0042	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	162 SF		
0043	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0044	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	52 SF		
0045	4430000000-N	1130	DRUMS	55 EA		
0046	4435000000-N	1135	CONES	60 EA		
0047	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		
0048	4455000000-N	1150	FLAGGER	50 MD		
0049	4480000000-N	1165	TMIA	1 EA		
0050	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	143 EA		
0051	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,758 LF		
0052	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,295 LF		
0053	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	24,364 LF		
0054	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	7,660 LF		

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	48	EA	
0056	5326200000-E	1510	12" WATER LINE	786	LF	
0057	5804000000-E	1530	ABANDON 12" UTILITY PIPE	470	LF	
0058	5871700000-E	1550	TRENCHLESS INSTALLATION OF 12" IN SOIL	662	LF	
0059	5871710000-E	1550	TRENCHLESS INSTALLATION OF 12" NOT IN SOIL	90	LF	
0060	6000000000-E	1605	TEMPORARY SILT FENCE	2,240	LF	
0061	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75	TON	
0062	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	480	TON	
0063	6012000000-E	1610	SEDIMENT CONTROL STONE	420	TON	
0064	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
0065	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
0066	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25	TON	
0067	6024000000-E	1622	TEMPORARY SLOPE DRAINS	215	LF	
0068	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	9	EA	
0069	6029000000-E	SP	SAFETY FENCE	350	LF	
0070	6030000000-E	1630	SILT EXCAVATION	630	CY	
0071	6036000000-E	1631	MATTING FOR EROSION CONTROL	170	SY	
0072	6042000000-E	1632	1/4" HARDWARE CLOTH	40	LF	
0073	6070000000-N	SP	SPECIAL STILLING BASINS	12	EA	

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
0075	6087000000-E	1660	MOWING	1 ACR		
0076	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0077	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0078	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0079	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5 TON		
0080	6114000000-N	SP	SPECIALIZED HAND MOWING	3 HR		
0081	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		
0082	6129000000-E	1670	WETLAND REFORESTATION	0.8 ACR		
0083	6135000000-E	SP	GENERIC EROSION CONTROL ITEM DISKING	0.8 ACR		
0084	6135000000-E	SP	GENERIC EROSION CONTROL ITEM RIPPING	0.8 ACR		
<b>STRUCTURE ITEMS</b>						
0085	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (17+42.25 -L-)	Lump Sum	L.S.	
0086	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (17+42.25 -L-)	Lump Sum	L.S.	
0087	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+42.25 -L-)	Lump Sum	L.S.	
0088	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	148.8 LF		
0089	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	60 LF		

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0090	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	148.3 LF		
0091	8113000000-N	SP	SID INSPECTION	1 EA		
0092	8114000000-N	SP	SPT TESTING	3 EA		
0093	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0094	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	1,245 CY		
0095	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	71 CY		
0096	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+42.25 -L-)	Lump Sum	L.S.	
0097	8217000000-E	425	REINFORCING STEEL (BRIDGE)	24,113 LB		
0098	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	4,726 LB		
0099	8364000000-E	450	HP12X53 STEEL PILES	500 LF		
0100	8503000000-E	460	CONCRETE BARRIER RAIL	360 LF		
0101	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	724 TON		
0102	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	804 SY		
0103	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0104	8753000000-E	430	3'-0" X 2'-3" PRESTRESSED CONC BOX BEAMS	2,514.75 LF		

0752/Mar08/Q88028.75/D472657590000/E104

Total Amount Of Bid For Entire Project :

**Contract No: C201565**

**County: Halifax**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General