

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (11 + 52.00-L1-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	100 TON		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
001C	0255000000-E	SP	GENERIC GRADING ITEM DISPOSAL OF CONTAMINATED SOIL	10 TON		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	30 TON		
0012	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	108 LF		
0013	0986000000-E	SP	GENERIC PIPE ITEM 24" PVC PIPE	40 LF		
0014	0995000000-E	340	PIPE REMOVAL	82 LF		
0015	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0016	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 3")	520 SY		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	40 TON		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	40 TON		
0019	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	145 TON		
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	13 TON		
0021	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	100 TON		
0022	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	34 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0025	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0026	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5 EA		
0029	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	28 LF		
0030	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0031	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1 EA		
0032	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0033	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	150 LF		
0034	2591000000-E	848	4" CONCRETE SIDEWALK	85 SY		
0035	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	2 EA		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	3649000000-E	876	RIP RAP, CLASS B	3 TON		
0037	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	161 SY		
003E	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	16.5 SF		
0039	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	44 LF		
004C	4102000000-N	904	SIGN ERECTION, TYPE E	4 EA		
0041	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	1 EA		
0042	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	4 EA		
0043	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1 EA		
0044	4238000000-N	907	DISPOSAL OF SIGN, D, E OR F	3 EA		
004E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	208 SF		
004E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0047	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	116 SF		
004E	4430000000-N	1130	DRUMS	15 EA		
0049	4435000000-N	1135	CONES	15 EA		
005C	4445000000-E	1145	BARRICADES (TYPE III)	140 LF		
0051	4450000000-N	1150	FLAGGER	100 HR		
0052	4516000000-N	1180	SKINNY DRUM	30 EA		
0053	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,252 LF		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	291 LF		
0055	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	108 LF		
0056	5325600000-E	1510	6" WATER LINE	97 LF		
0057	5540000000-E	1515	6" VALVE	1 EA		
0058	5672000000-N	1515	RELOCATE FIRE HYDRANT	1 EA		
0059	5912000000-N	SP	GENERIC UTILITY ITEM 6" DI RJ WATER MAIN ATTACHMENT	Lump Sum	L.S.	
0060	6000000000-E	1605	TEMPORARY SILT FENCE	335 LF		
0061	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	115 TON		
0062	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	105 TON		
0063	6012000000-E	1610	SEDIMENT CONTROL STONE	80 TON		
0064	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0065	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0066	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0067	6030000000-E	1630	SILT EXCAVATION	85 CY		
0068	6036000000-E	1631	MATTING FOR EROSION CONTROL	160 SY		
0069	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0070	6087000000-E	1660	MOWING	0.5 ACR		
0071	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0072	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0074	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
007E	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
007E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	4 EA		
0077	6890000000-E	SP	CONCRETE STEPS	1 CY		

---

**WALL ITEMS**


---

007E	8847000000-E	SP	GENERIC RETAINING WALL ITEM CAST-IN-PLACE CONCRETE FACED MSE RETAINING WALLS	1,820 SF		
007E	8847000000-E	SP	GENERIC RETAINING WALL ITEM TEMPORARY SHORING	800 SF		
008C	8847000000-E	SP	GENERIC RETAINING WALL ITEM TEMPORARY TIEBACK RETAINING WALL	1,250 SF		

---

**STRUCTURE ITEMS**


---

0081	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (11 + 83.94-L1-)	Lump Sum	L.S.	
0082	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (11 + 83.94-L1-)	Lump Sum	L.S.	
0083	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	5,287 SF		
0084	8161000000-E	420	GROOVING BRIDGE FLOORS	4,357 SF		
008E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	76.4 CY		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0086	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (11+83.94-L1-)	Lump Sum	L.S.	
0087	8217000000-E	425	REINFORCING STEEL (BRIDGE)	9,593 LB		
008E	8280000000-E	440	APPROX ..... LBS STRUCTURAL STEEL	262,400 LS		
008E	8364000000-E	450	HP12X53 STEEL PILES	500 LF		
009C	8531000000-E	462	4" SLOPE PROTECTION	227 SY		
0091	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0092	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0093	8860000000-N	SP	GENERIC STRUCTURE ITEM VIBRATION MONITORING	Lump Sum	L.S.	
0094	8867000000-E	SP	GENERIC STRUCTURE ITEM CLASSIC CONCRETE BRIDGE RAIL	255.83 LF		

0824/Apr05/Q292521.48/D407566200000/E94

Total Amount Of Bid For Entire Project :

**Contract No: C201477**

**County: Haywood**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General