

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	140 TON		
0006	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	948 LF		
0007	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	72 LF		
0008	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	172 LF		
0009	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	100 LF		
0010	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	24 LF		
0011	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0012	0995000000-E	340	PIPE REMOVAL	55 LF		
0013	1121000000-E	520	AGGREGATE BASE COURSE	15,280 TON		
0014	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
0015	1330000000-E	607	INCIDENTAL MILLING	80 SY		
0016	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	5,650 TON		
0017	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	6,320 TON		
0018	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	650 TON		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1570000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 76-22	360 TON		
0020	1662000000-E	650	OPEN-GRADED ASPHALT FRICTION COURSE, TYPE FC-1 MODIFIED	5,720 TON		
0021	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	100 TON		
0022	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	62,320 LF		
0023	2253000000-E	840	PIPE COLLARS	12.98 CY		
0024	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	43 EA		
0025	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	83.5 LF		
0026	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	11 EA		
0027	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	28 EA		
0028	2396000000-N	840	FRAME WITH COVER, STD 840.54	4 EA		
0029	2473000000-N	SP	GENERIC DRAINAGE ITEM BOLT DOWN RING AND COVER	1 EA		
0030	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	120 LF		
0031	2556000000-E	846	SHOULDER BERM GUTTER	40 LF		
0032	2619000000-E	850	4" CONCRETE PAVED DITCH	10 SY		
0033	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	1,290 SY		
0034	2703000000-E	854	CONCRETE BARRIER, TYPE ***** (SINGLE SLOPE)	10,640 LF		
0035	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	460 LF		
0036	2815000000-N	858	ADJUSTMENT OF DROP INLETS	1 EA		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	15 EA		
0038	3030000000-E	862	STEEL BM GUARDRAIL	137.5 LF		
0039	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50 LF		
0040	3060000000-E	862	STEEL BM GUARDRAIL, DOUBLE FACED	2,487.5 LF		
0041	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0042	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	2 EA		
0043	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1 EA		
0044	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	6 EA		
0045	3360000000-E	863	REMOVE EXISTING GUARDRAIL	410 LF		
0046	3649000000-E	876	RIP RAP, CLASS B	10 TON		
0047	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	25 SY		
0048	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	604 SF		
0049	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	104 SF		
0050	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	40 SF		
0051	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0052	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	2 DAY		
0053	4430000000-N	1130	DRUMS	160 EA		
0054	4435000000-N	1135	CONES	160 EA		
0055	4445000000-E	1145	BARRICADES (TYPE III)	120 LF		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4450000000-N	1150	FLAGGER	960	HR	
0057	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2	EA	
0058	4480000000-N	1165	TMIA	2	EA	
0059	4520000000-N	1266	TUBULAR MARKERS (FIXED)	60	EA	
0060	4590000000-E	SP	GENERIC TRAFFIC CONTROL ITEM DEPARTMENT FURNISHED PORTABLE CONCRETE BARRIER	400	LF	
0061	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	360	EA	
0062	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	159,878	LF	
0063	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	980	LF	
0064	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	120	LF	
0065	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (HIGHLY REFLECTIVE ELEMENTS)	84,452	LF	
0066	4847110000-E	1205	POLYUREA PAVEMENT MARKING LINES (8", *****) (HIGHLY REFLECTIVE ELEMENTS)	1,600	LF	
0067	4847140000-E	1205	POLYUREA PAVEMENT MARKING LINES (24", *****) (HIGHLY REFLECTIVE ELEMENTS)	60	LF	
0068	4847220000-N	1205	POLYUREA PAVEMENT MARKING SYMBOL (*****) (HIGHLY REFLECTIVE ELEMENTS)	45	EA	
0069	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	900	LF	
0070	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,096	EA	
0071	6000000000-E	1605	TEMPORARY SILT FENCE	1,940	LF	
0072	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	45	TON	

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	50 TON		
0074	6012000000-E	1610	SEDIMENT CONTROL STONE	140 TON		
0075	6015000000-E	1615	TEMPORARY MULCHING	3.5 ACR		
0076	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0077	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0078	6030000000-E	1630	SILT EXCAVATION	620 CY		
0079	6036000000-E	1631	MATTING FOR EROSION CONTROL	8,770 SY		
0080	6042000000-E	1632	1/4" HARDWARE CLOTH	905 LF		
0081	6084000000-E	1660	SEEDING & MULCHING	3.5 ACR		
0082	6087000000-E	1660	MOWING	2.5 ACR		
0083	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0084	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0085	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0086	6108000000-E	1665	FERTILIZER TOPDRESSING	2.5 TON		
0087	6114000000-N	SP	SPECIALIZED HAND MOWING	1 HR		
0088	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0089	8802012000-E	SP	PILE PANEL RETAINING WALLS	924 SF		
0090	8847000000-E	SP	GENERIC RETAINING WALL ITEM GABION AND RENO MATTRESS RETAINING WALLS	2,844 SF		

Contract No: C201796

County: Jackson

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General