

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000900000-N	SP	GENERIC MISCELLANEOUS ITEM ROADWAY CONSTRUCTION	Lump Sum	L.S.	
STRUCTURE ITEMS						
0003	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (22 + 03.60-L-)	Lump Sum	L.S.	
0004	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (22 + 03.60-L-)	Lump Sum	L.S.	
0005	8364000000-E	450	HP12X53 STEEL PILES	280 LF		
0006	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	280 LF		
0007	8391000000-N	450	STEEL PILE POINTS	16 EA		
0008	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	486 TON		
0009	8765000000-N	SP	CONSTRUCTION OF SUBSTRUCTURE	Lump Sum	L.S.	
0010	8766000000-N	SP	CONSTRUCTION OF SUPERSTRUCTURE	Lump Sum	L.S.	
1332/Apr02/Q1068.0/D67524200000/E10			Total Amount Of Bid For Entire Project :			

Contract No: C 201491

County: Nash

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General