

County : Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+81.43-L-)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	25 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0009	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	52 LF		
001C	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	680 TON		
0011	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	410 TON		
0012	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	60 TON		
0013	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		
0014	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8 CY		
001E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0016	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0017	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
001E	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		

County : Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0020	2355000000-N	840	FRAME WITH GRATE, STD 840.29	2 EA		
0021	2556000000-E	846	SHOULDER BERM GUTTER	60 LF		
0022	3030000000-E	862	STEEL BM GUARDRAIL	600 LF		
0023	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0024	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0025	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0026	3649000000-E	876	RIP RAP, CLASS B	35 TON		
0027	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	240 SY		
0028	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	256 SF		
0029	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0030	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0031	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	7,200 LF		
0032	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	20 EA		
0033	6000000000-E	1605	TEMPORARY SILT FENCE	985 LF		
0034	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	50 TON		
0035	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	90 TON		
0036	6012000000-E	1610	SEDIMENT CONTROL STONE	40 TON		

County : Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
003E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
003E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
004C	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
0041	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0042	6029000000-E	SP	SAFETY FENCE	250 LF		
0043	6030000000-E	1630	SILT EXCAVATION	320 CY		
0044	6036000000-E	1631	MATTING FOR EROSION CONTROL	455 SY		
004E	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
004E	6071030000-E	SP	COIR FIBER BAFFLES	230 LF		
0047	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
004E	6087000000-E	1660	MOWING	0.5 ACR		
004E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
005C	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0051	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0052	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0053	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0054	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		

County : Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
005E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+81.43 -L-)	Lump Sum	L.S.	
005E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (17+81.43 -L-)	Lump Sum	L.S.	
0057	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+81.43 -L-)	Lump Sum	L.S.	
005E	8364000000-E	450	HP12X53 STEEL PILES	720 LF		
005E	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	600 LF		
006C	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	267 TON		
0061	8765000000-N	SP	CONSTRUCTION OF SUBSTRUCTURE	Lump Sum	L.S.	
0062	8766000000-N	SP	CONSTRUCTION OF SUPERSTRUCTURE	Lump Sum	L.S.	
1332/Apr02/Q14633.95/D268455330000/E62			Total Amount Of Bid For Entire Project :			

Contract No: C201640

County: Sampson

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General