

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (22+70.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	100 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	65 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	40 TON		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	80 LF		
0012	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	56 LF		
0013	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	200 LF		
0014	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	20 LF		
0015	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0016	0995000000-E	340	PIPE REMOVAL	187 LF		
0017	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0018	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	185 SY		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1330000000-E	607	INCIDENTAL MILLING	300 SY		
0020	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	540 TON		
0021	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	130 TON		
0022	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	320 TON		
0023	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	65 TON		
0024	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	440 TON		
0025	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	80 TON		
0026	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	74 TON		
0027	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	5 TON		
0028	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	55 TON		
0029	2000000000-N	806	RIGHT OF WAY MARKERS	4 EA		
0030	2022000000-E	815	SUBDRAIN EXCAVATION	25 CY		
0031	2033000000-E	815	SUBDRAIN FINE AGGREGATE	20 CY		
0032	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0033	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0034	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0035	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0036	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2 EA		
0038	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0039	2556000000-E	846	SHOULDER BERM GUTTER	75 LF		
0040	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	120 LF		
0041	3030000000-E	862	STEEL BM GUARDRAIL	187.5 LF		
0042	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	100 LF		
0043	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0044	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0045	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0046	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0047	3566000000-E	867	WOVEN WIRE FENCE RESET	330 LF		
0048	3649000000-E	876	RIP RAP, CLASS B	10 TON		
0049	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	190 SY		
0050	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0051	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	439 SF		
0052	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	288 SF		
0053	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	119 SF		
0054	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0055	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	56 DAY		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4430000000-N	1130	DRUMS	80	EA	
0057	4445000000-E	1145	BARRICADES (TYPE III)	112	LF	
0058	4450000000-N	1150	FLAGGER	32	HR	
0059	4510000000-N	SP	POLICE	32	HR	
0060	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	12	EA	
0061	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	3,106	LF	
0062	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	3,679	LF	
0063	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	55	LF	
0064	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	117	LF	
0065	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	8	EA	
0066	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	1,845	LF	
0067	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	394	LF	
0068	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	108	LF	
0069	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	4	EA	
0070	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,851	LF	
0071	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	197	LF	
0072	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	52	LF	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	2 EA		
0074	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	45 EA		
0075	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0076	6000000000-E	1605	TEMPORARY SILT FENCE	1,090 LF		
0077	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	150 TON		
0078	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	255 TON		
0079	6012000000-E	1610	SEDIMENT CONTROL STONE	185 TON		
0080	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0081	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0082	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
0083	6024000000-E	1622	TEMPORARY SLOPE DRAINS	15 LF		
0084	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
0085	6029000000-E	SP	SAFETY FENCE	350 LF		
0086	6030000000-E	1630	SILT EXCAVATION	1,270 CY		
0087	6036000000-E	1631	MATTING FOR EROSION CONTROL	650 SY		
0088	6037000000-E	SP	COIR FIBER MAT	10 SY		
0089	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	265 SY		
0090	6071030000-E	SP	COIR FIBER BAFFLES	350 LF		
0091	6071050000-E	SP	*** SKIMMER (2")	1 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0093	6087000000-E	1660	MOWING	0.5 ACR		
0094	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0095	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0096	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0097	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0098	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0099	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		
0100	6123000000-E	1670	REFORESTATION	0.1 ACR		
0101	7060000000-E	1705	SIGNAL CABLE	170 LF		
0102	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	1 EA		
0103	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	1 EA		
0104	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	20 LF		
0105	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	1 EA		
0106	7420000000-E	1722	2" RISER WITH WEATHERHEAD	1 EA		
0107	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	60 LF		
0108	7456000000-E	1726	LEAD-IN CABLE (*****) (18-2)	380 LF		
0109	7636000000-N	1745	SIGN FOR SIGNALS	3 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>STRUCTURE ITEMS</b>						
0110	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (22+70.00-L-)	Lump Sum	L.S.	
0111	8096000000-E	SP	PILE EXCAVATION IN SOIL	77 LF		
0112	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	33 LF		
0113	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (22+70.00-L-)	Lump Sum	L.S.	
0114	8156000000-E	SP	CONCRETE WEARING SURFACE	2,787 SF		
0115	8161000000-E	420	GROOVING BRIDGE FLOORS	4,423 SF		
0116	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	42.4 CY		
0117	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (22+70.00-L-)	Lump Sum	L.S.	
0118	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,471 LB		
0119	8364000000-E	450	HP12X53 STEEL PILES	275 LF		
0120	8503000000-E	460	CONCRETE BARRIER RAIL	135.208 LF		
0121	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	277 TON		
0122	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	306 SY		
0123	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0124	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0125	8753000000-E	430	3'-0" X 2'-3" PRESTRESSED CONC BOX BEAMS	1,014.063 LF		
0126	8990000000-N	SP	CONTRACT TIME	1,000 DOL		

**Contract No: C201446**

**County: Wake**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General