

County : Edgcombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0004	0022000000-E	225	UNCLASSIFIED EXCAVATION	5,300 CY		
0005	0036000000-E	225	UNDERCUT EXCAVATION	3,000 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	3,630 TON		
0007	0106000000-E	230	BORROW EXCAVATION	15,500 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	688 CY		
0009	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	225 SY		
001C	0163000000-E	250	REMOVAL OF EXISTING CONCRETE PAVEMENT	45 SY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	8,000 SY		
0012	0199000000-E	SP	TEMPORARY SHORING	2,000 SF		
0013	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	510 TON		
0014	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	3,894 LF		
0015	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	742 LF		
0016	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	124 LF		
0017	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	12 LF		

County : Edgecombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0408000000-E	310	54" RC PIPE CULVERTS, CLASS III	12 LF		
001E	0995000000-E	340	PIPE REMOVAL	1,064 LF		
002C	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0021	1220000000-E	545	INCIDENTAL STONE BASE	630 TON		
0022	1330000000-E	607	INCIDENTAL MILLING	500 SY		
002E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	3,400 TON		
0024	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	10,400 TON		
002E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	775 TON		
002E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	150 TON		
0027	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
002E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
002E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
003C	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0031	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
003E	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
003E	2220000000-E	838	REINFORCED ENDWALLS	5 CY		
0034	2253000000-E	840	PIPE COLLARS	3.34 CY		
003E	2264000000-E	840	PIPE PLUGS	0.31 CY		

County : Edgcombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	52 EA		
0037	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	6 LF		
003E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	14 EA		
003E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	17 EA		
004C	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	21 EA		
0041	2514000000-E	842	CONCRETE BLOCK MASONRY RETAIN- ING WALLS	94 CY		
0042	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	13,600 LF		
0043	2612000000-E	848	6" CONCRETE DRIVEWAY	600 SY		
0044	2619000000-E	850	4" CONCRETE PAVED DITCH	75 SY		
004E	2830000000-N	858	ADJUSTMENT OF MANHOLES	2 EA		
004E	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	2 EA		
0047	3030000000-E	862	STEEL BM GUARDRAIL	875 LF		
004E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
004E	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	5 EA		
005C	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	10 EA		
0051	3360000000-E	863	REMOVE EXISTING GUARDRAIL	242 LF		
0052	3649000000-E	876	PLAIN RIP RAP, CLASS B	40 TON		
0053	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	390 SY		

County : Edgcombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0055	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	128 SF		
0056	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	200 SF		
0057	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	1 EA		
0058	4430000000-N	1130	DRUMS	100 EA		
0059	4450000000-N	1150	FLAGGER	4,000 HR		
0060	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0061	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	1 EA		
0062	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	250 LF		
0063	4505000000-E	1170	RESET PORTABLE CONCRETE BARRIER (ANCHORED)	125 LF		
0064	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	100 EA		
0065	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	100 LF		
0066	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	16,500 LF		
0067	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	750 LF		
0068	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	60 LF		
0069	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	90 EA		
0070	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	50,000 LF		

County : Edgcombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	60 LF		
0072	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	200 LF		
0073	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	400 EA		
0074	6000000000-E	1605	TEMPORARY SILT FENCE	8,800 LF		
0075	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	50 TON		
0076	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	50 TON		
0077	6012000000-E	1610	SEDIMENT CONTROL STONE	120 TON		
0078	6015000000-E	1615	TEMPORARY MULCHING	5 ACR		
0079	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	4,000 LB		
008C	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2 TON		
0081	6024000000-E	1622	TEMPORARY SLOPE DRAINS	100 LF		
0082	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	5 EA		
0083	6029000000-E	SP	SAFETY FENCE	500 LF		
0084	6030000000-E	1630	SILT EXCAVATION	450 CY		
0085	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,000 SY		
008E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	200 SY		
0087	6042000000-E	1632	1/4" HARDWARE CLOTH	1,200 LF		
008E	6070000000-N	SP	SPECIAL STILLING BASINS	2 EA		

County : Edgecombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	6084000000-E	1660	SEEDING & MULCHING	13 ACR		
0090	6087000000-E	1660	MOWING	13 ACR		
0091	6090000000-E	1661	SEED FOR REPAIR SEEDING	2,000 LB		
0092	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	2 TON		
0093	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	1,000 LB		
0094	6111000000-E	SP	IMPERVIOUS DIKE	150 LF		
0095	6114000000-N	SP	SPECIALIZED HAND MOWING	10 HR		
0096	6132000000-N	SP	GENERIC EROSION CONTROL ITEM RESPONSE FOR EROSION CONTROL	12 EA		

0806/May11/Q169572.65/D314639200000/E96

Total Amount Of Bid For Entire Project :

**Contract No: C201822**

**County: Edgecombe**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General

Signature Sheet (Bid - Acceptance by Department)