

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (21+09.46)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	600 CY		
000E	0063000000-N	SP	GRADING	Lump Sum	L.S.	
000E	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	100 TON		
0007	0106000000-E	230	BORROW EXCAVATION	5,550 CY		
000E	0134000000-E	240	DRAINAGE DITCH EXCAVATION	490 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
001C	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	30 TON		
0012	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	136 LF		
0013	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	48 LF		
0014	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
001E	0995000000-E	340	PIPE REMOVAL	100 LF		
001E	1220000000-E	545	INCIDENTAL STONE BASE	300 TON		
0017	1330000000-E	607	INCIDENTAL MILLING	120 SY		
001E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	630 TON		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,050 TON		
0020	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	420 TON		
0021	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	103 TON		
0022	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	12 TON		
0023	2000000000-N	806	RIGHT OF WAY MARKERS	19 EA		
0024	2022000000-E	815	SUBDRAIN EXCAVATION	112 CY		
0025	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84 CY		
0026	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0027	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
0028	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0029	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0030	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	6 EA		
0031	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	6 EA		
0032	2556000000-E	846	SHOULDER BERM GUTTER	230 LF		
0033	3030000000-E	862	STEEL BM GUARDRAIL	900 LF		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0035	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0036	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3642000000-E	876	RIP RAP, CLASS A	330 TON		
003E	3649000000-E	876	RIP RAP, CLASS B	210 TON		
0039	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,680 SY		
004C	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	384 SF		
0041	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0042	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	119 SF		
0043	4435000000-N	1135	CONES	30 EA		
0044	4450000000-N	1150	FLAGGER	272 HR		
004E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,800 LF		
004E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,800 LF		
0047	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	19 EA		
004E	6000000000-E	1605	TEMPORARY SILT FENCE	175 LF		
0049	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	210 TON		
005C	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	235 TON		
0051	6012000000-E	1610	SEDIMENT CONTROL STONE	185 TON		
0052	6015000000-E	1615	TEMPORARY MULCHING	4.5 ACR		
0053	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0054	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.75 TON		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	60 LF		
005E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0057	6029000000-E	SP	SAFETY FENCE	300 LF		
005E	6030000000-E	1630	SILT EXCAVATION	1,435 CY		
005E	6036000000-E	1631	MATTING FOR EROSION CONTROL	900 SY		
006C	6037000000-E	SP	COIR FIBER MAT	15 SY		
0061	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	900 SY		
0062	6042000000-E	1632	1/4" HARDWARE CLOTH	150 LF		
0063	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	30 SY		
0064	6071030000-E	SP	COIR FIBER BAFFLES	310 LF		
006E	6071050000-E	SP	*** SKIMMER (2")	2 EA		
006E	6084000000-E	1660	SEEDING & MULCHING	7.5 ACR		
0067	6087000000-E	1660	MOWING	2.5 ACR		
006E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
006E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
007C	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0071	6108000000-E	1665	FERTILIZER TOPDRESSING	3.5 TON		
0072	6114000000-N	SP	SPECIALIZED HAND MOWING	2.5 HR		
0073	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
--------	-------------	-------	-------------	----------	-----------	--------

***** BEGIN SCHEDULE AA *****
***** (3 ALTERNATES) *****

0074 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	80		LF
-------------	--------------	-----	---------------------------------	----	--	----

*** OR ***

0075 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	64		LF
-------------	--------------	-----	---------------------------------	----	--	----

0076 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	16		LF
-------------	--------------	----	-------------------------------	----	--	----

*** OR ***

0077 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	64		LF
-------------	--------------	-----	---------------------------------	----	--	----

0078 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	16		LF
-------------	--------------	----	--	----	--	----

***** END SCHEDULE AA *****

STRUCTURE ITEMS

0079	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (21 +09.45 -L-)	Lump Sum		L.S.
------	--------------	----	---	----------	--	------

008C	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (21 +09.45 -L-)	Lump Sum		L.S.
------	--------------	-----	---	----------	--	------

0081	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (21 +09.45 -L-)	Lump Sum		L.S.
------	--------------	-----	---	----------	--	------

0082	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	91.2		CY
------	--------------	-----	---------------------------	------	--	----

0083	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (21 +09.45 -L-)	Lump Sum		L.S.
------	--------------	-----	---	----------	--	------

0084	8217000000-E	425	REINFORCING STEEL (BRIDGE)	13,267		LB
------	--------------	-----	----------------------------	--------	--	----

0085	8364000000-E	450	HP12X53 STEEL PILES	550		LF
------	--------------	-----	---------------------	-----	--	----

0086	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	720		LF
------	--------------	-----	--------------------------------	-----	--	----

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0087	8391000000-N	450	STEEL PILE POINTS	24 EA		
008E	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	464.69 LF		
008E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	395 TON		
009C	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	440 SY		
0091	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0092	8753000000-E	430	3'-0" X 2'-3" PRESTRESSED CONC BOX BEAMS	3,252.81 LF		
1002/May30/Q46022.2/D372476380000/E92			Total Amount Of Bid For Entire Project :			

Contract No: C201644

County: Alamance

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General