

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (18 + 78.97)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	75 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	13 TON		
0010	0343000000-E	310	15" SIDE DRAIN PIPE	48 LF		
0011	0344000000-E	310	18" SIDE DRAIN PIPE	36 LF		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	28 LF		
0013	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	16 LF		
0014	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0015	0995000000-E	340	PIPE REMOVAL	48 LF		
0016	1121000000-E	520	AGGREGATE BASE COURSE	98 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	193 TON		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	252 TON		
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	25 TON		
0021	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		
0022	2000000000-N	806	RIGHT OF WAY MARKERS	5 EA		
0023	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		
0024	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8 CY		
0025	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0026	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0027	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0028	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0029	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0030	2355000000-N	840	FRAME WITH GRATE, STD 840.29	2 EA		
0031	2556000000-E	846	SHOULDER BERM GUTTER	120 LF		
0032	3030000000-E	862	STEEL BM GUARDRAIL	200 LF		
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0034	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0035	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0036	3649000000-E	876	RIP RAP, CLASS B	13 TON		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	570	SY	
003E	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (D)	16.6	SF	
003E	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	42.25	SF	
004C	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	173	LF	
0041	4096000000-N	904	SIGN ERECTION, TYPE D	2	EA	
0042	4102000000-N	904	SIGN ERECTION, TYPE E	13	EA	
0043	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	2	EA	
0044	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	13	EA	
004E	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	2	EA	
004E	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1	EA	
0047	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	344	SF	
004E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	84	SF	
004E	4445000000-E	1145	BARRICADES (TYPE III)	80	LF	
005C	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS)	3,400	LF	
0051	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	14	EA	
0052	6000000000-E	1605	TEMPORARY SILT FENCE	475	LF	
0053	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75	TON	

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	225 TON		
0055	6012000000-E	1610	SEDIMENT CONTROL STONE	310 TON		
0056	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0057	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0058	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0059	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
0060	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0061	6029000000-E	SP	SAFETY FENCE	150 LF		
0062	6030000000-E	1630	SILT EXCAVATION	500 CY		
0063	6036000000-E	1631	MATTING FOR EROSION CONTROL	285 SY		
0064	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	337 SY		
0065	6042000000-E	1632	1/4" HARDWARE CLOTH	240 LF		
0066	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
0067	6071030000-E	SP	COIR FIBER BAFFLES	215 LF		
0068	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0069	6087000000-E	1660	MOWING	1 ACR		
0070	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0071	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0072	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
0074	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
007E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		
0076	6123000000-E	1670	REFORESTATION	0.1 ACR		
<b>STRUCTURE ITEMS</b>						
0077	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (18 + 79.50-L-)	Lump Sum	L.S.	
007E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18 + 79.50-L-)	Lump Sum	L.S.	
0079	8105560000-E	SP	4'-0" DIA DRILLED PIERS IN SO IL	49.1 LF		
008C	8105660000-E	SP	4'-0" DIA DRILLED PIERS NOT IN SOIL	40 LF		
0081	8111600000-E	SP	PERMANENT STEEL CASING FOR 4'-0" DIA DRILLED PIER	50.1 LF		
0082	8113000000-N	SP	SID INSPECTION	2 EA		
0083	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0084	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	1,000 CY		
008E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	84.3 CY		
0086	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18 + 79.50-L-)	Lump Sum	L.S.	
0087	8217000000-E	425	REINFORCING STEEL (BRIDGE)	19,787 LB		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,939 LB		
008E	8364000000-E	450	HP12X53 STEEL PILES	295 LF		
009C	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	387.13 LF		
0091	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	688 TON		
0092	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	765 SY		
0093	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0094	8753000000-E	430	3'-0" X 2'-3" PRESTRESSED CONC BOX BEAMS	2,129.19 LF		

1506/Jun05/Q38107.47/D415037050000/E94

Total Amount Of Bid For Entire Project :

**Contract No: C201643**

**County: Johnston**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General