

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (22+03.60)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	350 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	250 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	250 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	23 TON		
0009	0343000000-E	310	15" SIDE DRAIN PIPE	20 LF		
0010	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	56 LF		
0011	0414000000-E	310	60" RC PIPE CULVERTS, CLASS III	80 LF		
0012	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	56 LF		
0013	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	4 EA		
0014	0995000000-E	340	PIPE REMOVAL	71 LF		
0015	1121000000-E	520	AGGREGATE BASE COURSE	1,210 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	420 TON		
0018	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	785 TON		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	570 TON		
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	90 TON		
0021	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	16 TON		
0022	2000000000-N	806	RIGHT OF WAY MARKERS	24 EA		
0023	2220000000-E	838	REINFORCED ENDWALLS	6 CY		
0024	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0025	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0026	2556000000-E	846	SHOULDER BERM GUTTER	90 LF		
0027	3030000000-E	862	STEEL BM GUARDRAIL	575 LF		
0028	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0029	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0030	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0031	3649000000-E	876	RIP RAP, CLASS B	3 TON		
0032	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	276 SY		
0033	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0034	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	32.25 SF		
0035	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	69 LF		
0036	4102000000-N	904	SIGN ERECTION, TYPE E	6 EA		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	12 EA		
0038	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	104 SF		
0039	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	144 SF		
0040	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	70 SF		
0041	4430000000-N	1130	DRUMS	123 EA		
0042	4445000000-E	1145	BARRICADES (TYPE III)	98 LF		
0043	4455000000-N	1150	FLAGGER	60 MD		
0044	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	114 EA		
0045	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	4,327 LF		
0046	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	4,319 LF		
0047	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	44 LF		
0048	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	17,277 LF		
0049	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	88 LF		
0050	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	31 EA		
0051	6000000000-E	1605	TEMPORARY SILT FENCE	3,585 LF		
0052	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	115 TON		
0053	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	455 TON		
0054	6012000000-E	1610	SEDIMENT CONTROL STONE	165 TON		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	6015000000-E	1615	TEMPORARY MULCHING	3.5 ACR		
0056	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0057	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0058	6024000000-E	1622	TEMPORARY SLOPE DRAINS	170 LF		
0059	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	5 EA		
0060	6029000000-E	SP	SAFETY FENCE	350 LF		
0061	6030000000-E	1630	SILT EXCAVATION	1,575 CY		
0062	6036000000-E	1631	MATTING FOR EROSION CONTROL	670 SY		
0063	6037000000-E	SP	COIR FIBER MAT	80 SY		
0064	6042000000-E	1632	1/4" HARDWARE CLOTH	80 LF		
0065	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	110 SY		
0066	6071030000-E	SP	COIR FIBER BAFFLES	470 LF		
0067	6071050000-E	SP	*** SKIMMER (2")	3 EA		
0068	6084000000-E	1660	SEEDING & MULCHING	4.5 ACR		
0069	6087000000-E	1660	MOWING	2 ACR		
0070	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0071	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0072	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0073	6108000000-E	1665	FERTILIZER TOPDRESSING	3.25 TON		
0074	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		
0076	6123000000-E	1670	REFORESTATION	0.28 ACR		
0077	6129000000-E	1670	WETLAND REFORESTATION	0.52 ACR		
0078	6135000000-E	SP	GENERIC EROSION CONTROL ITEM DISKING	0.52 ACR		
0079	6135000000-E	SP	GENERIC EROSION CONTROL ITEM RIPPING	0.52 ACR		
0080	6141000000-E	SP	GENERIC EROSION CONTROL ITEM LIVE STAKING	60 SY		
STRUCTURE ITEMS						
0081	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (22+03.60-L-)	Lump Sum	L.S.	
0082	8156000000-E	SP	CONCRETE WEARING SURFACE	4,902 SF		
0083	8161000000-E	420	GROOVING BRIDGE FLOORS	5,863 SF		
0084	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	54.4 CY		
0085	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (22+03.60-L-)	Lump Sum	L.S.	
0086	8217000000-E	425	REINFORCING STEEL (BRIDGE)	9,622 LB		
0087	8364000000-E	450	HP12X53 STEEL PILES	280 LF		
0088	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	280 LF		
0089	8391000000-N	450	STEEL PILE POINTS	16 EA		
0090	8503000000-E	460	CONCRETE BARRIER RAIL	300.54 LF		
0091	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	486 TON		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	540 SY		
0093	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0094	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0095	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,800 LF		
0802/Jun13/Q64612.03/D433860380000/E95			Total Amount Of Bid For Entire Project :			

Contract No: C201828

County: Nash

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General