

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0022000000-E	225	UNCLASSIFIED EXCAVATION	20,101 CY		
0005	0036000000-E	225	UNDERCUT EXCAVATION	240 CY		
0006	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	680 SY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	1,360 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,070 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	1,288 TON		
0010	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	3,044 LF		
0011	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	2,216 LF		
0012	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	752 LF		
0013	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	136 LF		
0014	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	76 LF		
0015	0995000000-E	340	PIPE REMOVAL	1,133 LF		
0016	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0017	1220000000-E	545	INCIDENTAL STONE BASE	495 TON		
0018	1245000000-E	SP	SHOULDER RECONSTRUCTION	9.2 SMI		
0019	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	6,510 TON		

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	2,830 TON		
0021	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	7,200 TON		
0022	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	845 TON		
0023	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	195 TON		
0024	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0025	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	4 EA		
0026	2612000000-E	848	6" CONCRETE DRIVEWAY	390 SY		
0027	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	950 SY		
0028	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
0029	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	49,130 LF		
0030	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	30,706 LF		
0031	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	52 EA		
0032	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	79,836 LF		
0033	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	310 EA		
0034	5325300000-E	1510	3" WATER LINE	130 LF		
0035	5325400000-E	1510	4" WATER LINE	105 LF		
0036	5325600000-E	1510	6" WATER LINE	1,245 LF		
0037	5325800000-E	1510	8" WATER LINE	300 LF		

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	5326200000-E	1510	12" WATER LINE	24,495.2		LF
0039	5534000000-E	1515	*** VALVE (3")	1		EA
0040	5538000000-E	1515	4" VALVE	1		EA
0041	5540000000-E	1515	6" VALVE	10		EA
0042	5546000000-E	1515	8" VALVE	3		EA
0043	5558000000-E	1515	12" VALVE	34		EA
0044	5571800000-E	1515	8" TAPPING VALVE	6		EA
0045	5572000000-E	1515	10" TAPPING VALVE	2		EA
0046	5648000000-N	1515	RELOCATE WATER METER	33		EA
0047	5649000000-N	1515	RECONNECT WATER METER	47		EA
0048	5672000000-N	1515	RELOCATE FIRE HYDRANT	8		EA
0049	6000000000-E	1605	TEMPORARY SILT FENCE	8,345		LF
0050	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	325		TON
0051	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	800		TON
0052	6012000000-E	1610	SEDIMENT CONTROL STONE	300		TON
0053	6015000000-E	1615	TEMPORARY MULCHING	24.5		ACR
0054	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	900		LB
0055	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	3.5		TON
0056	6029000000-E	SP	SAFETY FENCE	2,500		LF
0057	6030000000-E	1630	SILT EXCAVATION	2,325		CY

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	6036000000-E	1631	MATTING FOR EROSION CONTROL	4,600 SY		
0059	6042000000-E	1632	1/4" HARDWARE CLOTH	80 LF		
0060	6071030000-E	SP	COIR FIBER BAFFLES	3,000 LF		
0061	6084000000-E	1660	SEEDING & MULCHING	23.5 ACR		
0062	6090000000-E	1661	SEED FOR REPAIR SEEDING	250 LB		
0063	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5 TON		
0064	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	600 LB		
0065	6108000000-E	1665	FERTILIZER TOPDRESSING	17.5 TON		
0066	6114000000-N	SP	SPECIALIZED HAND MOWING	15 HR		
0067	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	15 EA		

0859/Jul13/Q262111.9/D251819230000/E67

Total Amount Of Bid For Entire Project :

2/16/99  
Z-13

**Contract No: C201079**

**County: Currituck**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General

Signature Sheet (Bid - Acceptance by Department)