

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION	12,100 CY		
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (26 + 10.31-NBL)	Lump Sum	L.S.	
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (26 + 29.70-SBL)	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	4,100 CY		
0007	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0008	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	2,000 TON		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	25 CY		
0010	0195000000-E	265	SELECT GRANULAR MATERIAL	2,000 CY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	4,000 SY		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	110 TON		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	780 LF		
0014	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	20 LF		
0015	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	228 LF		
0016	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0017	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1330000000-E	607	INCIDENTAL MILLING	2,530	SY	
001E	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	5,130	TON	
002C	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	4,680	TON	
0021	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	4,810	TON	
0022	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	441	TON	
0023	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	313	TON	
0024	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50	TON	
002E	2022000000-E	815	SUBDRAIN EXCAVATION	448	CY	
002E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	336	CY	
0027	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	2,000	LF	
002E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	60	EA	
002E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	4	EA	
003C	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	24	LF	
0031	2190000000-N	828	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	3	EA	
0032	2253000000-E	840	PIPE COLLARS	0.55	CY	
0033	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	13	EA	
0034	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	0.4	LF	

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	4 EA		
003E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	5 EA		
0037	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
003E	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	3 EA		
003E	2556000000-E	846	SHOULDER BERM GUTTER	200 LF		
004C	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	2 EA		
0041	3030000000-E	862	STEEL BM GUARDRAIL	2,637.5 LF		
0042	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	100 LF		
0043	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0044	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0045	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	3 EA		
004E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0047	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	8 EA		
004E	3360000000-E	863	REMOVE EXISTING GUARDRAIL	3,040 LF		
004E	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	1 EA		
005C	3595000000-E	869	RELAPPING GUARDRAIL	562.5 LF		
0051	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,250 SY		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0053	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	658 LF		
0054	4082000000-E	903	SUPPORTS, WOOD	2,520 LF		
005E	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
005E	4102000000-N	904	SIGN ERECTION, TYPE E	28 EA		
0057	4108000000-N	904	SIGN ERECTION, TYPE F	2 EA		
005E	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A & B)	35 EA		
005E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	36 EA		
006C	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	2 EA		
0061	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	3,472 SF		
0062	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	480 SF		
0063	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	106 SF		
0064	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
006E	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
006E	4430000000-N	1130	DRUMS	190 EA		
0067	4435000000-N	1135	CONES	100 EA		
006E	4445000000-E	1145	BARRICADES (TYPE III)	360 LF		
006E	4450000000-N	1150	FLAGGER	108 HR		
007C	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	4480000000-N	1165	TMIA	2	EA	
0072	4485000000-E	1170	PORTABLE CONCRETE BARRIER	2,000	LF	
0073	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	350	LF	
0074	4500000000-E	1170	RESET PORTABLE CONCRETE BAR- RIER	3,400	LF	
0075	4506000000-E	1170	RESET PORTABLE CONCRETE BAR- RIER (DRAINAGE)	350	LF	
0076	4516000000-N	1180	SKINNY DRUM	100	EA	
0077	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	1,006	EA	
007E	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	1,340	LF	
007E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	58,163	LF	
008C	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	308	LF	
0081	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	6	EA	
0082	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS)	15,856	LF	
0083	4847140000-E	1205	POLYUREA PAVEMENT MARKING LINES (24", *****) (STANDARD GLASS BEADS)	160	LF	
0084	4847220000-N	1205	POLYUREA PAVEMENT MARKING SYMBOL (*****) (STANDARD GLASS BEADS)	29	EA	
008E	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	10,818	LF	
008E	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	60	LF	

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0087	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	8 EA		
008E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	131 EA		
008E	5325200000-E	1510	2" WATER LINE	210 LF		
009C	5326200000-E	1510	12" WATER LINE	214 LF		
0091	5572200000-E	1515	12" TAPPING VALVE	1 EA		
0092	5804000000-E	1530	ABANDON 12" UTILITY PIPE	214 LF		
0093	6000000000-E	1605	TEMPORARY SILT FENCE	3,020 LF		
0094	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
009E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	235 TON		
009E	6012000000-E	1610	SEDIMENT CONTROL STONE	765 TON		
0097	6015000000-E	1615	TEMPORARY MULCHING	5.5 ACR		
009E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
009E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.75 TON		
010C	6024000000-E	1622	TEMPORARY SLOPE DRAINS	250 LF		
0101	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0102	6029000000-E	SP	SAFETY FENCE	550 LF		
0103	6030000000-E	1630	SILT EXCAVATION	1,350 CY		
0104	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,750 SY		
010E	6037000000-E	SP	COIR FIBER MAT	15 SY		

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0106	6042000000-E	1632	1/4" HARDWARE CLOTH	550	LF	
0107	6070000000-N	SP	SPECIAL STILLING BASINS	24	EA	
010E	6071030000-E	SP	COIR FIBER BAFFLES	300	LF	
0109	6071050000-E	SP	*** SKIMMER (1-1/2")	1	EA	
011C	6071050000-E	SP	*** SKIMMER (2-1/2")	1	EA	
0111	6084000000-E	1660	SEEDING & MULCHING	11	ACR	
0112	6087000000-E	1660	MOWING	3.5	ACR	
0113	6090000000-E	1661	SEED FOR REPAIR SEEDING	100	LB	
0114	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0115	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	125	LB	
0116	6108000000-E	1665	FERTILIZER TOPDRESSING	4.5	TON	
0117	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
011E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8	EA	

**WALL ITEMS**

0119	8436000000-E	453	GRAVITY RETAINING WALLS	245	SF	
------	--------------	-----	-------------------------	-----	----	--

**STRUCTURE ITEMS**

012C	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (26 + 20.00 -L- (LT. LN.)	Lump Sum	L.S.	
------	--------------	----	---	----------	------	--

County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0121	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (26 + 20.00 -L- (RT. LN.)	Lump Sum	L.S.	
0122	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (26 + 20.00 -L- (LT. LN.)	Lump Sum	L.S.	
0123	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (26 + 20.00 -L- (RT. LN.)	Lump Sum	L.S.	
0124	8105560000-E	SP	4'-0" DIA DRILLED PIERS IN SO IL	215.25 LF		
0125	8105660000-E	SP	4'-0" DIA DRILLED PIERS NOT IN SOIL	87 LF		
0126	8111600000-E	SP	PERMANENT STEEL CASING FOR 4'-0" DIA DRILLED PIER	61.42 LF		
0127	8113000000-N	SP	SID INSPECTION	4 EA		
0128	8114000000-N	SP	SPT TESTING	4 EA		
0129	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0130	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	2,300 CY		
0131	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	17,094 SF		
0132	8161000000-E	420	GROOVING BRIDGE FLOORS	17,416 SF		
0133	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	260.1 CY		
0134	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (26 + 20.00 -L- (LT. LN.)	Lump Sum	L.S.	
0135	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (26 + 20.00 -L- (RT. LN.)	Lump Sum	L.S.	
0136	8217000000-E	425	REINFORCING STEEL (BRIDGE)	66,764 LB		



County : Davidson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0137	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	11,696 LB		
0138	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	2,145 LF		
0139	8364000000-E	450	HP12X53 STEEL PILES	1,500 LF		
014C	8503000000-E	460	CONCRETE BARRIER RAIL	871.04 LF		
0141	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,976 TON		
0142	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	2,196 SY		
0143	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0144	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0756/Jul16/Q292172.26/D647538110000/E144			Total Amount Of Bid For Entire Project :			

**Contract No: C201601**

**County: Davidson**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General