

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000700000-N	SP	FIELD OFFICE	Lump Sum	L.S.	
0003	0000960000-E	SP	GENERIC MISCELLANEOUS ITEM SLOPE REPAIR	250 SY		
0004	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0005	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0015000000-N	205	SEALING ABANDONED WELLS	3 EA		
0007	0022000000-E	225	UNCLASSIFIED EXCAVATION	39,200 CY		
0008	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (70+22.00-L- LT)	Lump Sum	L.S.	
0009	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (70+22.00-L- RT)	Lump Sum	L.S.	
0010	0036000000-E	225	UNDERCUT EXCAVATION	4,900 CY		
0011	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	1,075 TON		
0012	0106000000-E	230	BORROW EXCAVATION	105,800 CY		
0013	0134000000-E	240	DRAINAGE DITCH EXCAVATION	1,400 CY		
0014	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	19,830 SY		
0015	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	5,890 SY		
0016	0195000000-E	265	SELECT GRANULAR MATERIAL	4,100 CY		
0017	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	4,500 SY		
0018	0199000000-E	SP	TEMPORARY SHORING	360 SF		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	945 TON		
0020	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (72", 0.138")	240 LF		
0021	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	224 LF		
0022	0654000000-E	310	**** X **** CS PIPE ARCH CULVERTS, ***** THICK (142" X 91", 0.138")	80 LF		
0023	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	584 LF		
0024	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	288 LF		
0025	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	92 LF		
0026	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	16 EA		
0027	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0028	0808000000-E	310	24" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0029	0995000000-E	340	PIPE REMOVAL	2,150 LF		
0030	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0031	1110000000-E	510	STABILIZER AGGREGATE	500 TON		
0032	1121000000-E	520	AGGREGATE BASE COURSE	29,620 TON		
0033	1220000000-E	545	INCIDENTAL STONE BASE	235 TON		
0034	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	13,520 SY		
0035	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/4")	180 SY		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 3-1/2")	3,820 SY		
0037	1330000000-E	607	INCIDENTAL MILLING	500 SY		
0038	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	3,340 TON		
0039	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	14,730 TON		
0040	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	3,970 TON		
0041	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	14,780 TON		
0042	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	3,390 TON		
0043	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	14,860 TON		
0044	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,883 TON		
0045	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	966 TON		
0046	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	140 TON		
0047	2000000000-N	806	RIGHT OF WAY MARKERS	23 EA		
0048	2022000000-E	815	SUBDRAIN EXCAVATION	306 CY		
0049	2033000000-E	815	SUBDRAIN FINE AGGREGATE	230 CY		
0050	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,350 LF		
0051	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	39 EA		
0052	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0054	2190000000-N	828	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	4 EA		
0055	2253000000-E	840	PIPE COLLARS	3.553 CY		
0056	2264000000-E	840	PIPE PLUGS	1.18 CY		
0057	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	107 EA		
0058	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	18.86 LF		
0059	2352000000-N	840	FRAME WITH GRATE, STD 840.**** (840.16)	17 EA		
0060	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	13 EA		
0061	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	25 EA		
0062	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	8 EA		
0063	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	14 EA		
0064	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	21 EA		
0065	2396000000-N	840	FRAME WITH COVER, STD 840.54	7 EA		
0066	2418000000-E	SP	FRAME WITH GRATES, DRIVEWAY DROP INLET	26 LF		
0067	2535000000-E	846	***X *** CONCRETE CURB (8" X 18")	1,500 LF		
0068	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	8,670 LF		
0069	2556000000-E	846	SHOULDER BERM GUTTER	2,510 LF		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0070	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	480 LF		
0071	2580000000-E	846	CONCRETE VALLEY GUTTER	150 LF		
0072	2591000000-E	848	4" CONCRETE SIDEWALK	2,690 SY		
0073	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	30 EA		
0074	2612000000-E	848	6" CONCRETE DRIVEWAY	130 SY		
0075	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	2,370 SY		
0076	2815000000-N	858	ADJUSTMENT OF DROP INLETS	7 EA		
0077	2830000000-N	858	ADJUSTMENT OF MANHOLES	1 EA		
0078	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	4 EA		
0079	3030000000-E	862	STEEL BM GUARDRAIL	3,612.5 LF		
0080	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50 LF		
0081	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0082	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0083	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	2 EA		
0084	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	16 EA		
0085	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	9 EA		
0086	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	4 EA		
0087	3360000000-E	863	REMOVE EXISTING GUARDRAIL	3,493 LF		
0088	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	1,900 LF		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (CAT-1)	1 EA		
0090	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	5 EA		
0091	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	9 EA		
0092	3524000000-E	SP	VINYL COATED CHAIN LINK FENCE, *** FABRIC (60")	1,740 LF		
0093	3539000000-E	866	METAL LINE POSTS FOR *** CHAIN LINK FENCE (60")	476 EA		
0094	3545000000-E	866	METAL TERMINAL POSTS FOR *** CHAIN LINK FENCE (60")	6 EA		
0095	3595000000-E	869	RELAPPING GUARDRAIL	1,188 LF		
0096	3628000000-E	876	RIP RAP, CLASS I	98 TON		
0097	3642000000-E	876	RIP RAP, CLASS A	55 TON		
0098	3649000000-E	876	RIP RAP, CLASS B	118 TON		
0099	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	3,997 SY		
0100	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	15 EA		
0101	4048000000-E	902	REINFORCED CONCRETE SIGN FOUN- DATIONS	2 CY		
0102	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	1,119 LB		
0103	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	1,101 LF		
0104	4096000000-N	904	SIGN ERECTION, TYPE D	7 EA		
0105	4102000000-N	904	SIGN ERECTION, TYPE E	44 EA		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0106	4108000000-N	904	SIGN ERECTION, TYPE F	2 EA		
0107	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (A)	2 EA		
0108	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (B)	1 EA		
0109	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	1 EA		
0110	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	3 EA		
0111	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (F)	1 EA		
0112	4138000000-N	907	DISPOSAL OF SUPPORT, STEEL BEAM	6 EA		
0113	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	50 EA		
0114	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	7 EA		
0115	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	624 SF		
0116	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	1,002 SF		
0117	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	204 SF		
0118	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	8 EA		
0119	4430000000-N	1130	DRUMS	570 EA		
0120	4435000000-N	1135	CONES	100 EA		
0121	4445000000-E	1145	BARRICADES (TYPE III)	362 LF		
0122	4450000000-N	1150	FLAGGER	832 HR		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0123	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	5 EA		
0124	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	9 EA		
0125	4480000000-N	1165	TMIA	2 EA		
0126	4485000000-E	1170	PORTABLE CONCRETE BARRIER	80 LF		
0127	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	2,350 LF		
0128	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	5,490 LF		
0129	4500000000-E	1170	RESET PORTABLE CONCRETE BAR- RIER	8,414 LF		
0130	4510000000-N	SP	POLICE	88 HR		
0131	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	1,316 EA		
0132	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	25,639 LF		
0133	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	24,532 LF		
0134	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	100 LF		
0135	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	33 LF		
0136	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	710 LF		
0137	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	788 LF		
0138	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	119 EA		
0139	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (TYPE 2)	1,571 LF		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0140	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	192,684 LF		
0141	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	400 LF		
0142	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	550 LF		
0143	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,938 LF		
0144	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	216 EA		
0145	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	17,225 LF		
0146	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	255 LF		
0147	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	27 EA		
0148	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	1,213 EA		
0149	4915000000-E	1264	7' U-CHANNEL POSTS	6 EA		
0150	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	6 EA		
0151	5010000000-E	1401	100' HIGH MOUNT STANDARD	4 EA		
0152	5020000000-N	1401	PORTABLE DRIVE UNIT	1 EA		
0153	5025000000-E	1402	HIGH MOUNT FOUNDATIONS	28 CY		
0154	5030000000-N	1403	HIGH MOUNT LUMINAIRES ***** (750W HPS)	24 EA		
0155	5120000000-N	1407	ELECTRIC SERVICE POLE **** ***** (30' CLASS 4)	1 EA		
0156	5125000000-E	1407	ELECTRIC SERVICE LATERAL ***** (3 #1/0 USE)	60 LF		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0157	5145000000-N	1408	LIGHT CONTROL EQUIPMENT, TYPE RW ***** (240/480 VOLT)	1 EA		
0158	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (2")	660 LF		
0159	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (4")	360 LF		
0160	5170000000-E	1410	** #8 W/G FEEDER CIRCUIT (2)	451 LF		
0161	5175000000-E	1410	** #6 W/G FEEDER CIRCUIT (2)	691 LF		
0162	5180000000-E	1410	** #4 W/G FEEDER CIRCUIT (2)	484 LF		
0163	5205000000-E	1410	** #8 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1-1/2")	1,038 LF		
0164	5210000000-E	1410	** #6 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1-1/2")	820 LF		
0165	5215000000-E	1410	** #4 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1-1/2")	143 LF		
0166	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC18)	9 EA		
0167	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0168	5325400000-E	1510	4" WATER LINE	25 LF		
0169	5325600000-E	1510	6" WATER LINE	10 LF		
0170	5326600000-E	1510	16" WATER LINE	236 LF		
0171	5558600000-E	1515	16" VALVE	1 EA		
0172	5648000000-N	1515	RELOCATE WATER METER	6 EA		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0173	5672000000-N	1515	RELOCATE FIRE HYDRANT	3 EA		
0174	5810000000-E	1530	ABANDON 16" UTILITY PIPE	450 LF		
0175	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE EXT 4" WATER METER ASSEMBLY W/ NEW 6' X 8' METER VAULT	1 EA		
0176	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE EXT 6" WATER METER ASSEMBLY W/ NEW 6' X 10' METER VAULT	1 EA		
0177	5888000000-E	SP	GENERIC UTILITY ITEM 20" HDPE WATER PIPE, SDR 9, 200 # WP BY DIRECTIONAL BORE	230 LF		
0178	6000000000-E	1605	TEMPORARY SILT FENCE	14,090 LF		
0179	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	470 TON		
0180	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	2,170 TON		
0181	6012000000-E	1610	SEDIMENT CONTROL STONE	2,100 TON		
0182	6015000000-E	1615	TEMPORARY MULCHING	28.5 ACR		
0183	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	1,050 LB		
0184	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	4.25 TON		
0185	6024000000-E	1622	TEMPORARY SLOPE DRAINS	400 LF		
0186	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	10 EA		
0187	6029000000-E	SP	SAFETY FENCE	3,200 LF		
0188	6030000000-E	1630	SILT EXCAVATION	8,415 CY		
0189	6036000000-E	1631	MATTING FOR EROSION CONTROL	6,910 SY		
0190	6042000000-E	1632	1/4" HARDWARE CLOTH	2,280 LF		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0191	6069000000-E	1638	STILLING BASINS	90 CY		
0192	6070000000-N	SP	SPECIAL STILLING BASINS	24 EA		
0193	6071030000-E	SP	COIR FIBER BAFFLES	2,050 LF		
0194	6084000000-E	1660	SEEDING & MULCHING	34 ACR		
0195	6087000000-E	1660	MOWING	16.5 ACR		
0196	6090000000-E	1661	SEED FOR REPAIR SEEDING	350 LB		
0197	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1 TON		
0198	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	675 LB		
0199	6108000000-E	1665	FERTILIZER TOPDRESSING	25.25 TON		
0200	6111000000-E	SP	IMPERVIOUS DIKE	260 LF		
0201	6114000000-N	SP	SPECIALIZED HAND MOWING	14 HR		
0202	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	44 EA		
0203	6123000000-E	1670	REFORESTATION	3.05 ACR		
0204	7000000000-E	1705	PEDESTRIAN SIGNAL HEAD (***, ** SECTION) (16", 1 SECTION W/COUNTDOWN)	6 EA		
0205	7060000000-E	1705	SIGNAL CABLE	8,870 LF		
0206	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	48 EA		
0207	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	3 EA		
0208	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	14 EA		
0209	7180000000-N	1706	BACKPLATE	17 EA		
0210	7264000000-E	1710	MESSENGER CABLE (3/8")	2,710 LF		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0211	7279000000-E	1715	TRACER WIRE	1,771 LF		
0212	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	560 LF		
0213	7300000000-E	1715	UNPAVED TRENCHING (***** (2, 2")	1,050 LF		
0214	7301000000-E	1715	DIRECTIONAL DRILL (***** (1, 2")	1,721 LF		
0215	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	14 EA		
0216	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEA- VY DUTY)	4 EA		
0217	7360000000-N	1720	WOOD POLE	2 EA		
0218	7372000000-N	1721	GUY ASSEMBLY	4 EA		
0219	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0220	7420000000-E	1722	2" RISER WITH WEATHERHEAD	2 EA		
0221	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	6,075 LF		
0222	7456000000-E	1726	LEAD-IN CABLE (***** (18-2)	5,000 LF		
0223	7456000000-E	1726	LEAD-IN CABLE (***** (18-4)	3,290 LF		
0224	7516000000-E	1730	COMMUNICATIONS CABLE (**FIBER) (12)	1,921 LF		
0225	7552000000-N	1731	INTERCONNECT CENTER	1 EA		
0226	7564100000-N	1732	FIBER-OPTIC TRANSCEIVER, SELF- HEALING RING	1 EA		
0227	7566000000-N	1733	DELINEATOR MARKER	2 EA		
0228	7575160000-E	1734	REMOVE EXISTING COMMUNICATIONS CABLE	1,677 LF		
0229	7576000000-N	SP	METAL STRAIN SIGNAL POLE	12 EA		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0230	7613000000-N	SP	SOIL TEST	12	EA	
0231	7614100000-E	SP	DRILLED PIER FOUNDATION	72	CY	
0232	7636000000-N	1745	SIGN FOR SIGNALS	12	EA	
0233	7744000000-N	1751	DETECTOR CARD (TYPE 170)	7	EA	
0234	7816000000-N	1751	DETECTOR CARD (NEMA TS-1)	4	EA	
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0235	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	4,608	LF	
AA1						
0236	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	958	LF	
AA1						
0237	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	784	LF	
AA1						
0238	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	656	LF	
AA1						
*** OR ***						
0239	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	4,452	LF	
AA2						
0240	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	834	LF	
AA2						
0241	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	760	LF	
AA2						
0242	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	560	LF	
AA2						
0243	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	156	LF	
AA2						
0244	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	124	LF	
AA2						
0245	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	24	LF	
AA2						

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0246 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (30")	96 LF		
*** OR ***						
0247 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	4,452 LF		
0248 AA3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	834 LF		
0249 AA3	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	760 LF		
0250 AA3	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	560 LF		
0251 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	156 LF		
0252 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18", 0.064")	124 LF		
0253 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24", 0.064")	24 LF		
0254 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (30", 0.064")	96 LF		
***** END SCHEDULE AA *****						
CULVERT ITEMS						
0255	8126000000-N	414	CULVERT EXCAVATION, STA ***** (77+89.00 -L-)	Lump Sum	L.S.	
0256	8133000000-E	414	FOUNDATION CONDITIONING MATER- IAL, BOX CULVERT	109 TON		
0257	8196000000-E	420	CLASS A CONCRETE (CULVERT)	183.3 CY		
0258	8245000000-E	425	REINFORCING STEEL (CULVERT)	32,175 LB		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0259	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (22+37.00 -L-)	Lump Sum	L.S.	
0260	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (70+22.00 -L- LEFT LANE)	Lump Sum	L.S.	
0261	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (14+31.00 -L-)	Lump Sum	L.S.	
0262	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+31.00 -L-)	Lump Sum	L.S.	
0263	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (22+37.00 -L-)	Lump Sum	L.S.	
0264	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (70+22.00 -L- LEFT LANE)	Lump Sum	L.S.	
0265	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (70+22.00 -L- RIGHT LANE)	Lump Sum	L.S.	
0266	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	531.6 LF		
0267	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	199.5 LF		
0268	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	321.05 LF		
0269	8113000000-N	SP	SID INSPECTION	3 EA		
0270	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0271	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	19,076 CY		
0272	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	34,902 SF		
0273	8156000000-E	SP	CONCRETE WEARING SURFACE	8,957 SF		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0274	8161000000-E	420	GROOVING BRIDGE FLOORS	48,704 SF		
0275	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	111.2 CY		
0276	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	569.6 CY		
0277	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+31.00 -L-)	Lump Sum	L.S.	
0278	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (22+37.00 -L-)	Lump Sum	L.S.	
0279	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (70+22.00 -L- LEFT LANE)	Lump Sum	L.S.	
0280	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (70+22.00 -L- RIGHT LANE)	Lump Sum	L.S.	
0281	8217000000-E	425	REINFORCING STEEL (BRIDGE)	124,285 LB		
0282	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	2,951 LB		
0283	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	21,228 LB		
0284	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	1,068,000 LS		
0285	8364000000-E	450	HP12X53 STEEL PILES	2,160 LF		
0286	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	960 LF		
0287	8475000000-E	460	TWO BAR METAL RAIL	1,161.08 LF		
0288	8482000000-E	460	THREE BAR METAL RAIL	360.4 LF		
0289	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" x 2'-6")	1,191.54 LF		
0290	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	2,404 TON		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0291	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	2,674 SY		
0292	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0293	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0294	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	3,901.67 LF		
0295	8860000000-N	SP	GENERIC STRUCTURE ITEM TEMPORARY STRUCTURE DRAINAGE SYSTEM AT STA 70+22.00 -L- RIG HT LANE	Lump Sum	L.S.	
1107/Jul19/Q2111259.283/D1286491730000/E295			Total Amount Of Bid For Entire Project :			

Contract No: C201487

County: Durham

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General