

County : Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	6,377 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	2,283 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	46.25 SMI		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	1,662 SY		
0006	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2")	7,304 SY		
0007	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	61,543 SY		
0008	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (1/2" TO 1-1/4")	299,200 SY		
0009	1330000000-E	607	INCIDENTAL MILLING	2,475 SY		
0010	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	2,649 TON		
0011	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	10,112 TON		
0012	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	4,908 TON		
0013	1539000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S12.5C	73,055 TON		
0014	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	590 TON		
0015	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	4,312 TON		
0016	1570000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 76-22	1,056 TON		
0017	1663000000-E	650	OPEN-GRADED ASPHALT FRICTION COURSE, TYPE FC-2 MODIFIED	17,598 TON		

County : Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	179,520 LF		
0019	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (FULL DEPTH)	995 TON		
0020	1880000000-E	SP	GENERIC PAVING ITEM WEDGING EXISTING PAVEMENT	36 TON		
0021	2612000000-E	848	6" CONCRETE DRIVEWAY	70 SY		
0022	3030000000-E	862	STEEL BM GUARDRAIL	50 LF		
0023	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	25 EA		
0024	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	20 EA		
0025	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	12 EA		
0026	3345000000-E	864	REMOVE & RESET EXISTING GUARD- RAIL	187.5 LF		
0027	3420000000-E	SP	GENERIC GUARDRAIL ITEM REPAIR STEEL BEAM GUARDRAIL	400 LF		
0028	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0029	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
0030	4480000000-N	1165	TMIA	2 EA		
0031	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	34,537 LF		
0032	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	24,962 LF		
0033	4702000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 120 MILS)	125 LF		
0034	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	40 LF		

County : Sampson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	9 EA		
0036	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	8 EA		
0037	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	545,453 LF		
0038	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	6,625 LF		
0039	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	40 LF		
0040	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	8 EA		
0041	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (HIGHLY REFLECTIVE ELEMENTS)	237,380 LF		
0042	4847110000-E	1205	POLYUREA PAVEMENT MARKING LINES (8", *****) (HIGHLY REFLECTIVE ELEMENTS)	6,010 LF		
0043	4895000000-N	SP	GENERIC PAVEMENT MARKING ITEM MARKERS FOR SHOULDER DRAINS	128 EA		
0044	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	2,244 EA		
0045	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,626 EA		
0046	6000000000-E	1605	TEMPORARY SILT FENCE	700 LF		
0047	6015000000-E	1615	TEMPORARY MULCHING	7 ACR		
0048	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	350 LB		
0049	6084000000-E	1660	SEEDING & MULCHING	23.24 ACR		
0050	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	1 EA		
0051	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	400 LF		

**Contract No: C201799**

**County: Sampson**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General