

County : Vance, Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0036000000-E	225	UNDERCUT EXCAVATION	350 CY		
0003	0170000000-E	SP	REMOVAL OF EXISTING CONCRETE PAVEMENT SLABS	3,300 SY		
0004	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,000 SY		
0005	1022000000-E	SP	SEALING EXISTING PAVEMENT CRACKS	400,000 LB		
0006	1121000000-E	520	AGGREGATE BASE COURSE	675 TON		
0007	1245000000-E	SP	SHOULDER RECONSTRUCTION	40 SMI		
0008	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (4")	98,891 SY		
0009	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (5")	98,891 SY		
0010	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	8,435 SY		
0011	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	2,260 TON		
0012	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	33,480 TON		
0013	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	16,200 TON		
0014	1520000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE)	1,540 TON		
0015	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	2,736 TON		
0016	1567000000-E	SP	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-28	1,030 TON		
0017	1704000000-E	SP	PATCHING EXISTING PAVEMENT	670 TON		

County : Vance, Warren

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1839110000-E	661	ULTRATHIN HOT MIX ASPHALT, TYPE B	19,720 TON		
0019	1839200000-E	661	APPLICATION OF ULTRATHIN HOT MIX ASPHALT	563,200 SY		
0020	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	422,400 LF		
0021	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
0022	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	211,200 LF		
0023	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	264,000 LF		
0024	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	8,000 LF		
0025	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	4,500 LF		
0026	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	500 LF		
0027	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	654,000 LF		
0028	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	400 EA		
0029	6084000000-E	1660	SEEDING & MULCHING	5 ACR		

0902/Jul11/Q2817425.0/D68198410000/E29

Total Amount Of Bid For Entire Project :

**Contract No: C201780**

**Counties: Vance, Warren**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General

Signature Sheet (Bid - Acceptance by Department)