

County : Jackson, Swain

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	147,000 CY		
0006	0036000000-E	225	UNDERCUT EXCAVATION	16 CY		
0007	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	5,179 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	67 TON		
0009	0995000000-E	340	PIPE REMOVAL	239 LF		
0010	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0011	1121000000-E	520	AGGREGATE BASE COURSE	3,570 TON		
0012	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0013	1275000000-E	600	PRIME COAT	2,169 GAL		
0014	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2")	4,264 SY		
0015	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,060 TON		
0016	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,840 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	165 TON		
0018	2264000000-E	840	PIPE PLUGS	0.05 CY		
0019	2275000000-E	SP	FLOWABLE FILL	16 CY		

County : Jackson, Swain

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	8 EA		
0021	2354000000-N	840	FRAME WITH GRATE, STD 840.22	1 EA		
0022	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2 EA		
0023	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	2 EA		
0024	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	2 EA		
0025	2396000000-N	840	FRAME WITH COVER, STD 840.54	2 EA		
0026	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	2,102 LF		
0027	2591000000-E	848	4" CONCRETE SIDEWALK	820 SY		
0028	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	1 EA		
0029	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	3 EA		
0030	2830000000-N	858	ADJUSTMENT OF MANHOLES	1 EA		
0031	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	3 EA		
0032	2860000000-N	859	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX	1 EA		
0033	3030000000-E	862	STEEL BM GUARDRAIL	103.75 LF		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0035	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		
0036	3345000000-E	864	REMOVE & RESET EXISTING GUARDRAIL	240 LF		
0037	3972000000-E	SP	#57 STONE BACKFILL	150 TON		

County : Jackson, Swain

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	28 SF		
0039	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	297.5 SF		
0040	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	40 SF		
0041	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	93 SF		
0042	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0043	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
0044	4430000000-N	1130	DRUMS	100 EA		
0045	4445000000-E	1145	BARRICADES (TYPE III)	60 LF		
0046	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0047	4480000000-N	1165	TMIA	1 EA		
0048	4485000000-E	1170	PORTABLE CONCRETE BARRIER	1,320 LF		
0049	4500000000-E	1170	RESET PORTABLE CONCRETE BAR- RIER	1,320 LF		
0050	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	7,179 LF		
0051	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	779 LF		
0052	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	66 LF		
0053	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	3 EA		
0054	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	3,434 LF		
0055	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	66 LF		

County : Jackson, Swain

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	7 EA		
0057	5055000000-N	1404	LIGHT STANDARD, TYPE MISC ***** (SA, 35', 12')	7 EA		
0058	5055000000-N	1404	LIGHT STANDARD, TYPE MISC ***** (SA, 35', 8')	4 EA		
0059	5070000000-N	1405	STANDARD FOUNDATION ***** (R1)	11 EA		
0060	5080000000-N	1406	LIGHT STANDARD LUMINAIRES, TYPE ***** (TYPE RDW 250W HPS)	11 EA		
0061	5205000000-E	1410	** #8 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1-1/2")	1,250 LF		
0062	5270000000-N	SP	GENERIC LIGHTING ITEM CONNECTION TO DPC ELECTRICAL SERVICE	2 EA		
0063	5270000000-N	SP	GENERIC LIGHTING ITEM REMOVE LIGHT STANDARD	6 EA		
0064	5270000000-N	SP	GENERIC LIGHTING ITEM REMOVE LIGHT STANDARD FOUNDATION	6 EA		
0065	5801000000-E	1530	ABANDON 8" UTILITY PIPE	976 LF		
0066	5816000000-N	1530	ABANDON UTILITY MANHOLE	5 EA		
0067	6000000000-E	1605	TEMPORARY SILT FENCE	1,325 LF		
0068	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	0.5 TON		
0069	6012000000-E	1610	SEDIMENT CONTROL STONE	15.92 TON		
0070	6042000000-E	1632	1/4" HARDWARE CLOTH	205 LF		
0071	6084000000-E	1660	SEEDING & MULCHING	1.6 ACR		
0072	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		

County : Jackson, Swain

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.1 TON		
0074	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	162 LF		
0075	7456000000-E	1726	LEAD-IN CABLE (***** (18-2)	30 LF		
0076	7960000000-N	SP	METAL POLE FOUNDATION REMOVAL	6 EA		
0077	7972000000-N	SP	METAL POLE REMOVAL	6 EA		
0078	8096000000-E	SP	PILE EXCAVATION IN SOIL	522 LF		
0079	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	13 LF		
0080	8203000000-E	420	CLASS A CONCRETE (RETAINING WALL)	29.3 CY		
0081	8252000000-E	425	REINFORCING STEEL (RETAINING WALL)	41,206 LB		
0082	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	110,600 LS		
0083	8590000000-E	876	RIP RAP, CLASS ** (II)	7,650 TON		
0084	8839000000-E	SP	GENERIC RETAINING WALL ITEM GROUND ANCHORS	1,035 LF		
0085	8839000000-E	SP	GENERIC RETAINING WALL ITEM HP12X53 GALVANIZED STEEL PILES (RETAINING WALL)	1,204 LF		
0086	8839000000-E	SP	GENERIC RETAINING WALL ITEM TIE BACKS	1,710 LF		
0087	8839000000-E	SP	GENERIC RETAINING WALL ITEM W6X8.5 STEEL PILES	770 LF		
0088	8853000000-E	SP	GENERIC RETAINING WALL ITEM CLASS AA CONCRETE	399.8 CY		
0089	8853000000-E	SP	GENERIC RETAINING WALL ITEM DRILLED PIER CONCRETE ENCASE- MENT	48.3 CY		

County : Jackson, Swain

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0090	8853000000-E	SP	GENERIC RETAINING WALL ITEM TREATED STRUCTURAL TIMBER	170.7 CY		
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0091 AA1	0360000000-E	310	12" RC PIPE CULVERTS, CLASS III	417 LF		
0092 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	215 LF		
*** OR ***						
0093 AA2	0360000000-E	310	12" RC PIPE CULVERTS, CLASS III	362 LF		
0094 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	205 LF		
0095 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (12")	55 LF		
0096 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	10 LF		
*** OR ***						
0097 AA3	0360000000-E	310	12" RC PIPE CULVERTS, CLASS III	362 LF		
0098 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	205 LF		
0099 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (12", 0.064")	55 LF		
0100 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (15", 0.064")	10 LF		
***** END SCHEDULE AA *****						

Contract No: C201514

County: Jackson / Swain

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General