

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (19 + 59.00)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	550 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	200 TON		
0007	0106000000-E	230	BORROW EXCAVATION	3,950 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	260 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	85 TON		
0012	0344000000-E	310	18" SIDE DRAIN PIPE	84 LF		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	20 LF		
0014	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	4 LF		
0015	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	100 LF		
0016	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	12 LF		
0017	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK (15", 0.064")	2 EA		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0995000000-E	340	PIPE REMOVAL	158 LF		
001E	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
002C	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,925 TON		
0021	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	375 TON		
0022	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	600 TON		
0023	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	137 TON		
0024	2000000000-N	806	RIGHT OF WAY MARKERS	16 EA		
002E	2253000000-E	840	PIPE COLLARS	1 CY		
002E	2264000000-E	840	PIPE PLUGS	0.5 CY		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
002E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
002E	2556000000-E	846	SHOULDER BERM GUTTER	25 LF		
003C	2612000000-E	848	6" CONCRETE DRIVEWAY	70 SY		
0031	2995000000-N	SP	GENERIC DRAINAGE ITEM ADJUST EXT JUNCTION BOX WITH MANHOLE	1 EA		
0032	3030000000-E	862	STEEL BM GUARDRAIL	150 LF		
003E	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	62.5 LF		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
003E	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0037	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
003E	3649000000-E	876	RIP RAP, CLASS B	10 TON		
003E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	296 SY		
004C	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	431 SF		
0041	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	144 SF		
0042	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	70 SF		
0043	4435000000-N	1135	CONES	30 EA		
0044	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
004E	4455000000-N	1150	FLAGGER	90 MD		
004E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	9,080 LF		
0047	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	69 LF		
004E	5325600000-E	1510	6" WATER LINE	1,050 LF		
004E	5325800000-E	1510	8" WATER LINE	67 LF		
005C	5540000000-E	1515	6" VALVE	1 EA		
0051	5546000000-E	1515	8" VALVE	1 EA		
0052	5649000000-N	1515	RECONNECT WATER METER	3 EA		
0053	5666000000-E	1515	FIRE HYDRANT	1 EA		
0054	5691300000-E	1520	8" SANITARY GRAVITY SEWER	107 LF		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	5691700000-E	1520	18" SANITARY GRAVITY SEWER	85	LF	
005E	5775000000-E	1525	4' DIA UTILITY MANHOLE	2	EA	
0057	5800000000-E	1530	ABANDON 6" UTILITY PIPE	1,056	LF	
005E	5801000000-E	1530	ABANDON 8" UTILITY PIPE	240	LF	
005E	5811000000-E	1530	ABANDON 18" UTILITY PIPE	85	LF	
006C	5816000000-N	1530	ABANDON UTILITY MANHOLE	1	EA	
0061	5828000000-N	1530	REMOVE UTILITY MANHOLE	1	EA	
0062	5871910000-E	1550	TRENCHLESS INSTALLATION OF 16" NOT IN SOIL	40	LF	
006E	6000000000-E	1605	TEMPORARY SILT FENCE	925	LF	
0064	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	205	TON	
006E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	230	TON	
006E	6012000000-E	1610	SEDIMENT CONTROL STONE	135	TON	
0067	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
006E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
006E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25	TON	
007C	6029000000-E	SP	SAFETY FENCE	250	LF	
0071	6030000000-E	1630	SILT EXCAVATION	1,340	CY	
0072	6036000000-E	1631	MATTING FOR EROSION CONTROL	530	SY	
007E	6037000000-E	SP	COIR FIBER MAT	20	SY	

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	770	SY	
0075	6071030000-E	SP	COIR FIBER BAFFLES	270	LF	
0076	6071050000-E	SP	*** SKIMMER (1-1/2")	3	EA	
0077	6084000000-E	1660	SEEDING & MULCHING	2	ACR	
0078	6087000000-E	1660	MOWING	1	ACR	
0079	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0080	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0081	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0082	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5	TON	
0083	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
0084	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8	EA	

STRUCTURE ITEMS

0085	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (19 + 59.00 -L-)	Lump Sum	L.S.	
0086	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (19 + 59.00 -L-)	Lump Sum	L.S.	
0087	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	3,732	SF	
0088	8161000000-E	420	GROOVING BRIDGE FLOORS	5,047	SF	
0089	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	38.2	CY	

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
009C	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (19+59.00 -L-)	Lump Sum	L.S.	
0091	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,496 LB		
0092	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	104,000 LS		
0093	8364000000-E	450	HP12X53 STEEL PILES	315 LF		
0094	8468000000-E	460	ONE BAR METAL RAIL	161.67 LF		
009E	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-0" X 1'-6")	176.67 LF		
009E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	280 TON		
0097	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	310 SY		
009E	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1434/Aug09/Q147102.04/D429165490000/E98

Total Amount Of Bid For Entire Project :

Contract No: C201680

County: Randolph

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General