

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (21+00.00)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	1,250 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	30 TON		
0008	0106000000-E	230	BORROW EXCAVATION	23,375 CY		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	2,720 CY		
0010	0195000000-E	265	SELECT GRANULAR MATERIAL	1,000 CY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,000 SY		
0012	0241000000-E	SP	GENERIC GRADING ITEM ROCK PLATING	550 SY		
0013	0255000000-E	SP	GENERIC GRADING ITEM DISPOSAL OF CONTAMINATED SOIL	50 TON		
0014	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	47 TON		
0015	0343000000-E	310	15" SIDE DRAIN PIPE	28 LF		
0016	0344000000-E	310	18" SIDE DRAIN PIPE	40 LF		
0017	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	104 LF		
0018	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	20 LF		

County : Davie, Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	250 LF		
0020	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0021	0995000000-E	340	PIPE REMOVAL	105 LF		
0022	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0023	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	757 TON		
0024	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	462 TON		
0025	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,050 TON		
0026	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	118 TON		
0027	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	30 TON		
0028	2000000000-N	806	RIGHT OF WAY MARKERS	12 EA		
0029	2253000000-E	840	PIPE COLLARS	0.45 CY		
0030	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0031	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0032	2556000000-E	846	SHOULDER BERM GUTTER	401 LF		
0033	2830000000-N	858	ADJUSTMENT OF MANHOLES	1 EA		
0034	3030000000-E	862	STEEL BM GUARDRAIL	1,775 LF		
0035	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	75 LF		
0036	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	3 EA		

County : Davie, Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0038	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0039	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0040	3360000000-E	863	REMOVE EXISTING GUARDRAIL	1,876 LF		
0041	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	2 EA		
0042	3635000000-E	876	RIP RAP, CLASS II	110 TON		
0043	3649000000-E	876	RIP RAP, CLASS B	5 TON		
0044	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	945 SY		
0045	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	52 SF		
0046	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0047	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	20 SF		
0048	4430000000-N	1130	DRUMS	25 EA		
0049	4435000000-N	1135	CONES	32 EA		
0050	4445000000-E	1145	BARRICADES (TYPE III)	375 LF		
0051	4450000000-N	1150	FLAGGER	140 HR		
0052	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	46 EA		
0053	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,880 LF		
0054	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,880 LF		
0055	4730000000-E	1205	EPOXY PAVEMENT MARKING LINES (4")	1,600 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	7,360 LF		
0057	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	10 EA		
0058	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	36 EA		
0059	5648000000-N	1515	RELOCATE WATER METER	4 EA		
0060	5672000000-N	1515	RELOCATE FIRE HYDRANT	1 EA		
0061	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	4 EA		
0062	6000000000-E	1605	TEMPORARY SILT FENCE	1,200 LF		
0063	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	100 TON		
0064	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	500 TON		
0065	6012000000-E	1610	SEDIMENT CONTROL STONE	450 TON		
0066	6015000000-E	1615	TEMPORARY MULCHING	3.5 ACR		
0067	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0068	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0069	6024000000-E	1622	TEMPORARY SLOPE DRAINS	335 LF		
0070	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	7 EA		
0071	6029000000-E	SP	SAFETY FENCE	750 LF		
0072	6030000000-E	1630	SILT EXCAVATION	1,210 CY		
0073	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,270 SY		
0074	6042000000-E	1632	1/4" HARDWARE CLOTH	100 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	6045000000-E	SP	*** TEMPORARY PIPE (18")	60 LF		
0076	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	150 SY		
0077	6069000000-E	1638	STILLING BASINS	40 CY		
0078	6070000000-N	SP	SPECIAL STILLING BASINS	12 EA		
0079	6071030000-E	SP	COIR FIBER BAFFLES	350 LF		
0080	6084000000-E	1660	SEEDING & MULCHING	3.5 ACR		
0081	6087000000-E	1660	MOWING	2.5 ACR		
0082	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0083	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0084	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0085	6108000000-E	1665	FERTILIZER TOPDRESSING	2.75 TON		
0086	6111000000-E	SP	IMPERVIOUS DIKE	45 LF		
0087	6114000000-N	SP	SPECIALIZED HAND MOWING	4.5 HR		
0088	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		
0089	6123000000-E	1670	REFORESTATION	1.35 ACR		
CULVERT ITEMS						
0090	8126000000-N	414	CULVERT EXCAVATION, STA ***** (26+26.72-L-)	Lump Sum	L.S.	
0091	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	13 TON		
0092	8196000000-E	420	CLASS A CONCRETE (CULVERT)	38.5 CY		

County : Davie, Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	8245000000-E	425	REINFORCING STEEL (CULVERT)	4,202 LB		
STRUCTURE ITEMS						
0094	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (21+00.00-L-)	Lump Sum	L.S.	
0095	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (21+00.00-L-)	Lump Sum	L.S.	
0096	8105560000-E	SP	4'-0" DIA DRILLED PIERS IN SO IL	155.59 LF		
0097	8105660000-E	SP	4'-0" DIA DRILLED PIERS NOT IN SOIL	81 LF		
0098	8111600000-E	SP	PERMANENT STEEL CASING FOR 4'-0" DIA DRILLED PIER	66.7 LF		
0099	8113000000-N	SP	SID INSPECTION	4 EA		
0100	8114000000-N	SP	SPT TESTING	1 EA		
0101	8115000000-N	SP	CROSSHOLE SONIC LOGGING	3 EA		
0102	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	14,081 SF		
0103	8161000000-E	420	GROOVING BRIDGE FLOORS	12,977 SF		
0104	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	198.5 CY		
0105	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (21+00.00-L-)	Lump Sum	L.S.	
0106	8217000000-E	425	REINFORCING STEEL (BRIDGE)	57,447 LB		
0107	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	10,230 LB		
0108	8277000000-E	430	MODIFIED 72" PRESTRESSED CONC GIRDERS	1,579.43 LF		

County : Davie, Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0109	8364000000-E	450	HP12X53 STEEL PILES	945 LF		
0110	8503000000-E	460	CONCRETE BARRIER RAIL	798.94 LF		
0111	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	885 TON		
0112	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	985 SY		
0113	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0114	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0930/Aug10/Q165480.96/D522944450000/E114			Total Amount Of Bid For Entire Project :			

Contract No: C201224

Counties: Rowan/Davie

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General