

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+80.90-L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	600 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	500 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	40 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	45 TON		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	32 LF		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	52 LF		
0014	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (12", 0.064")	16 LF		
0015	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	112 LF		
0016	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	4 EA		
0017	0706000000-E	310	12" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	20 LF		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	52 LF		
0019	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0020	0995000000-E	340	PIPE REMOVAL	234 LF		
0021	1121000000-E	520	AGGREGATE BASE COURSE	210 TON		
0022	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
0023	1330000000-E	607	INCIDENTAL MILLING	200 SY		
0024	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	470 TON		
0025	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	440 TON		
0026	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	49 TON		
0027	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	18 TON		
0028	2022000000-E	815	SUBDRAIN EXCAVATION	224 CY		
0029	2033000000-E	815	SUBDRAIN FINE AGGREGATE	168 CY		
0030	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
0031	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30 EA		
0032	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0033	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0034	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0035	2354200000-N	840	FRAME WITH GRATE, STD 840.24	4 EA		
0036	2556000000-E	846	SHOULDER BERM GUTTER	100 LF		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3030000000-E	862	STEEL BM GUARDRAIL	275 LF		
0038	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	75 LF		
0039	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0040	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (TL-2)	1 EA		
0041	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0042	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1 EA		
0043	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0044	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	50 LF		
0045	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (B-77)	4 EA		
0046	3389000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (TL-2)	1 EA		
0047	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	3 EA		
0048	3649000000-E	876	RIP RAP, CLASS B	15 TON		
0049	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	380 SY		
0050	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0051	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	224 SF		
0052	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	256 SF		
0053	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	56 SF		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	1 EA		
0055	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	1 EA		
0056	4430000000-N	1130	DRUMS	70 EA		
0057	4435000000-N	1135	CONES	50 EA		
0058	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0059	4450000000-N	1150	FLAGGER	1,600 HR		
0060	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0061	4516000000-N	1180	SKINNY DRUM	50 EA		
0062	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	100 EA		
0063	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	18,005 LF		
0064	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	284 LF		
0065	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,950 LF		
0066	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	30 LF		
0067	5325600000-E	1510	6" WATER LINE	139 LF		
0068	5800000000-E	1530	ABANDON 6" UTILITY PIPE	265 LF		
0069	5888000000-E	SP	GENERIC UTILITY ITEM 8" HDPE WATER PIPE, SDR 9, 200# WP, BY DIRECTIONAL BORE	168 LF		
0070	6000000000-E	1605	TEMPORARY SILT FENCE	850 LF		
0071	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	180 TON		
0072	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	190 TON		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6012000000-E	1610	SEDIMENT CONTROL STONE	80 TON		
0074	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		
0075	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0076	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0077	6029000000-E	SP	SAFETY FENCE	225 LF		
0078	6030000000-E	1630	SILT EXCAVATION	655 CY		
0079	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,500 SY		
0080	6037000000-E	SP	COIR FIBER MAT	30 SY		
0081	6042000000-E	1632	1/4" HARDWARE CLOTH	80 LF		
0082	6071030000-E	SP	COIR FIBER BAFFLES	150 LF		
0083	6071050000-E	SP	*** SKIMMER (1-1/2")	5 EA		
0084	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0085	6087000000-E	1660	MOWING	2 ACR		
0086	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0087	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0088	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0089	6108000000-E	1665	FERTILIZER TOPDRESSING	2.25 TON		
0090	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0091	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	24 EA		
0092	6123000000-E	1670	REFORESTATION	0.2 ACR		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0093	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (16+80.90-L-)	Lump Sum	L.S.	
0094	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+80.90-L-)	Lump Sum	L.S.	
0095	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (16+80.90-L-)	Lump Sum	L.S.	
0096	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	33.8 CY		
0097	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+80.90-L-)	Lump Sum	L.S.	
0098	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,046 LB		
0099	8364000000-E	450	HP12X53 STEEL PILES	765 LF		
0100	8391000000-N	450	STEEL PILE POINTS	18 EA		
0101	8503000000-E	460	CONCRETE BARRIER RAIL	175.33 LF		
0102	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	153 TON		
0103	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	170 SY		
0104	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0105	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	876.67 LF		

Contract No: C201681

County: Haywood

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General