



PROJECT SPECIAL PROVISIONS
Utility Construction

All proposed utility construction shall meet the applicable requirements of the NC Department of Transportation's "Standard Specifications for Roads and Structures" dated July 2006. Division 15 of the Standard Specifications is revised as follows:

Page 15-1, Paragraph 4

Provide access for Department personnel and the owner's representatives to all phases of construction. Notify Department personnel and the utility owner two weeks prior to commencement of any work and one week prior to service interruption. Keep utility owner's representatives informed of work progress and provide opportunity for inspection of construction and testing. *The water lines and sanitary sewer lines on this project belong to the Town of Four Oaks. The owner's representative is Mr. Roy D. Adams, Public Works Director who can be reached by telephone at (919) 963-3112 extension 25.*

At locations where water and sewer lines cross, the Contractor will provide ferrous pipe in accordance with the requirements of Title 15A of the North Carolina Administrative Code. Additionally, the owner will provide the Contractor with new fire hydrants at the locations noted on the Utility Construction plan as "fire hydrant" and "relocate fire hydrant". However, the Contractor will be responsible for valves and other items on hydrant legs or service lines as identified under Section 1515-5 of the Standard Specification "Measurement and Payment".

Page 15-10

Change: **Fire Hydrants**
To: **(D) Fire Hydrants**

Abandoned Utility Pipe

The 8" diameter truss pipe that is to be abandoned on this project shall be filled with grout or flowable fill in accordance with Section 1530-3 of the Standard Specifications. Measurement and payment shall be in accordance with Section 1530-4 of the Standard Specifications.

PROJECT SPECIAL PROVISIONS
Utility

UTILITIES BY OTHERS

General:

The following utility companies have facilities that will be in conflict with the construction of this project.

- A) Progress Energy (Power Distribution)
- B) Embarq – Telephone
- C) Time Warner Cable - CATV

The conflicting facilities of these concerns will be adjusted prior to the date of availability, unless otherwise noted and are therefore listed in these special provisions for the benefit of the Contractor. All utility work listed herein will be done by the utility owner. All utilities are shown on the plans from the best available information.

The Contractor’s attention is directed to Article 105-8 of the Standard Specifications.

Utilities Requiring Adjustment:

- A) Progress Energy (Distribution)
 - 1) See Utilities by Others Plans.
- B) Bell South - Telephone
 - 1) See Utilities by Others Plans.

NOTE: Bell South’s existing buried telephone cables will remain in place to be adjusted as necessary. Existing aerial telephone lines will be removed utilizing existing buried cables except as shown on the plans.

- C) Time Warner – CATV
 - 1) See Utilities by Others Plans.

NOTE: Time Warner’s existing aerial cable TV is in joint use with Progress Energy and will relocate in joint use with power throughout the project. The contractor shall allow Time Warner until November 1, 2007 to complete their relocations in joint use with Progress Energy. Any existing buried cable TV will remain in place to be adjusted as necessary.

NOTE: All other utilities will remain in place and will be adjusted as necessary.