

County : Alexander

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (19 + 18.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	750 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	390 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0010	0199000000-E	SP	TEMPORARY SHORING	300 SF		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	35 TON		
0012	0342000000-E	310	*** SIDE DRAIN PIPE (15")	144 LF		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	40 LF		
0014	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	88 LF		
0015	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	44 LF		
0016	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0017	0995000000-E	340	PIPE REMOVAL	42 LF		
0018	1121000000-E	520	AGGREGATE BASE COURSE	255 TON		

County : Alexander

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0020	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,400 TON		
0021	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	680 TON		
0022	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	105 TON		
0023	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	95 TON		
0024	2264000000-E	840	PIPE PLUGS	0.22 CY		
0025	2275000000-E	SP	FLOWABLE FILL	3 CY		
0026	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0027	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	1.5 LF		
0028	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0029	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0030	2556000000-E	846	SHOULDER BERM GUTTER	10 LF		
0031	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	100 LF		
0032	3030000000-E	862	STEEL BM GUARDRAIL	200 LF		
0033	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	62.5 LF		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0035	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0036	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		

County : Alexander

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
003E	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	50 LF		
003E	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	1 EA		
004C	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	1 EA		
0041	3649000000-E	876	RIP RAP, CLASS B	263 TON		
0042	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	735 SY		
004E	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (D)	41.4 SF		
0044	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	31.75 SF		
004E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	224 LF		
004E	4096000000-N	904	SIGN ERECTION, TYPE D	4 EA		
0047	4102000000-N	904	SIGN ERECTION, TYPE E	8 EA		
004E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	14 EA		
004E	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1 EA		
005C	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	72 SF		
0051	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0052	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	60 SF		
005E	4430000000-N	1130	DRUMS	40 EA		
0054	4435000000-N	1135	CONES	40 EA		

County : Alexander

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	4445000000-E	1145	BARRICADES (TYPE III)	192 LF		
005E	4450000000-N	1150	FLAGGER	276 HR		
0057	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	32,440 LF		
005E	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	3,240 LF		
005E	6000000000-E	1605	TEMPORARY SILT FENCE	750 LF		
006C	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	90 TON		
0061	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	170 TON		
0062	6012000000-E	1610	SEDIMENT CONTROL STONE	55 TON		
006E	6015000000-E	1615	TEMPORARY MULCHING	4.5 ACR		
0064	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
006E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.75 TON		
006E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	140 LF		
0067	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
006E	6029000000-E	SP	SAFETY FENCE	400 LF		
006E	6030000000-E	1630	SILT EXCAVATION	1,220 CY		
007C	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,100 SY		
0071	6037000000-E	SP	COIR FIBER MAT	45 SY		
0072	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	2,980 SY		

County : Alexander

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
0074	6071030000-E	SP	COIR FIBER BAFFLES	225 LF		
0075	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0076	6071050000-E	SP	*** SKIMMER (2")	1 EA		
0077	6071050000-E	SP	*** SKIMMER (2-1/2")	2 EA		
007E	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
0079	6087000000-E	1660	MOWING	2.5 ACR		
008C	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0081	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0082	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0083	6108000000-E	1665	FERTILIZER TOPDRESSING	3.75 TON		
0084	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0085	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8 EA		
008E	6123000000-E	1670	REFORESTATION	0.15 ACR		

**STRUCTURE ITEMS**

0087	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (19 + 18.00-L-)	Lump Sum	L.S.	
008E	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	4,055 SF		
008E	8161000000-E	420	GROOVING BRIDGE FLOORS	4,120 SF		

County : Alexander

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
009C	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	75.4 CY		
0091	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (19 + 18.00-L-)	Lump Sum	L.S.	
0092	8217000000-E	425	REINFORCING STEEL (BRIDGE)	11,919 LB		
0093	8280000000-E	440	APPROX ..... LBS STRUCTURAL STEEL	122,300 LS		
0094	8364000000-E	450	HP12X53 STEEL PILES	675 LF		
0095	8475000000-E	460	TWO BAR METAL RAIL	217.23 LF		
0096	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 2'-6")	234.3 LF		
0097	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	280 TON		
0098	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	310 SY		
0099	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
010C	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1048/Oct03/Q195441.2/D424828780000/E100

Total Amount Of Bid For Entire Project :

**Contract No: C201584**

**County: Alexander**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General