

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	1,158 TON		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	96.28 SMI		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	25,344 SY		
0005	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	41,584 SY		
0006	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	620 TON		
0007	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	50,493 TON		
0008	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	16,939 TON		
0009	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	4,161 TON		
0010	2830000000-N	858	ADJUSTMENT OF MANHOLES	51 EA		
0011	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	65 EA		
0012	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	341,500 LF		
0013	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	338,700 LF		
0014	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,300 LF		
0015	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	650 LF		
0016	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	500 LF		
0017	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,580 LF		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	68 EA		
0019	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	261 EA		
0020	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	633,600 LF		
0021	4891000000-E	1205	GENERIC PAVEMENT MARKING ITEM THERMOPLASTIC PAVEMENT MKG (4") (240MIL) (RUMBLE STRIPS)	550 LF		
0022	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	3,630 EA		
0023	6084000000-E	1660	SEEDING & MULCHING	117 ACR		
0024	7288000000-E	1715	PAVED TRENCHING (*****) (1, 2")	200 LF		
0025	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	1,150 LF		
0026	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	21 EA		
0027	7420000000-E	1722	2" RISER WITH WEATHERHEAD	15 EA		
0028	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	10,900 LF		
0029	7456000000-E	1726	LEAD-IN CABLE (*****) (18-2)	1,700 LF		
0030	7990000000-E	SP	GENERIC SIGNAL ITEM 1" PVC CONDUIT	220 LF		
0031	7990000000-E	SP	GENERIC SIGNAL ITEM 2" PVC CONDUIT	1,100 LF		
1453/Oct17/Q1478274.28/D135368100000/E31			Total Amount Of Bid For Entire Project :			

Contract No: C201934

County: Robeson

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General