



PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	FINAL PAVEMENT MARKINGS COLD APPLIED PLASTIC (4") (Type-II - PERMANENT HIGH PERFORMANCE)	PAY ITEM QUANTITY BREAKDOWN	TOTAL QUANTITY
CA-II	WHITE EDGELINE		378 LF	
CI-II	YELLOW DOUBLE CENTER		378 LF	
			TOTAL	756 LF
TI	YELLOW DOUBLE CENTER	THERMOPLASTIC(4", 120 MILS)	2272 LF	
			TOTAL	2272 LF
TA	WHITE EDGELINE	THERMOPLASTIC(4", 90 MILS)	2272 LF	
			TOTAL	2272 LF
MA	YELLOW & YELLOW	MARKERS PERMANENT RAISED PAVEMENT MARKERS	17 EA	
			TOTAL	17 EA
CA-IV	WHITE EDGELINE		378 LF	
CI-IV	YELLOW DOUBLE CENTER		378 LF	
			TOTAL	756 LF
PA	WHITE EDGELINE	PAINT(4")	4544 LF	
PI	YELLOW DOUBLE CENTER		4544 LF	
			TOTAL	9088 LF
MH	YELLOW & YELLOW	MARKERS TEMPORARY RAISED PAVEMENT MARKERS	17 EA	
			TOTAL	17 EA

SEE ROADWAY STANDARD DRAWING NO. 1250.01 AND 1251.01 FOR PAVEMENT MARKER SPACING AND RAISED PAVEMENT MARKERS.

APPROVED: *[Signature]* DATE: *01/07*

SEAL

SEAL
8973
ENGINEER
G.L. GETTLER

PAVEMENT MARKING SCHEDULE

SCALE: NONE		REVISIONS
DATE: 01/07		
DWG. BY: MW		
DESIGN BY: MW		
REVIEWED BY: JWG		

R:\JAN-2007\2249\Roadway\Drawings\TrafficControl\top\B3917\TrafficControl\top\B3917_TC_TCP_PM-1.dgn