

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+05.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	62 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	10 TON		
001C	0343000000-E	310	15" SIDE DRAIN PIPE	20 LF		
0011	0344000000-E	310	18" SIDE DRAIN PIPE	56 LF		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	16 LF		
0013	0995000000-E	340	PIPE REMOVAL	129 LF		
0014	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	598 TON		
0016	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	352 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	47 TON		
001E	2000000000-N	806	RIGHT OF WAY MARKERS	14 EA		

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0020	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
0021	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0022	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0023	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0024	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0025	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0026	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0027	2612000000-E	848	6" CONCRETE DRIVEWAY	85 SY		
0028	3030000000-E	862	STEEL BM GUARDRAIL	250 LF		
0029	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0030	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0031	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0032	3649000000-E	876	RIP RAP, CLASS B	2 TON		
0033	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	517 SY		
0034	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	332 SF		
0035	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	144 SF		
0036	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,500	LF	
003E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,500	LF	
003E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	9	EA	
004C	6000000000-E	1605	TEMPORARY SILT FENCE	960	LF	
0041	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	90	TON	
0042	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	150	TON	
0043	6012000000-E	1610	SEDIMENT CONTROL STONE	235	TON	
0044	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
004E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25	TON	
0047	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50	LF	
004E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2	EA	
004E	6029000000-E	SP	SAFETY FENCE	150	LF	
005C	6030000000-E	1630	SILT EXCAVATION	475	CY	
0051	6036000000-E	1631	MATTING FOR EROSION CONTROL	850	SY	
0052	6070000000-N	SP	SPECIAL STILLING BASINS	8	EA	
0053	6071030000-E	SP	COIR FIBER BAFFLES	150	LF	
0054	6084000000-E	1660	SEEDING & MULCHING	1.5	ACR	

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6087000000-E	1660	MOWING	1	ACR	
005E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0057	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
005E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
005E	6108000000-E	1665	FERTILIZER TOPDRESSING	1	TON	
006C	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
0061	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	8	EA	
0062	6123000000-E	1670	REFORESTATION	0.1	ACR	

STRUCTURE ITEMS

0063	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17 + 05.00-L-)	Lump Sum	L.S.	
0064	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SOIL	46.9	LF	
006E	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	33	LF	
0066	8111200000-E	SP	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	12.9	LF	
0067	8113000000-N	SP	SID INSPECTION	2	EA	
006E	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2	EA	
0069	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	505	CY	
007C	8156000000-E	SP	CONCRETE WEARING SURFACE	3,608	SF	
0071	8161000000-E	420	GROOVING BRIDGE FLOORS	4,723	SF	

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	51.3 CY		
0073	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+05.00-L-)	Lump Sum	L.S.	
0074	8217000000-E	425	REINFORCING STEEL (BRIDGE)	14,370 LB		
007E	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,522 LB		
0076	8364000000-E	450	HP12X53 STEEL PILES	80 LF		
0077	8475000000-E	460	TWO BAR METAL RAIL	200.02 LF		
007E	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 3'-1 1/4")	215.17 LF		
007E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	180 TON		
008C	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	199 SY		
0081	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0082	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0083	8753000000-E	430	3'-0" X 2'-3" PRESTRESSED CONC BOX BEAMS	1,291 LF		

0912/Oct04/Q36638.89/D391752470000/E83

Total Amount Of Bid For Entire Project :

Contract No: C201714

County: Wilson

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General