

County : Hoke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	12,500 CY		
0006	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (50+30.00)	Lump Sum	L.S.	
0007	0036000000-E	225	UNDERCUT EXCAVATION	2,000 CY		
0008	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	1,000 TON		
0009	0106000000-E	230	BORROW EXCAVATION	117,000 CY		
0010	0134000000-E	240	DRAINAGE DITCH EXCAVATION	1,125 CY		
0011	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	4,280 SY		
0012	0192000000-N	260	PROOF ROLLING	9 HR		
0013	0195000000-E	265	SELECT GRANULAR MATERIAL	2,000 CY		
0014	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	2,000 SY		
0015	0234000000-E	SP	GENERIC GRADING ITEM SELECT MATERIAL FOR PRIMARY GEOGRID REINFORCEMENT	3,000 CY		
0016	0241000000-E	SP	GENERIC GRADING ITEM FILTER FABRIC FOR DRAINAGE, TYPE 2	2,300 SY		
0017	0241000000-E	SP	GENERIC GRADING ITEM PRIMARY GEOGRID REINFORCEMENT	4,000 SY		
0018	0241000000-E	SP	GENERIC GRADING ITEM SECONDARY GEOGRID REINFORCE- MENT	5,500 SY		

County : Hoke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0255000000-E	SP	GENERIC GRADING ITEM CONTAMINATED SOIL EXCAVATION	10 TON		
0020	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	550 TON		
0021	0343000000-E	310	15" SIDE DRAIN PIPE	200 LF		
0022	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	992 LF		
0023	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	240 LF		
0024	0420000000-E	310	66" RC PIPE CULVERTS, CLASS III	124 LF		
0025	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	176 LF		
0026	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	6 EA		
0027	0995000000-E	340	PIPE REMOVAL	737 LF		
0028	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0029	1110000000-E	510	STABILIZER AGGREGATE	1,500 TON		
0030	1121000000-E	520	AGGREGATE BASE COURSE	19,500 TON		
0031	1220000000-E	545	INCIDENTAL STONE BASE	150 TON		
0032	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	4,025 TON		
0033	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	7,050 TON		
0034	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	10,500 TON		
0035	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,135 TON		
0036	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	150 TON		

County : Hoke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2022000000-E	815	SUBDRAIN EXCAVATION	680 CY		
0038	2033000000-E	815	SUBDRAIN FINE AGGREGATE	340 CY		
0039	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	2,000 LF		
0040	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	60 EA		
0041	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	4 EA		
0042	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	24 LF		
0043	2209000000-E	838	ENDWALLS	5 CY		
0044	2220000000-E	838	REINFORCED ENDWALLS	7 CY		
0045	2264000000-E	840	PIPE PLUGS	1 CY		
0046	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	50 EA		
0047	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	6 LF		
0048	2352000000-N	840	FRAME WITH GRATE, STD 840.**** (840.16)	3 EA		
0049	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	16 EA		
0050	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1 EA		
0051	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	15 EA		
0052	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	13 EA		
0053	2396000000-N	840	FRAME WITH COVER, STD 840.54	2 EA		
0054	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	3,920 LF		

County : Hoke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	2556000000-E	846	SHOULDER BERM GUTTER	1,590 LF		
0056	2612000000-E	848	6" CONCRETE DRIVEWAY	80 SY		
0057	3030000000-E	862	STEEL BM GUARDRAIL	1,650 LF		
0058	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0059	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0060	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0061	3628000000-E	876	RIP RAP, CLASS I	17 TON		
0062	3649000000-E	876	RIP RAP, CLASS B	92 TON		
0063	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	810 SY		
0064	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0065	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	616 SF		
0066	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	416 SF		
0067	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	670 SF		
0068	4430000000-N	1130	DRUMS	400 EA		
0069	4435000000-N	1135	CONES	250 EA		
0070	4445000000-E	1145	BARRICADES (TYPE III)	448 LF		
0071	4455000000-N	1150	FLAGGER	360 MD		
0072	4480000000-N	1165	TMIA	1 EA		
0073	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	188 EA		

County : Hoke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	21,934 LF		
0075	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	38,747 LF		
0076	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,428 LF		
0077	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	445 LF		
0078	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	40 EA		
0079	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	76 EA		
0080	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (TYPE 2)	1,120 LF		
0081	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	52,141 LF		
0082	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	412 LF		
0083	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	152 LF		
0084	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	7 EA		
0085	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	15,418 LF		
0086	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	34 LF		
0087	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	4 EA		
0088	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	812 EA		
0089	5325600000-E	1510	6" WATER LINE	549.02 LF		
0090	5325800000-E	1510	8" WATER LINE	80 LF		

County : Hoke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	5648000000-N	1515	RELOCATE WATER METER	4 EA		
0092	5672000000-N	1515	RELOCATE FIRE HYDRANT	10 EA		
0093	5691300000-E	1520	8" SANITARY GRAVITY SEWER	137.7 LF		
0094	5691400000-E	1520	10" SANITARY GRAVITY SEWER	784.3 LF		
0095	5709100000-E	1520	2" FORCE MAIN SEWER	138.5 LF		
0096	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	2 EA		
0097	5775000000-E	1525	4' DIA UTILITY MANHOLE	6 EA		
0098	5801000000-E	1530	ABANDON 8" UTILITY PIPE	906 LF		
0099	5816000000-N	1530	ABANDON UTILITY MANHOLE	3 EA		
0100	6000000000-E	1605	TEMPORARY SILT FENCE	4,000 LF		
0101	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	430 TON		
0102	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,505 TON		
0103	6012000000-E	1610	SEDIMENT CONTROL STONE	1,070 TON		
0104	6015000000-E	1615	TEMPORARY MULCHING	21.5 ACR		
0105	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	750 LB		
0106	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	3 TON		
0107	6024000000-E	1622	TEMPORARY SLOPE DRAINS	865 LF		
0108	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	16 EA		
0109	6029000000-E	SP	SAFETY FENCE	540 LF		
0110	6030000000-E	1630	SILT EXCAVATION	11,030 CY		

County : Hoke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0111	6036000000-E	1631	MATTING FOR EROSION CONTROL	3,280 SY		
0112	6037000000-E	SP	COIR FIBER MAT	100 SY		
0113	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	4,000 SY		
0114	6042000000-E	1632	1/4" HARDWARE CLOTH	1,215 LF		
0115	6071030000-E	SP	COIR FIBER BAFFLES	1,875 LF		
0116	6071050000-E	SP	*** SKIMMER (1-1/2")	9 EA		
0117	6071050000-E	SP	*** SKIMMER (2")	3 EA		
0118	6071050000-E	SP	*** SKIMMER (3")	1 EA		
0119	6084000000-E	1660	SEEDING & MULCHING	28 ACR		
0120	6087000000-E	1660	MOWING	12.5 ACR		
0121	6090000000-E	1661	SEED FOR REPAIR SEEDING	200 LB		
0122	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5 TON		
0123	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	500 LB		
0124	6108000000-E	1665	FERTILIZER TOPDRESSING	21 TON		
0125	6114000000-N	SP	SPECIALIZED HAND MOWING	4 HR		
0126	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	27 EA		
0127	7060000000-E	1705	SIGNAL CABLE	1,450 LF		
0128	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	14 EA		
0129	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	4 EA		

County : Hoke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0130	7264000000-E	1710	MESSENGER CABLE (3/8")	1,020 LF		
0131	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	2,590 LF		
0132	7301000000-E	1715	DIRECTIONAL DRILL (***** (1, 2")	170 LF		
0133	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	18 EA		
0134	7360000000-N	1720	WOOD POLE	7 EA		
0135	7372000000-N	1721	GUY ASSEMBLY	14 EA		
0136	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0137	7420000000-E	1722	2" RISER WITH WEATHERHEAD	8 EA		
0138	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	3,000 LF		
0139	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	7,000 LF		
0140	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1 EA		
0141	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	1 EA		
0142	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	11 EA		
0143	7901000000-N	1753	CABINET BASE EXTENDER	1 EA		
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0144 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,748 LF		
0145 AA1	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	756 LF		
0146 AA1	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	716 LF		

County : Hoke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0147 AA1	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	236	LF	
*** OR ***						
0148 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,220	LF	
0149 AA2	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	644	LF	
0150 AA2	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	96	LF	
0151 AA2	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	184	LF	
0152 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	528	LF	
0153 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	112	LF	
0154 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (30")	620	LF	
0155 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (36")	52	LF	
*** OR ***						
0156 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,220	LF	
0157 AA3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	644	LF	
0158 AA3	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	96	LF	
0159 AA3	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	184	LF	
0160 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (15", 0.064")	528	LF	
0161 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (18", 0.064")	112	LF	

County : Hoke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0162 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (30", 0.064")	620 LF		
0163 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (36", 0.064")	52 LF		

***** END SCHEDULE AA *****

STRUCTURE ITEMS

0164	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (50+72.21-L-)	Lump Sum	L.S.	
0165	8112730000-N	SP	PDA TESTING	2 EA		
0166	8112740000-N	SP	PDA ASSISTANCE	2 EA		
0167	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	9,108 SF		
0168	8161000000-E	420	GROOVING BRIDGE FLOORS	8,916 SF		
0169	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	61.5 CY		
0170	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (50+72.21-L-)	Lump Sum	L.S.	
0171	8217000000-E	425	REINFORCING STEEL (BRIDGE)	8,239 LB		
0172	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	357,200 LS		
0173	8364000000-E	450	HP12X53 STEEL PILES	1,440 LF		
0174	8385200000-E	450	PP ** X **** GALVANIZED STEEL PILES (24 X 0.50)	570 LF		
0175	8392000000-N	450	PIPE PILE PLATES	6 EA		
0176	8393000000-N	450	PILE REDRIVES	6 EA		

County : Hoke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0177	8475000000-E	460	TWO BAR METAL RAIL	514.19 LF		
0178	8517000000-E	460	1'***X ***** CONCRETE PARA- PET (1'-2" X 2'-6")	530 LF		
0179	8594000000-E	876	RIP RAP, CLASS B	850 TON		
0180	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
1545/Nov07/Q798541.71/D705484550000/E180			Total Amount Of Bid For Entire Project :			

Contract No: C201738

County: Hoke

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General