

PROJECT SPECIAL PROVISIONS

## Utilities by Others

The existing high-pressure gas mains crossing Line L between stations 21+00 and 22+00 will remain in place. WGP-Transco, who identifies these lines as Maiden Lateral Lines A (10") and B (16") owns the lines. Investigations between NCDOT and WGP-Transco revealed that the existing pipes are Class 3, are cased, and should have about 3 feet of cover from the proposed curb and gutter on the south side of the project.

The Contractor is directed to perform the following:

1. Provide a 2-week notice and allow 1 week for the relocation of the cathodic protection test leads and a casing vent. Contact Mr. Dewain Tabor at (704) 892-7631.
2. Provide a list of equipment proposed to be used over the pipeline for review by WGP-Transco for load stress analysis prior to using equipment. Allow 30 days for review. Vibratory rollers or other vibratory equipment will not be allowed to be used over the pipelines. The Resident Engineer will determine whether unusually large equipment will be allowed. WGP-Transco does not anticipate any issues with typical grading equipment.
3. Provide a certificate of insurance verifying \$1,000,000 of General Liability Insurance covering the Contractor and any subcontractors working over the pipeline.
4. Provide sufficient notice and coordinate activities to allow the WGP-Transco inspector to be present when construction work is performed over the pipeline.

The Contractor's attention is directed to Article 105.8 of the Standard Specifications.

This work will be considered incidental and will be paid for at the contract unit prices of the various items in the contract.

PROJECT SPECIAL PROVISIONS  
Utilities by Others

## General:

The following utility companies have facilities that will be in conflict with the construction of this project:

- GAS**            Transcontinental Gas Pipe Line Corp  
300 Potts Street  
Davidson, NC 28036  
Mr. Dewain Tabor  
704-892-7631
- Williams Gas Pipeline – Transco  
345 Greenbriar Drive  
Charlottesville, VA 22901  
Mr. Ron Gray, Sr. Engineer  
434-964-2125 (Office)    434-981-2104 (Mobile)  
ronald.e.gray@williams.com
- Phone**        Byers Engineering Co  
(Bell South)  
710 S. Marietta St  
Gastonia, NC 28052  
Mr. Charles Mayberry, VP  
704-868-8580 (Office)    704-460-5097 (Cell)  
charles.mayberry@byers.com
- Cable**        Charter Communications  
220 McLean Drive  
Lenoir, NC 28645  
Mr. Craig Cline  
828-322-3877
- Power**        Duke Energy  
Keith Bumpious, Sr. Engineer  
704-382-5367
- Water and Sewer**    Lincoln County Utilities  
115 W. Main St  
Lincolnton, NC 28090  
Attn: Mr. Steve Gilbert  
704-736-8496

Catawba County Public Service Admin.  
PO Box 389  
Newton, NC 28658  
Attn: Mr Jack Chandler  
828-465-8940

Gas           Piedmont Natural Gas  
              Mr. Travis Richey, Operations Tech  
              828-312-2147

Phone        Mr. Mitch Cline  
              877-203-7324

The conflicting aerial pole lines will be adjusted prior to May 22, 2008. All other utilities will remain in place and be adjusted as necessary. The utility owners will perform all utility work. All utilities are shown on the plans from the best available information.

The Contractor's attention is directed to Article 105.8 of the Standard Specifications.