

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	800 CY		
0005	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	1,500 TON		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	300 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	2,500 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	550 TON		
0009	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,428 LF		
0010	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,324 LF		
0011	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	1,240 LF		
0012	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	1,048 LF		
0013	0408000000-E	310	54" RC PIPE CULVERTS, CLASS III	88 LF		
0014	0995000000-E	340	PIPE REMOVAL	2,300 LF		
0015	1220000000-E	545	INCIDENTAL STONE BASE	1,500 TON		
0016	1330000000-E	607	INCIDENTAL MILLING	500 SY		
0017	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	4,460 TON		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	5,320 TON		
001E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	529 TON		
002C	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	120 TON		
0021	2209000000-E	838	ENDWALLS	7 CY		
0022	2220000000-E	838	REINFORCED ENDWALLS	10 CY		
0023	2253000000-E	840	PIPE COLLARS	3 CY		
0024	2264000000-E	840	PIPE PLUGS	0.2 CY		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	69 EA		
002E	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	4 LF		
0027	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	13 EA		
002E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	3 EA		
002E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	8 EA		
003C	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	20 EA		
0031	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	20 EA		
0032	2396000000-N	840	FRAME WITH COVER, STD 840.54	2 EA		
0033	2474000000-N	SP	GENERIC DRAINAGE ITEM DRY DETENTION BASIN	Lump Sum	L.S.	
0034	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	9,775 LF		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	2612000000-E	848	6" CONCRETE DRIVEWAY	710	SY	
003E	2619000000-E	850	4" CONCRETE PAVED DITCH	12	SY	
0037	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	35	SY	
003E	3360000000-E	863	REMOVE EXISTING GUARDRAIL	80	LF	
003E	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	750	LF	
004C	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	65	EA	
0041	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	10	EA	
0042	3554000000-E	866	METAL GATE POSTS FOR *** CHAIN LINK FENCE, DOUBLE GATE (48")	2	EA	
0043	3565000000-E	866	DOUBLE GATES, *** HIGH, *** WIDE, *** OPENING (48" HIGH, 10' WIDE, 20' OPEN- ING)	1	EA	
0044	3649000000-E	876	RIP RAP, CLASS B	40	TON	
004E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	240	SY	
004E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	468	SF	
0047	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	192	SF	
004E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	288	SF	
004E	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2	EA	
005C	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2	EA	
0051	4430000000-N	1130	DRUMS	150	EA	
0052	4435000000-N	1135	CONES	100	EA	

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	4445000000-E	1145	BARRICADES (TYPE III)	200 LF		
0054	4455000000-N	1150	FLAGGER	480 MD		
0055	4480000000-N	1165	TMIA	1 EA		
0056	4510000000-N	SP	POLICE	50 HR		
0057	4520000000-N	1266	TUBULAR MARKERS (FIXED)	50 EA		
0058	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	150 EA		
0059	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	5,000 LF		
0060	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	20,000 LF		
0061	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	150 LF		
0062	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	350 LF		
0063	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	40 EA		
0064	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	4,000 LF		
0065	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	200 LF		
0066	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	36 EA		
0067	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	100 LF		
0068	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	100 LF		
0069	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	200 EA		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007C	4915000000-E	1264	7' U-CHANNEL POSTS	4	EA	
0071	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	4	EA	
0072	6000000000-E	1605	TEMPORARY SILT FENCE	5,445	LF	
0073	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75	TON	
0074	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	660	TON	
0075	6012000000-E	1610	SEDIMENT CONTROL STONE	635	TON	
0076	6015000000-E	1615	TEMPORARY MULCHING	7.5	ACR	
0077	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	300	LB	
0078	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25	TON	
0079	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50	LF	
008C	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2	EA	
0081	6029000000-E	SP	SAFETY FENCE	1,000	LF	
0082	6030000000-E	1630	SILT EXCAVATION	2,400	CY	
0083	6036000000-E	1631	MATting FOR EROSION CONTROL	3,000	SY	
0084	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	2,650	SY	
0085	6042000000-E	1632	1/4" HARDWARE CLOTH	1,340	LF	
0086	6070000000-N	SP	SPECIAL STILLING BASINS	4	EA	
0087	6071030000-E	SP	COIR FIBER BAFFLES	600	LF	
008E	6084000000-E	1660	SEEDING & MULCHING	8	ACR	

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	6087000000-E	1660	MOWING	4.5	ACR	
009C	6090000000-E	1661	SEED FOR REPAIR SEEDING	100	LB	
0091	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0092	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	175	LB	
0093	6108000000-E	1665	FERTILIZER TOPDRESSING	6	TON	
0094	6111000000-E	SP	IMPERVIOUS DIKE	96	LF	
009E	6114000000-N	SP	SPECIALIZED HAND MOWING	3	HR	
0096	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	

1415/Nov08/Q88281.7/D353512130000/E96

Total Amount Of Bid For Entire Project :

**Contract No: C201912**

**County: Nash**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General