

County : Warren, Franklin, Vance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	925 TON		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	89.28 SMI		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	750 SY		
000E	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	7,800 SY		
000E	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	700 SY		
0007	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 4-1/2")	10,650 SY		
000E	1330000000-E	607	INCIDENTAL MILLING	4,525 SY		
000E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	7,373 TON		
001C	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	15,854 TON		
0011	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	2,019 TON		
0012	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	13,921 TON		
0013	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	12,991 TON		
0014	1524000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5C (LEVELING COURSE)	40 TON		
001E	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	25,640 TON		
001E	1526000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S4.75A	2,712 TON		

County : Warren, Franklin, Vance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	3,847 TON		
001E	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	782 TON		
001E	1704000000-E	SP	PATCHING EXISTING PAVEMENT	2,380 TON		
002C	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	69,696 LF		
0021	2830000000-N	858	ADJUSTMENT OF MANHOLES	7 EA		
0022	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	14 EA		
0023	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	485,490 LF		
0024	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	306,144 LF		
002E	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	100 LF		
002E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	542 LF		
0027	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	13 EA		
002E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	109 EA		
002E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	97,000 LF		
003C	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	100 LF		
0031	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	122 LF		
0032	4840000000-N	1205	PAINT PAVEMENT MARKING CHARAC- TER	4 EA		

County : Warren, Franklin, Vance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0033	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	658	EA	
0034	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	650	EA	
0035	6084000000-E	1660	SEEDING & MULCHING	61.24	ACR	
0036	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,000	LF	
0037	7456000000-E	1726	LEAD-IN CABLE (***** (18-4)	100	LF	

1405/Nov15/Q1074809.52/D111792100000/E37

Total Amount Of Bid For Entire Project :

Contract No: C201958

County: Warren, Franklin and Vance

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General