

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16+85.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	300 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	300 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	38 TON		
0010	0343000000-E	310	15" SIDE DRAIN PIPE	24 LF		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	32 LF		
0012	0660000000-E	310	****BIT COAT CS PIPE CULVERTS, TYPE A ***** THICK (15", 0.064")	16 LF		
0013	0680000000-E	310	*** BIT COAT CS PIPE ELBOWS, TYPE A ***** THICK (15", 0.064")	2 EA		
0014	1121000000-E	520	AGGREGATE BASE COURSE	90 TON		
0015	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	355 TON		
0017	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	386 TON		
0018	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	39 TON		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0020	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
0021	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0022	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0023	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0024	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0025	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0026	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0027	2556000000-E	846	SHOULDER BERM GUTTER	50 LF		
0028	3030000000-E	862	STEEL BM GUARDRAIL	187.5 LF		
0029	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0030	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0031	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0032	3649000000-E	876	RIP RAP, CLASS B	22 TON		
0033	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	226 SY		
0034	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	360 SF		
0035	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	119 SF		
0036	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	10 DAY		
0037	4445000000-E	1145	BARRICADES (TYPE III)	112 LF		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	770 LF		
0039	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	770 LF		
0040	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (I)	800 LF		
0041	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	8 EA		
0042	5326000000-E	1510	10" WATER LINE	383 LF		
0043	5326200000-E	1510	12" WATER LINE	382 LF		
0044	5552000000-E	1515	10" VALVE	1 EA		
0045	5558000000-E	1515	12" VALVE	2 EA		
0046	5589100000-E	1515	1" AIR RELEASE VALVE	2 EA		
0047	5871600000-E	1550	TRENCHLESS INSTALLATION OF 10" IN SOIL	250 LF		
0048	6000000000-E	1605	TEMPORARY SILT FENCE	370 LF		
0049	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	50 TON		
0050	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	100 TON		
0051	6012000000-E	1610	SEDIMENT CONTROL STONE	40 TON		
0052	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0053	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0054	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
0055	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0057	6029000000-E	SP	SAFETY FENCE	300 LF		
0058	6030000000-E	1630	SILT EXCAVATION	225 CY		
0059	6036000000-E	1631	MATTING FOR EROSION CONTROL	115 SY		
0060	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
0061	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	120 SY		
0062	6071030000-E	SP	COIR FIBER BAFFLES	105 LF		
0063	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0064	6087000000-E	1660	MOWING	0.5 ACR		
0065	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0066	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0067	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0068	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0069	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0070	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0071	6123000000-E	1670	REFORESTATION	0.1 ACR		
STRUCTURE ITEMS						
0072	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+85.00 -L-)	Lump Sum	L.S.	
0073	8112730000-N	SP	PDA TESTING	1 EA		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8112740000-N	SP	PDA ASSISTANCE	1 EA		
0075	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (16+85.00 -L-)	Lump Sum	L.S.	
0076	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	67.3 CY		
0077	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+85.00 -L-)	Lump Sum	L.S.	
0078	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	11,378 LB		
0079	8364000000-E	450	HP12X53 STEEL PILES	2,640 LF		
0080	8393000000-N	450	PILE REDRIVES	20 EA		
0081	8475000000-E	460	TWO BAR METAL RAIL	384.75 LF		
0082	8517000000-E	460	1'-***X ***** CONCRETE PARAPET (1'-2" X 2'-9 1/2")	399.75 LF		
0083	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	651 TON		
0084	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	723 SY		
0085	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0086	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	2,593.5 LF		
1324/Nov29/Q27056.4/D389951900000/E86			Total Amount Of Bid For Entire Project :			

Contract No: C201730

County: Beaufort

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General