

County : Beaufort, Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+34 -L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0008	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	100 CY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	14 TON		
0010	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	92 LF		
0011	0660000000-E	310	****BIT COAT CS PIPE CULVERTS, TYPE A ***** THICK (15", 0.064")	40 LF		
0012	0680000000-E	310	*** BIT COAT CS PIPE ELBOWS, TYPE A ***** THICK (15", 0.064")	4 EA		
0013	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	270 TON		
0015	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	410 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	39 TON		
0017	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20 TON		

County : Beaufort, Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5 EA		
0019	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	5 EA		
0020	2556000000-E	846	SHOULDER BERM GUTTER	110 LF		
0021	3030000000-E	862	STEEL BM GUARDRAIL	550 LF		
0022	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0023	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0024	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0025	3649000000-E	876	RIP RAP, CLASS B	2 TON		
0026	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	195 SY		
0027	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	440 SF		
0028	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	96 SF		
0029	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		
0030	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	6,800 LF		
0031	6000000000-E	1605	TEMPORARY SILT FENCE	1,125 LF		
0032	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	50 TON		
0033	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	40 TON		
0034	6012000000-E	1610	SEDIMENT CONTROL STONE	80 TON		
0035	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0036	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		

County : Beaufort, Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0038	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
0039	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0040	6029000000-E	SP	SAFETY FENCE	160 LF		
0041	6030000000-E	1630	SILT EXCAVATION	55 CY		
0042	6036000000-E	1631	MATTING FOR EROSION CONTROL	175 SY		
0043	6042000000-E	1632	1/4" HARDWARE CLOTH	350 LF		
0044	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0045	6087000000-E	1660	MOWING	1 ACR		
0046	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0047	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0048	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0049	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0050	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0051	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0052	6123000000-E	1670	REFORESTATION	0.1 ACR		

STRUCTURE ITEMS

0053	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+34.00 -L-)	Lump Sum	L.S.	
0054	8112730000-N	SP	PDA TESTING	2 EA		

County : Beaufort, Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	8112740000-N	SP	PDA ASSISTANCE	2 EA		
0056	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (17+34.00 -L-)	Lump Sum	L.S.	
0057	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	63.8 CY		
0058	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+34.00 -L-)	Lump Sum	L.S.	
0059	8217000000-E	425	REINFORCING STEEL (BRIDGE)	11,818 LB		
0060	8364000000-E	450	HP12X53 STEEL PILES	700 LF		
0061	8387000000-E	450	PP 18 X 0.50 GALVANIZED STEEL PILES	1,050 LF		
0062	8392000000-N	450	PIPE PILE PLATES	21 EA		
0063	8393000000-N	450	PILE REDRIVES	20 EA		
0064	8503000000-E	460	CONCRETE BARRIER RAIL	435.5 LF		
0065	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	798 TON		
0066	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	887 SY		
0067	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0068	8753000000-E	430	3'-0" X 2'-3" PRESTRESSED CONC BOX BEAMS	2,391.14 LF		

1022/Dec07/Q30105.79/D322302970000/E68

Total Amount Of Bid For Entire Project :

Contract No: C201496

County: Pitt & Beaufort

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General