

County : Caldwell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (14+69.500-L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	85 CY		
0007	0199000000-E	SP	TEMPORARY SHORING	270 SF		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	45 TON		
0009	0343000000-E	310	15" SIDE DRAIN PIPE	20 LF		
0010	0453000000-E	310	*** PIPE END SECTION (15")	2 EA		
0011	0453000000-E	310	*** PIPE END SECTION (24")	1 EA		
0012	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	24 LF		
0013	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0014	0995000000-E	340	PIPE REMOVAL	36 LF		
0015	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	642 TON		
0017	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	385 TON		
0018	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	53 TON		

County : Caldwell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2000000000-N	806	RIGHT OF WAY MARKERS	30 EA		
0020	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0021	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	1 EA		
0022	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0023	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	1 EA		
0024	2556000000-E	846	SHOULDER BERM GUTTER	30 LF		
0025	3030000000-E	862	STEEL BM GUARDRAIL	137.5 LF		
0026	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0027	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0028	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0029	3649000000-E	876	RIP RAP, CLASS B	18 TON		
0030	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	240 SY		
0031	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0032	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	37.5 SF		
0033	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (F)	6 SF		
0034	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	110 LF		
0035	4102000000-N	904	SIGN ERECTION, TYPE E	6 EA		
0036	4108000000-N	904	SIGN ERECTION, TYPE F	1 EA		

County : Caldwell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	2	EA	
0038	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	11	EA	
0039	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1	EA	
0040	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	109	SF	
0041	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	192	SF	
0042	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	20	SF	
0043	4430000000-N	1130	DRUMS	20	EA	
0044	4435000000-N	1135	CONES	50	EA	
0045	4445000000-E	1145	BARRICADES (TYPE III)	48	LF	
0046	4450000000-N	1150	FLAGGER	750	HR	
0047	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2	EA	
0048	4480000000-N	1165	TMIA	2	EA	
0049	4485000000-E	1170	PORTABLE CONCRETE BARRIER	170	LF	
0050	4516000000-N	1180	SKINNY DRUM	50	EA	
0051	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	10,074	LF	
0052	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	84	LF	
0053	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS)	5,037	LF	
0054	4847140000-E	1205	POLYUREA PAVEMENT MARKING LINES (24", *****) (STANDARD GLASS BEADS)	42	LF	

County : Caldwell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	82	EA	
0056	6000000000-E	1605	TEMPORARY SILT FENCE	750	LF	
0057	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	105	TON	
0058	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	155	TON	
0059	6012000000-E	1610	SEDIMENT CONTROL STONE	60	TON	
0060	6015000000-E	1615	TEMPORARY MULCHING	2	ACR	
0061	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0062	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5	TON	
0063	6029000000-E	SP	SAFETY FENCE	200	LF	
0064	6030000000-E	1630	SILT EXCAVATION	665	CY	
0065	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,000	SY	
0066	6037000000-E	SP	COIR FIBER MAT	40	SY	
0067	6042000000-E	1632	1/4" HARDWARE CLOTH	40	LF	
0068	6071030000-E	SP	COIR FIBER BAFFLES	170	LF	
0069	6071050000-E	SP	*** SKIMMER (1-1/2")	5	EA	
0070	6071050000-E	SP	*** SKIMMER (2")	1	EA	
0071	6084000000-E	1660	SEEDING & MULCHING	2	ACR	
0072	6087000000-E	1660	MOWING	1.5	ACR	
0073	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	

County : Caldwell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0075	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0076	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5	TON	
0077	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
0078	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	
0079	6123000000-E	1670	REFORESTATION	0.1	ACR	

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

0080	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	208	LF	
------	--------------	-----	---------------------------------	-----	----	--

0081	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	172	LF	
------	--------------	-----	---------------------------------	-----	----	--

*** OR ***

0082	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	116	LF	
------	--------------	-----	---------------------------------	-----	----	--

0083	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	208	LF	
------	--------------	----	-------------------------------	-----	----	--

0084	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	56	LF	
------	--------------	----	-------------------------------	----	----	--

*** OR ***

0085	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	116	LF	
------	--------------	-----	---------------------------------	-----	----	--

0086	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (15")	208	LF	
------	--------------	----	-------------------------------------------------------------------	-----	----	--

0087	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (24")	56	LF	
------	--------------	----	-------------------------------------------------------------------	----	----	--

***** END SCHEDULE AA *****

County : Caldwell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0088	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+69.50-L-)	Lump Sum	L.S.	
0089	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (14+69.50-L-)	Lump Sum	L.S.	
0090	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	3,270 SF		
0091	8161000000-E	420	GROOVING BRIDGE FLOORS	3,089 SF		
0092	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	27.2 CY		
0093	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+69.50-L-)	Lump Sum	L.S.	
0094	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,014 LB		
0095	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	128,700 LS		
0096	8364000000-E	450	HP12X53 STEEL PILES	240 LF		
0097	8503000000-E	460	CONCRETE BARRIER RAIL	236.67 LF		
0098	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	202 TON		
0099	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	223 SY		
0100	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

0904/Dec05/Q165560.72/D411181870000/E100

Total Amount Of Bid For Entire Project :

Contract No: C201602

County: Caldwell

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General