

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (14+76.00 -L-)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	10 TON		
0009	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	52 LF		
0010	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	24 LF		
0011	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0012	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	120 TON		
0013	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	70 TON		
0014	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	10 TON		
0015	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0016	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0017	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0018	2556000000-E	846	SHOULDER BERM GUTTER	30 LF		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	4 EA		
0020	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0021	3649000000-E	876	RIP RAP, CLASS B	19 TON		
0022	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	155 SY		
0023	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	269 SF		
0024	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	57 SF		
0025	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0026	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	2,880 LF		
0027	6000000000-E	1605	TEMPORARY SILT FENCE	510 LF		
0028	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0029	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	100 TON		
0030	6012000000-E	1610	SEDIMENT CONTROL STONE	40 TON		
0031	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0032	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0033	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
0034	6029000000-E	SP	SAFETY FENCE	165 LF		
0035	6030000000-E	1630	SILT EXCAVATION	145 CY		
0036	6036000000-E	1631	MATTING FOR EROSION CONTROL	205 SY		
0037	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	77 SY		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
0039	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0040	6087000000-E	1660	MOWING	0.5 ACR		
0041	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0042	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0043	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0044	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25 TON		
0045	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0046	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0047	6123000000-E	1670	REFORESTATION	0.1 ACR		
STRUCTURE ITEMS						
0048	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+76.00-L-)	Lump Sum	L.S.	
0049	8096000000-E	SP	PILE EXCAVATION IN SOIL	90 LF		
0050	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	30 LF		
0051	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (14+76.00-L-)	Lump Sum	L.S.	
0052	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	2,357 SF		
0053	8161000000-E	420	GROOVING BRIDGE FLOORS	2,318 SF		
0054	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	28 CY		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+76.00-L-)	Lump Sum	L.S.	
0056	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,739 LB		
0057	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	372.67 LF		
0058	8364000000-E	450	HP12X53 STEEL PILES	280 LF		
0059	8503000000-E	460	CONCRETE BARRIER RAIL	186.67 LF		
0060	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	161 TON		
0061	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	178 SY		
0062	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0063	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1427/Nov30/Q17648.69/D308974100000/E63

Total Amount Of Bid For Entire Project :

Contract No: C201788

County: Durham

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General