

County : Mecklenburg, Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0000720000-N	SP	FIELD OFFICE	33 MO		
0004	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0005	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	3 ACR		
0006	0022000000-E	225	UNCLASSIFIED EXCAVATION	51,000 CY		
0007	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (124+82.50-L-)	Lump Sum	L.S.	
0008	0036000000-E	225	UNDERCUT EXCAVATION	28,500 CY		
0009	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	3,000 TON		
0010	0106000000-E	230	BORROW EXCAVATION	132,000 CY		
0011	0134000000-E	240	DRAINAGE DITCH EXCAVATION	5,500 CY		
0012	0141000000-E	240	BERM DITCH CONSTRUCTION	2,400 LF		
0013	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	15,750 SY		
0014	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	100 SY		
0015	0192000000-N	260	PROOF ROLLING	30 HR		
0016	0195000000-E	265	SELECT GRANULAR MATERIAL	10,000 CY		
0017	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	10,000 SY		
0018	0199000000-E	SP	TEMPORARY SHORING	2,161 SF		

County : Mecklenburg, Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0255000000-E	SP	GENERIC GRADING ITEM EXCAVATION, HAULING, AND DISPOSAL OF PETROLEUM CONTAMINATED SOIL	50 TON		
002C	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	2,484 TON		
0021	0343000000-E	310	15" SIDE DRAIN PIPE	144 LF		
0022	0344000000-E	310	18" SIDE DRAIN PIPE	24 LF		
0023	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	10,992 LF		
0024	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	2,224 LF		
002E	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	2,090 LF		
002E	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	704 LF		
0027	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	248 LF		
002E	0408000000-E	310	54" RC PIPE CULVERTS, CLASS III	164 LF		
002E	0420000000-E	310	66" RC PIPE CULVERTS, CLASS III	16 LF		
003C	0426000000-E	310	72" RC PIPE CULVERTS, CLASS III	148 LF		
0031	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	180 LF		
0032	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	56 LF		
0033	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	24 LF		
0034	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	3 EA		

County : Mecklenburg, Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	2 EA		
003E	0808000000-E	310	24" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	1 EA		
0037	0995000000-E	340	PIPE REMOVAL	2,720 LF		
003E	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
003E	1044000000-E	501	LIME TREATED SOIL (SLURRY METHOD)	65,580 SY		
004C	1066000000-E	501	LIME FOR LIME TREATED SOIL	660 TON		
0041	1121000000-E	520	AGGREGATE BASE COURSE	1,000 TON		
0042	1176000000-E	542	SOIL CEMENT BASE	21,860 SY		
004E	1187000000-E	542	PORTLAND CEMENT FOR SOIL CE- MENT BASE	602 TON		
0044	1198000000-E	SP	AGGREGATE FOR SOIL CEMENT BASE	40 TON		
004E	1209000000-E	543	ASPHALT CURING SEAL	13,290 GAL		
004E	1330000000-E	607	INCIDENTAL MILLING	1,200 SY		
0047	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.OB	3,420 TON		
004E	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.OC	31,710 TON		
004E	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.OB	3,150 TON		
005C	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.OC	29,400 TON		
0051	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	3,150 TON		
0052	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	31,500 TON		

County : Mecklenburg, Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	3,085 TON		
0054	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	1,890 TON		
0055	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	1,050 TON		
0056	2022000000-E	815	SUBDRAIN EXCAVATION	336 CY		
0057	2033000000-E	815	SUBDRAIN FINE AGGREGATE	168 CY		
0058	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
0059	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30 EA		
006C	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0061	2132000000-N	816	CONCRETE PAD FOR SHOULDER DRAIN PIPE OUTLET	2 EA		
0062	2143000000-E	818	BLOTTING SAND	20 TON		
0063	2190000000-N	828	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	12 EA		
0064	2209000000-E	838	ENDWALLS	4 CY		
0065	2220000000-E	838	REINFORCED ENDWALLS	12.1 CY		
0066	2253000000-E	840	PIPE COLLARS	3.009 CY		
0067	2264000000-E	840	PIPE PLUGS	1.573 CY		
0068	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	202 EA		
0069	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	9.303 CY		
007C	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	86 LF		

County : Mecklenburg, Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	2352000000-N	840	FRAME WITH GRATE, STD 840.**** (840.16)	27 EA		
0072	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	7 EA		
0073	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	5 EA		
0074	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	39 EA		
007E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	60 EA		
007E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	62 EA		
0077	2396000000-N	840	FRAME WITH COVER, STD 840.54	2 EA		
007E	2535000000-E	846	***X *** CONCRETE CURB (8" X 18")	230 LF		
007E	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	21,900 LF		
008C	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	37,080 LF		
0081	2591000000-E	848	4" CONCRETE SIDEWALK	19,090 SY		
0082	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	70 EA		
0083	2612000000-E	848	6" CONCRETE DRIVEWAY	380 SY		
0084	2619000000-E	850	4" CONCRETE PAVED DITCH	70 SY		
008E	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	6,020 SY		
008E	3030000000-E	862	STEEL BM GUARDRAIL	1,712.5 LF		
0087	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	5 EA		

County : Mecklenburg, Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	2	EA	
008E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	6	EA	
009C	3360000000-E	863	REMOVE EXISTING GUARDRAIL	860	LF	
0091	3524000000-E	SP	VINYL COATED CHAIN LINK FENCE, *** FABRIC (60")	410	LF	
0092	3539000000-E	866	METAL LINE POSTS FOR *** CHAIN LINK FENCE (60")	34	EA	
009E	3545000000-E	866	METAL TERMINAL POSTS FOR *** CHAIN LINK FENCE (60")	2	EA	
0094	3628000000-E	876	RIP RAP, CLASS I	130	TON	
009E	3649000000-E	876	RIP RAP, CLASS B	110	TON	
009E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	4,030	SY	
0097	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	7	EA	
009E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	3,561	LF	
009E	4096000000-N	904	SIGN ERECTION, TYPE D	7	EA	
010C	4102000000-N	904	SIGN ERECTION, TYPE E	195	EA	
0101	4108000000-N	904	SIGN ERECTION, TYPE F	19	EA	
0102	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	11	EA	
010E	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	5	EA	

County : Mecklenburg, Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0104	4152000000-N	907	DISPOSAL OF SIGN SYSTEM, STEEL BEAM	1	EA	
0105	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	96	EA	
0106	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	16	EA	
0107	4238000000-N	907	DISPOSAL OF SIGN, D, E OR F	1	EA	
0108	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	2,012	SF	
0109	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	928	SF	
011C	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	200	SF	
0111	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2	EA	
0112	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	5	EA	
0113	4430000000-N	1130	DRUMS	700	EA	
0114	4435000000-N	1135	CONES	140	EA	
0115	4445000000-E	1145	BARRICADES (TYPE III)	480	LF	
0116	4450000000-N	1150	FLAGGER	7,200	HR	
0117	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4	EA	
0118	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	2	EA	
0119	4480000000-N	1165	TMIA	2	EA	
012C	4485000000-E	1170	PORTABLE CONCRETE BARRIER	810	LF	
0121	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	110	LF	
0122	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	270	LF	

County : Mecklenburg, Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0123	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	70 LF		
0124	4506000000-E	1170	RESET PORTABLE CONCRETE BARRIER (DRAINAGE)	30 LF		
0125	4507000000-E	SP	WATER FILLED BARRIER	1,832 LF		
0126	4508000000-E	SP	RESET WATER FILLED BARRIER	4,053 LF		
0127	4510000000-N	SP	POLICE	600 HR		
0128	4516000000-N	1180	SKINNY DRUM	260 EA		
0129	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	2,070 EA		
013C	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	530 LF		
0131	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	495,000 LF		
0132	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	8,400 LF		
0133	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	4,950 LF		
0134	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	32 EA		
0135	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	600 EA		
0136	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS)	59,070 LF		
0137	4847110000-E	1205	POLYUREA PAVEMENT MARKING LINES (8", *****) (STANDARD GLASS BEADS)	7,270 LF		
0138	4847140000-E	1205	POLYUREA PAVEMENT MARKING LINES (24", *****) (STANDARD GLASS BEADS)	1,340 LF		

County : Mecklenburg, Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0139	4847200000-N	1205	POLYUREA PAVEMENT MARKING CHARACTER (*****) (STANDARD GLASS BEADS)	36 EA		
014C	4847220000-N	1205	POLYUREA PAVEMENT MARKING SYMBOL (*****) (STANDARD GLASS BEADS)	248 EA		
0141	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	6,600 LF		
0142	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	1,050 LF		
0143	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	450 LF		
0144	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	42 EA		
014E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	1,495 EA		
014E	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0147	5325600000-E	1510	6" WATER LINE	35 LF		
014E	5325800000-E	1510	8" WATER LINE	142 LF		
0149	5326200000-E	1510	12" WATER LINE	2,212 LF		
015C	5326600000-E	1510	16" WATER LINE	7,643 LF		
0151	5327400000-E	1510	24" WATER LINE	1,847 LF		
0152	5546000000-E	1515	8" VALVE	2 EA		
0153	5558000000-E	1515	12" VALVE	3 EA		
0154	5558600000-E	1515	16" VALVE	7 EA		
015E	5559400000-E	1515	24" VALVE	2 EA		
015E	5572200000-E	1515	12" TAPPING VALVE	5 EA		

County : Mecklenburg, Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0157	5573400000-E	1515	24" TAPPING VALVE	7 EA		
0158	5606000000-E	1515	2" BLOW OFF	2 EA		
0159	5648000000-N	1515	RELOCATE WATER METER	21 EA		
016C	5672000000-N	1515	RELOCATE FIRE HYDRANT	11 EA		
0161	5679000000-E	1515	12" LINE STOP	5 EA		
0162	5679200000-E	1515	16" LINE STOP	3 EA		
0163	5679600000-E	1515	24" LINE STOP	7 EA		
0164	5709100000-E	1520	2" FORCE MAIN SEWER	529 LF		
0165	5775000000-E	1525	4' DIA UTILITY MANHOLE	2 EA		
016E	5804000000-E	1530	ABANDON 12" UTILITY PIPE	1,955 LF		
0167	5810000000-E	1530	ABANDON 16" UTILITY PIPE	65 LF		
016E	5813000000-E	1530	ABANDON 24" UTILITY PIPE	1,295 LF		
0169	5871700000-E	1550	TRENCHLESS INSTALLATION OF 12" IN SOIL	55 LF		
017C	5882000000-N	SP	GENERIC UTILITY ITEM ADJUSTMENT OF WATER VAULT	1 EA		
0171	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE WATER VAULT	1 EA		
0172	6000000000-E	1605	TEMPORARY SILT FENCE	15,500 LF		
0173	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	1,975 TON		
0174	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	3,340 TON		
017E	6012000000-E	1610	SEDIMENT CONTROL STONE	4,570 TON		

County : Mecklenburg, Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0176	6015000000-E	1615	TEMPORARY MULCHING	38.5	ACR	
0177	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	1,400	LB	
017E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	5.5	TON	
017E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	950	LF	
018C	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	18	EA	
0181	6029000000-E	SP	SAFETY FENCE	400	LF	
0182	6030000000-E	1630	SILT EXCAVATION	24,000	CY	
0183	6036000000-E	1631	MATTING FOR EROSION CONTROL	14,650	SY	
0184	6037000000-E	SP	COIR FIBER MAT	250	SY	
018E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,220	SY	
018E	6042000000-E	1632	1/4" HARDWARE CLOTH	5,400	LF	
0187	6070000000-N	SP	SPECIAL STILLING BASINS	24	EA	
018E	6071030000-E	SP	COIR FIBER BAFFLES	2,500	LF	
018E	6071050000-E	SP	*** SKIMMER (1-1/2")	17	EA	
019C	6071050000-E	SP	*** SKIMMER (2")	11	EA	
0191	6071050000-E	SP	*** SKIMMER (2-1/2")	5	EA	
0192	6071050000-E	SP	*** SKIMMER (3")	1	EA	
0193	6084000000-E	1660	SEEDING & MULCHING	44	ACR	

County : Mecklenburg, Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0194	6087000000-E	1660	MOWING	23	ACR	
0195	6090000000-E	1661	SEED FOR REPAIR SEEDING	350	LB	
0196	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.75	TON	
0197	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	925	LB	
0198	6108000000-E	1665	FERTILIZER TOPDRESSING	32.75	TON	
0199	6111000000-E	SP	IMPERVIOUS DIKE	375	LF	
0200	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
0201	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	36	EA	
0202	7000000000-E	1705	PEDESTRIAN SIGNAL HEAD (***, ** SECTION) (16", 1 SECTION W/COUNTDOWN)	8	EA	
0203	7060000000-E	1705	SIGNAL CABLE	7,770	LF	
0204	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	30	EA	
0205	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	2	EA	
0206	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	7	EA	
0207	7228000000-N	SP	RELOCATE EXISTING VEHICLE SIG- NAL HEAD	10	EA	
0208	7252000000-E	1710	MESSENGER CABLE (1/4")	16,880	LF	
0209	7264000000-E	1710	MESSENGER CABLE (3/8")	2,180	LF	
0210	7279000000-E	1715	TRACER WIRE	1,460	LF	
0211	7288000000-E	1715	PAVED TRENCHING (***** (1 CONDUIT, 2")	190	LF	

County : Mecklenburg, Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0212	7300000000-E	1715	UNPAVED TRENCHING (*****) (1 CONDUIT, 2")	3,455 LF		
0213	7301000000-E	1715	DIRECTIONAL DRILL (*****) (1 CONDUIT, 2")	245 LF		
0214	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	21 EA		
0215	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEAVY DUTY)	7 EA		
0216	7360000000-N	1720	WOOD POLE	12 EA		
0217	7372000000-N	1721	GUY ASSEMBLY	50 EA		
0218	7408000000-E	1722	1" RISER WITH WEATHERHEAD	3 EA		
0219	7420000000-E	1722	2" RISER WITH WEATHERHEAD	16 EA		
0220	7432000000-E	1722	2" RISER WITH HEAT SHRINK TUBING	4 EA		
0221	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	10,960 LF		
0222	7456000000-E	1726	LEAD-IN CABLE (*****) (18-2)	14,960 LF		
0223	7456000000-E	1726	LEAD-IN CABLE (*****) (18-4)	500 LF		
0224	7516000000-E	1730	COMMUNICATIONS CABLE (**FIBER) (24)	20,075 LF		
0225	7528000000-E	1730	DROP CABLE	905 LF		
0226	7540000000-N	1731	SPLICE ENCLOSURE	8 EA		
0227	7552000000-N	1731	INTERCONNECT CENTER	3 EA		
0228	7564000000-N	1732	FIBER-OPTIC TRANSCEIVER, DROP & REPEAT	3 EA		
0229	7566000000-N	1733	DELINEATOR MARKER	7 EA		

County : Mecklenburg, Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
023C	7574000000-N	SP	FURNISH FIBER-OPTIC TRANSCEIVER	1 EA		
0231	7575000000-N	SP	FIBER-OPTIC TRAINING	Lump Sum	L.S.	
0232	7636000000-N	1745	SIGN FOR SIGNALS	10 EA		
0233	7684000000-N	1750	SIGNAL CABINET FOUNDATION	3 EA		
0234	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	3 EA		
023E	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	31 EA		
023E	7901000000-N	1753	CABINET BASE EXTENDER	3 EA		
0237	7980000000-N	SP	GENERIC SIGNAL ITEM DAIL-UP MODEM	1 EA		
023E	7980000000-N	SP	GENERIC SIGNAL ITEM TELEPHONE DEMARCATION ASSEMBLY	1 EA		
WALL ITEMS						
023E	8436000000-E	453	GRAVITY RETAINING WALLS	3,920 SF		
STRUCTURE ITEMS						
024C	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (124+82.50 -L)	Lump Sum	L.S.	
0241	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	115.4 LF		
0242	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	56 LF		
0243	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	104.1 LF		

County : Mecklenburg, Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0244	8113000000-N	SP	SID INSPECTION	2 EA		
0245	8114000000-N	SP	SPT TESTING	2 EA		
0246	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0247	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	645 CY		
0248	8156000000-E	SP	CONCRETE WEARING SURFACE	7,495 SF		
0249	8161000000-E	420	GROOVING BRIDGE FLOORS	10,686 SF		
0250	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	83.1 CY		
0251	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	190.8 CY		
0252	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (124+82.50 -L-)	Lump Sum	L.S.	
0253	8217000000-E	425	REINFORCING STEEL (BRIDGE)	45,011 LB		
0254	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	2,487 LB		
0255	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	5,864 LB		
0256	8364000000-E	450	HP12X53 STEEL PILES	840 LF		
0257	8482000000-E	460	THREE BAR METAL RAIL	189.39 LF		
0258	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	776 TON		
0259	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	860 SY		
0260	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0261	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

County : Mecklenburg, Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0262	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	3,070 LF		

0918/Dec17/Q1458573.175/D1166153700000/E262 Total Amount Of Bid For Entire Project :

Contract No: C201622

County: Mecklenburg & Union

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General